INPUT/OUTPUT SUMMARY

SYSTEM, APPARATUS, OR AREA POINT DESCRIPTION	INPUTS: ANALOG MEASURED: TEMPERATURE	PRESSURE	KW	AIR FLOW	WATER FLOW	CO2/IAQ	RPM'S	AMPS	SECONDARY ADJUST	ANALOG CALC.: ENTHALPY	RUN TIME	EFFICIENCY	INPUTS: BINARY: STATUS	FLOW	PRESSURE	ALARM	OVER-RIDE	OUTPUTS: DIGITAL: OFF-ON	OFF-LO-HI	ON-OFF CONTROL	OUTPUTS: ANALOG: DAMPER POSITION	VALVE POSITION	SETPOINT ADJUST	SYSTEM FEATURES: ALARMS: HI ANALOG	LO ANALOG	LO BINARY	PROOF	PROGRAMS: TIME SCHEDULING	DUTY CYCLING	START/STOP OPT.	SEQUENCING	SMOKE CONTROL	ALARM INSTRUCT.	MAIN. WK. ORD.	GENERAL: COLOR GRAPHIC	SUPPLEMENTAL NOTES
RTU'S																																					
Supply Fan							X						X					X						X				X	X					X		
Gas Valve (Heat)													X									X			X											
Heating Coil Disch. Temp	X																																			
Cooling Coil Disch. Temp	X																																			
Power Exhaust Fan													X					X						X												RTU-LP-23 and 24 only
Compressor #1													X					X						X												
Compressor #2													X					X						X												RTU-LP-23 and 24 only
Supply Temp	X																							X												
Return Temp	X																																			
Space Humidity		X																																		Monitor Only
Return Damper																						X														
Smoke Detector														X																						
Filter Status													X																							
Over-ride																X																				
Setpoint Adjust									X																											
Condensate Flow Switch			X																					X												
Space Temp	X																							X												
Fans																												X						X		
Toilet Fans																		X																		
VAV Diffuser																								X				X						X		
Volume Damper																						X														
Space Temp	X																																			
Misc. Points																																		X		
OA Temp	X									X																										
Dew Point	X									X																										
Ductless Split	X																							X												
Fire Alarm Status									X																X											

GENERAL NOTE:
INPUT/OUTPUT SUMMARY IS A GENERAL LIST OF CONTROL POINTS REQUIRED FOR THE OPERATION OF THE MECHANICAL SYSTEM. IN ADDITION TO CONTROL POINTS INDICATED, THE CONTROLS CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING ADDITIONAL POINTS AS REQUIRED FOR OPERATION OF THE MECHANICAL SYSTEM AS SPECIFIED AND OUTLINED IN THE SEQUENCE OF OPERATION, CONTROL DIAGRAMS AND TO COMPLY WITH THE SPECIFICATIONS.

CONTROLS AND SEQUENCE OF OPERATION

BAS INSTRUCTION

FULLY INTEGRATE NEW EQUIPMENT INTO EXISTING CAMPUS ALLERTON BAS. BAS GRAPHICS SHALL BE UPDATED TO INCLUDE ALL NEW EQUIPMENT AND EQUIPMENT LOCATIONS. ALL CONTROLS POINTS SHALL MATCH EXISTING SYSTEM SETUP.

CONSTANT VOLUME ROOFTOP UNIT

ROOFTOP UNITS SHALL BE STARTED AND STOPPED ON A PROGRAMMED BASIS BY THE DDC CONTROL SYSTEM. UNIT SHALL BE PROVIDED WITH A WALL MOUNTED DDC SENSOR (BY BAS VENDOR) FOR SPACE TEMPERATURE CONTROL. WHILE IN THE OCCUPIED MODE, THE SUPPLY FAN SHALL OPERATE CONTINUOUSLY TO PROVIDE VENTILATION AIR TO THE SPACE. DX COMPRESSORS SHALL CYCLE AS REQUIRED TO MAINTAIN SPACE TEMPERATURE. UPON A DROP IN SPACE TEMPERATURE, UNIT SHALL ACTIVATE 1ST STAGE OF GAS HEAT TO MAINTAIN SPACE SETPOINT. UPON A FURTHER DROP IN SPACE TEMPERATURE, THE 2ND STAGE OF GAS HEAT SHALL BE ENERGIZED (LP-23 AND 24 ONLY).

WHILE IN THE UNOCCUPIED MODE, THE UNIT SUPPLY FAN, DX COOLING, AND HEATING SHALL CYCLE AS NOTED ABOVE TO MAINTAIN SETBACK TEMPERATURES. IF ACTIVATED DURING THE UNOCCUPIED MODE, THE UNIT SHALL RUN FOR A MINIMUM OF TEN MINUTES AND SHALL NOT BE ALLOWED TO RESTART FOR A MINIMUM OF TWENTY MINUTES FOLLOWING SHUT-DOWN.

ROOFTOP UNIT FACTORY MOUNTED CONTROLS SHALL PROVIDE ECONOMIZER OPERATION TO PROVIDE "FREE COOLING" WHEN OUTDOOR AIR CONDITIONS ALLOW. UPON BAS DETERMINATION THAT OUTSIDE AIR ENTHALPY IS BELOW RETURN AIR ENTHALPY IN COOLING MODE, THE OUTSIDE AIR AND RETURN AIR DAMPERS SHALL MODULATE TO MAINTAIN UNIT DISCHARGE AIR TEMPERATURE. IF "ECONOMIZER" CONTROL IS INSUFFICIENT TO MAINTAIN DISCHARGE AIR TEMPERATURE, THE UNIT COOLING CYCLE SHALL FUNCTION AS OUTLINED ABOVE. UPON A DROP IN DISCHARGE AIR TEMPERATURE BELOW SETPOINT, THE OUTSIDE AIR DAMPER SHALL MODULATE CLOSED UNTIL THE MINIMUM OUTSIDE AIR POSITION IS REACHED. WITH OUTSIDE AIR DAMPER AT MINIMUM POSITION AND A CONTINUED DROP IN UNIT SUPPLY AIR TEMPERATURE BELOW SETPOINT THE UNIT HEATING CYCLE SHALL FUNCTION AS OUTLINED ABOVE. POWER EXHAUST SHALL ACTIVATE AS REQUIRED TO MAINTAIN BUILDING PRESSURIZATION AS OUTSIDE AIR DAMPERS ARE OPENED FOR ECONOMIZER OPERATION.

PROVIDE EACH UNIT WITH A IONIZATION TYPE SMOKE DETECTOR, INSTALLED IN THE RETURN DUCTWORK, SHUTTING DOWN THE UNIT UPON ACTIVATION. SMOKE DETECTOR SHALL BE SUPPLIED AND WIRED FOR INTERFACE WITH FIRE ALARM SYSTEM AND UNIT SHUTDOWN BY THE ELECTRICAL CONTRACTOR. SMOKE DETECTOR SHALL BE INSTALLED IN THE RETURN DUCT BY THE MECHANICAL CONTRACTOR.

TOILET EXHAUST FANS
CENTRAL BAS SHALL OPERATE EXHAUST FANS ON A PROGRAMMED SCHEDULE.

IT / DATA ROOMS:
IT / DATA ROOM IS PROVIDED WITH A DUCTLESS SPLIT SYSTEM UNIT. DUCTLESS SPLIT SYSTEM UNIT SHALL BE PROVIDED WITH STAND ALONE CONTROLS, ELECTRONIC 7-DAY PROGRAMMABLE THERMOSTATS SEPARATE FROM THE CENTRAL DDC SYSTEM. HOWEVER, THE BAS SHALL STILL MONITOR SYSTEM STATUS AND SHALL ALSO MONITOR ROOM TEMPERATURE. THE DUCTLESS SPLIT UNIT SHALL PROVIDE COOLING ON A CONTINUOUS BASIS. SUPPLY FAN AND COOLING CYCLE SHALL CYCLE WITH A CALL FOR COOLING TO MAINTAIN ROOM TEMPERATURE SETPOINT OF 72° F. THE BAS SHALL ACTIVATE AN ALARM IF THE ROOM TEMPERATURE RISES ABOVE 78° F.

NOTES:
1. ALL CONTROL SETPOINTS SHALL BE ADJUSTABLE, INDICATED TEMPERATURE SETPOINTS SHOULD BE USED FOR ORIGINAL SYSTEM SET-UP. ANY CHANGES IN SETPOINT SETTINGS REQUIRED FOR INTENDED SYSTEM OPERATION SHALL BE NOTED ON AS-BUILT DRAWINGS.
2. IONIZATION TYPE DUCT SMOKE DETECTORS SHALL BE FURNISHED AND WIRED TO THE FIRE ALARM SYSTEM AND FOR UNIT SHUT-DOWN BY THE ELECTRICAL CONTRACTOR. MECHANICAL CONTRACTOR SHALL INSTALL DETECTOR IN THE RETURN DUCT PRIOR TO THE OUTSIDE AIR CONNECTION.
3. ELECTRICAL CONTRACTOR SHALL PROVIDE A DEDICATED 120V CIRCUIT IN A J-BOX FOR CONTROL POWER. CONTROLS CONTRACTOR SHALL EXTEND 120V POWER FROM J-BOX TO CONTROL PANELS, DAMPER ACTUATORS, TRANSFORMERS, ETC. AS REQUIRED FOR OPERATION OF CONTROL SYSTEM.

Order Plans @ WWW.LDILLC.COM

adwarchitects
environmentsforlife
architecture planning interiors
6 coliseum centre,
2815 coliseum drive, suite 500
charlotte, north carolina 28217
t| 704 379 1919
f| 704 379 1920
www.adwarchitects.com

optima engineering
1927 South Tryon St., Suite 300, Charlotte NC 28203
150 Fayetteville St., Suite 520, Raleigh, NC 27601
Phone: 704-338-1292 • www.optimaengineering.com

SCO #16-15889-02A

RICHMOND COMMUNITY COLLEGE

LINDSEY-PETRIS CAFETERIA / DINING ADDITION VOL.1

BID DOCUMENTS

MECHANICAL CONTROLS POINTS AND SEQUENCE OF OPERATIONS

DATE 4-5-2019
PROJECT NO 16063

REVISIONS
NO DATE DESCRIPTION:

THIS DRAWING IS THE PROPERTY OF ADW ARCHITECTS, PA AND SHALL NOT BE REPRODUCED OR COPIED IN WHOLE OR IN PART. IT SHALL NOT BE USED ON ANY OTHER PROJECT OR GIVEN TO ANY OTHER COMPANY OR AGENCY WITHOUT THE CONSENT OF ADW ARCHITECTS, PA.

NORTH CAROLINA PROFESSIONAL 17228 ENGINEER RONALD V. ALMAND 04/05/19
SEAL

SHEET NUMBER 4 OF 6
OPTIMA # 17-2017

M004

THIS DRAWING IS AN INSTRUMENT OF SERVICE. THE DRAWING AND THE INFORMATION THEREON IS THE PROPERTY OF OPTIMA ENGINEERING, P.A. ANY REPRODUCTION, ALTERATION, OR USE FOR OTHER THAN THE INTENDED PROJECT, WITHOUT THE WRITTEN CONSENT OF OPTIMA ENGINEERING, P.A. IS EXPRESSLY FORBIDDEN. COPYRIGHT © OPTIMA ENGINEERING P.A. 2018, ALL RIGHTS RESERVED.