



**GENERAL NOTES**

- REFER TO K-SHEETS FOR ADDITIONAL LOCATION INFORMATION.
- ALL CONDUIT ON THIS SHEET FURNISHED AND INSTALLED BY BATTERY PACKS ARE TO BE DIRECT WIRE. NO EXPOSED WIRING IS PERMITTED. ELECTRICAL CONTRACTOR.
- ALL P.O.S. CONDUITS FROM POS OUTLETS SHALL RUN UP IN WALLS AND OVERHEAD TO OFFICE, BY ELECTRICAL CONTRACTOR.
- ALL EMPTY CONDUIT TO HAVE NYLON PULLSTRINGS INSTALLED.
- POS SYSTEM AND WIRING BY OWNER.
- ROUTE ALL EXPOSED CONDUIT PARALLEL AND PERPENDICULAR TO TRUSSES BETWEEN BOTTOM OF TOP CHORD AND TOP OF BOTTOM CHORD AS REQUIRED. PAINT AS DIRECTED.
- DUPLEX AND DOUBLE DUPLEX RECEPTACLES FOR P.O.S. SYSTEM (ISOLATED GROUND RECEPTACLES) SHALL NOT SHARE CONDUIT. ANY OTHER "NORMAL POWER" DEVICES. ISOLATED GROUND RECEPTACLES SHALL BE "ORANGE" IN COLOR.
- P.O.S. CONTACTS: POS SYSTEM: MICROS (415) 442-0819, ZIMMERMAN POS WIRING, JACIFIC TECHNOLOGY SOLUTIONS, (949) 851-6129, MKS WICKEN, OR ADAM KRANSON

**CAMERA LAYOUT SCHEDULE**

CAM. NUMBER	LOCATION
1	ENTRY
2	DINING
3	DINING #1
4	DINING #2
5	DINING #3
6	DINING #3
7	SERVICE AREA
8	GALLEY
9	SERVICE AREA
10	GALLEY
11	DELIVERY DOOR
12	KITCHEN STORAGE
13	WALK-IN COOLER
14	WALK-IN FREEZER
15	OFFICE

**FIRE ALARM GENERAL NOTE**

- AN APPROVED FIRE ALARM SYSTEM MONITORED BY A LISTED CENTRAL STATION, REMOTE STATION OR PROPRIETARY STATION SHALL BE PROVIDED, DESIGNED PER NFPA STD. 72 (2005). PRIOR TO INSTALLATION A LICENSED CONTRACTOR SHALL SUBMIT TO THE FIRE DEPARTMENT, ONE (1) SET OF MANUFACTURER'S CUT SHEETS AND STATE FIRE MARSHALL LISTING SHEETS FOR EACH DEVICE, THREE (3) SETS OF SHOP DRAWINGS, A COMPLETED PERMIT APPLICATION, AND APPLICABLE FEES FOR REVIEW. ELECTRICAL CONTRACTOR SHALL INSTALL CONDUIT AND OUTLET BOXES. WIRING AND DEVICES SHALL BE BY FIRE ALARM SYSTEM CONTRACTOR. FIRE ALARM SYSTEM CONTRACTOR SHALL SUBMIT FINAL FIRE ALARM SYSTEM SHOP DRAWINGS TO LOCAL FIRE DEPARTMENT PLAN CHECK FOR APPROVAL PRIOR TO INSTALLATION. PROVIDE DOCUMENTATION TO FIRE INSPECTOR VERIFYING SERVICE CONTRACTS OF FIRE ALARM SYSTEM.

**KEYED NOTES**

- PROVIDE 1" CONDUIT TO HUB WITH (3) CAT. 5 CABLE FROM EACH POS DATA OUTLET LOCATION. REFER TO CORRESPONDING CALL OUT
- PROVIDE 6"x8" PULLBOX FOR RECEPTION AND AUDIO ASSEM. LOCATE AT AUDIO SHELF.
- PROVIDE 4/5 JUNCTION BOX WITH 1/2" CONDUIT TO ABOVE CEILING SPACE FOR RECESSED FIRE SUPPRESSION SYSTEM.
- 12"x12"x4" POS CAB. E.C. TO TERMINATE ALL CAT-5 CABLE FOR POS EQUIPMENT.
- PROVIDE CAT 5 WIRING 6" BELOW CEILING FOR WIRELESS ROUTER.
- JUNCTION BOX WITH 1" C.O. TO CEILING SPACE FOR MUSIC CONTROL.
- RECEPTACLE TO BE MOUNTED ABOVE FINISHED CEILING AT POLE LOCATIONS AS INDICATED. HOOD AND KITCHEN EQUIPMENT VENDORS. VERIFY EXACT LOCATION AND REQUIREMENTS WITH HOOD AND KITCHEN EQUIPMENT PROVIDERS PRIOR TO ROUGH-IN.
- CEILING MOUNTED SPEAKER
- MOUNT AT 78" A.F.F. VERIFY EXACT LOCATION WITH KDS PROVIDER PRIOR TO ROUGH-IN.
- CONTRACTOR SHALL PROVIDE J-BOX FOR REMOTE/TEST/ALARM SWITCH FOR DUCT MOUNTED SMOKE DETECTORS FOR RTU-1 THRU 3. SWITCHES SHALL BE PROVIDED WITH AUDIBLE/VISUAL ALARM STATUS, KEYED TEST SWITCH AND RESET SWITCH. COORDINATE REQUIREMENTS WITH DUCT DETECTOR MANUFACTURER AND PROVIDE AS NECESSARY PRIOR TO ROUGH-IN. VERIFY EXACT MOUNTING LOCATION WITH OWNER AND ARCHITECT PRIOR TO ROUGH-IN.

- VERIFY AND FIELD COORDINATE ALL EQUIPMENT ROUGH-IN REQUIREMENTS.
- REFER TO K-SHEETS FOR ADDITIONAL SOUND AND SECURITY SYSTEM CONDUIT REQUIREMENTS.
- VERIFY EXACT LOCATION AND REQUIREMENTS OF DUCT MOUNTED SMOKE DETECTOR WITH MECHANICAL CONTRACTOR AND MANUFACTURER.
- VERIFY LOCATION OF TELEVISION AND DEDICATED OUTLET WITH ARCHITECT AND OWNER PRIOR TO ROUGH-IN.

PROJECT NO.:  
DRAWN BY: TBA  
CHECKED BY: TBA  
ISSUED DATE: 05.07.19

ISSUED REVISIONS:

NO.	DATE	DESCRIPTION