



- GENERAL NOTES:**
- REFER TO DRAWING E3 FOR ROOF PLAN AND ADDITIONAL ELECTRICAL REQUIREMENTS AND EQUIPMENT CONNECTIONS.
 - REFER TO DRAWING E6 FOR ADDITIONAL ELECTRICAL ROOM INFO.
 - COORDINATE CONDUIT REQUIREMENTS AND LOCATIONS WITH THE SITE AND PETROLEUM CONTRACTORS.
 - INSTALL CONDUITS AND CONDUITS IN ACCORDANCE WITH THE REQUIREMENTS FOR THE PADS, RISERS AND DOWNING.
 - THIS PROJECT HAS A LARGE QUANTITY OF UNDERGROUND CONDUITS. COORDINATE WITH PLUMBING AND STRUCTURAL CONTRACTORS TO AVOID UNDERGROUND SPACE CONFLICTS. PROVIDE SEALS AT THE POINTS OF UNDERGROUND CONDUITS TO AVOID SPACE CONFLICTS WITH OTHER DISCIPLINES.
 - THE ELECTRICAL CONTRACTOR SHALL INSTALL ALL ELECTRICAL CONDUITS FROM THE STORE TO THE EDGE OF THE CONCRETE CANOPY PAD AND TANK PAD. PETROLEUM CONTRACTOR TO RUN ALL CONDUITS UNDER CANOPY PAD TO CANOPY COLUMNS AND COORDINATE THE HEIGHT OF THE SEAL OFF FITTINGS WITH THE OPENINGS PROVIDED BY THE STEEL COLUMNS. GENERAL CONTRACTOR TO CONNECT AT SEAL OFF FITTINGS IN COLUMNS FOR CONDUIT RUNS FOR LIGHTING AND INTERCOM.

- ELECTRICAL PLAN NOTES:**
- NOT USED.
 - CONDUIT TO BE RUN FROM FLOOR LOCATION TO ELECTRICAL ROOM OR CROSSWALL. FIELD COORDINATE LOCATION IN ELECTRICAL ROOM. REFER TO DRAWING E3 FOR ADDITIONAL INFORMATION.
 - THE ELECTRICAL CONTRACTOR SHALL EXTEND ALL ELECTRICAL CONDUITS FROM THE STORE TO THE EDGE OF THE CONCRETE CANOPY PAD AND TANK PAD. PETROLEUM CONTRACTOR TO RUN ALL CONDUITS UNDER CANOPY PAD TO CANOPY COLUMNS AND COORDINATE THE HEIGHT OF THE SEAL OFF FITTINGS WITH THE OPENINGS PROVIDED BY THE STEEL COLUMNS. GENERAL CONTRACTOR TO CONNECT AT SEAL OFF FITTINGS IN COLUMNS FOR CONDUIT RUNS FOR LIGHTING AND INTERCOM.
 - THE ELECTRICAL CONTRACTOR SHALL FURNISH AND INSTALL ALL CONDUITS TO THE AIR PUMP (1-1/2\"/>

CONDUIT PLAN
64 1/4" = 1'-0"

1925 Prospect Ave.
Orlando, FL 32814
P (407) 661-9100
F (407) 661-9101
www.epi.com



CLIENT NAME
WAWA
260 WEST BALTIMORE PIKE
WAWA, PENNSYLVANIA 19063

PROJECT NAME
WAWA F85FB 2019.01 STORE #5357-DOR
NW 87TH AVE. & NW 33RD ST.
DORAL, FLORIDA

SHEET TITLE
CONDUIT PLAN

No.	Revision	Description	Date
1	PRELIMINARY	PRELIMINARY	08/17/2018
2	REVISED	REVISED	08/20/2018
3	REVISED	REVISED	08/20/2018
4	REVISED	REVISED	08/20/2018
5	REVISED	REVISED	08/20/2018

PROJECT NO.	271708
DATE	08-20-2018
DRAWN	WAWA
CHECKED	JPM