



Order Plans @ WWW.DILine.com

**NOTES:
POS SYSTEM**

- ALL POS CONDUIT MUST BE 1" SCHEDULE 40 ETC. NO FLEX CONDUIT. CONDUIT MUST BE 1" MINIMUM O.D. SWEEP ALL TURN, NO RIGHT ANGLES!!
- ALL CONDUIT RUNS TO TERMINALS UNDER SLAB. NEED PLASTIC RINGS ON ALL CONDUIT ENDS.
- ALL CONDUIT RUNS TO LINE PRINTERS ABOVE CEILING. STUB CONDUIT TO 6" ABOVE CEILING. NEED PLASTIC RINGS ON ALL CONDUIT ENDS. 3 EA. DOUBLE GANG BOXES.
- 2 OUTLETS ON AN ISOLATED GROUND CIRCUIT WITH DEDICATED GROUND AT EACH TERMINAL AND OFFICE COMPUTER.
- ALL CABLE TO BE PROVIDED BY OWNER. INSTALLED BY OWNER USING CAT5 POS CABLE ONLY!!!!

ALL CONDUIT RUNS SHOWN ARE UNDER SLAB
ALL CONDUIT TO BE 1" MIN.

PULL STRINGS TO BE PROVIDED IN ALL CONDUIT RUNS
REFER TO SHEET FS-2.2 FOR WIRING DIAGRAM

XXXXXXXX.X
COPYRIGHT NOTICE
THIS DRAWING IS THE PROPERTY OF TEXAS ROADHOUSE INC. AND IS NOT TO BE USED FOR ANY PURPOSE OTHER THAN THE SPECIFIC PROJECT AND SITE NAMED HEREIN, AND CANNOT BE REPRODUCED IN ANY MANNER WITHOUT THE EXPRESS WRITTEN PERMISSION FROM TEXAS ROADHOUSE INC.



GASTONIA, NC
EAST FRANKLIN BLVD & ARNSTROM PARK RD
Bubba's PIZZA & BURGERS

PERMIT/BID SET
05.03.2019

DRAWN BY:	KMS
CHECKED BY:	
REVISIONS:	1

THE CONSTRUCTION DOCUMENTS SHALL CONSIST OF ALL DRAWINGS, SPECIFICATIONS, SURVEYS, SOLE REPORTS, ADDENDA AND OTHER DOCUMENTS. NONE OF THIS INFORMATION OR DRAWING SHEETS SHALL BE TAKEN SEPARATELY OR "STAND ALONE" FROM THE REMAINDER OF THE CONSTRUCTION DOCUMENTS. THE CONTRACTOR SHALL BE RESPONSIBLE TO REVIEW THE ENTIRE SET OF CONSTRUCTION DOCUMENTS TO DETERMINE THEIR PARTICULAR SCOPE OF WORK. ANY ATTENTION OF THE ARCHITECT PRIOR TO SUBMITTING A BID SHALL BE INTERPRETED AT THE SOLE DISCRETION OF THE ARCHITECT.

SHEET TITLE
POS
CONDUIT
LAYOUT

SHEET #
FS-2.1

