



NOTES:

1. LUMBER IS REQUIRED TO PROVIDE ALL MATERIALS TO MAKE FINAL CONNECTIONS BETWEEN EQUIPMENT TO WATER LINES AND DRAIN STANDOFF SUPPORTS MUST BE INSTALLED ON ALL INDIRECT CONNECTION DRAIN LINES
2. QUICK DISCONNECT GAS HOSES PROVIDED BY EQUIPMENT SUPPLIER ALL OTHER MATERIALS REQUIRED TO MAKE FINAL CONNECTIONS TO EQUIPMENT ARE THE RESPONSIBILITY OF THE PLUMBING CONTRACTOR
3. EQUIPMENT SHOWN IN THIS DRAWING IS SUBJECT TO CHANGE VERIFY ALL UTILITY CONNECTIONS WITH EQUIPMENT SUPPLIER AND CONFIRM COMPLIANCE WITH LOCAL BUILDING CODES PRIOR TO DOING ROUGH-INS
4. CONDENSATE DRAIN LINES FROM WALK-IN BOX EVAPORATORS TO FLOOR DRAINS TO BE INSTALLED BY PLUMBING CONTRACTOR
5. WHERE HOSE BIBBS ARE INDICATED, P.C. TO PROVIDE HOSE BIB W/ VACUUM BREAKER T&S 8-0736 OR EQUAL AND CONNECT TO NOTED WATER SUPPLY BEER CHASE TO BE INSTALLED IN ACCORDANCE TO ILLUSTRATION SHOWN BELOW. ANY BENDS IN CHASE MUST HAVE A MINIMUM 36" RADIUS. OPENINGS AT BOTH ENDS TO BE THOROUGHLY SEALED AND WATER TIGHT.
7. ALL MULTI-COMPARTMENT SINKS MUST BE PIPED IN COPPER TO INDIVIDUALLY DISCHARGE TO PROVIDED FLOOR SINKS WITH AIR GAP



Order Plans @

WWW.DILine.com

XXXXXXXX.X
 COPYRIGHT NOTICE
 THIS DRAWING IS THE PROPERTY OF TEXAS ROADHOUSE INC. AND IS NOT TO BE USED FOR ANY PURPOSE OTHER THAN THE SPECIFIC PROJECT AND SITE NAMED HEREIN, AND CANNOT BE REPRODUCED IN ANY MANNER WITHOUT THE EXPRESS WRITTEN PERMISSION FROM TEXAS ROADHOUSE INC.



GASTONIA, NC
 EAST FRANKLIN BLVD & ARMSTRONG PARK RD

PERMIT/BID SET
 05.03.2019
 DRAWN BY: KMS
 CHECKED BY:
 REVISIONS: 1

THE CONSTRUCTION DOCUMENTS SHALL CONSIST OF ALL DRAWINGS, SPECIFICATIONS, SURVEYS, SOIL REPORTS, ADDENDUMS AND OTHER DOCUMENTS REFERENCED HEREIN. THESE DOCUMENTS SHALL BE TAKEN SEPARATELY OR IN CONJUNCTION WITH THE REMAINDER OF THE CONSTRUCTION DOCUMENTS. THE CONTRACTOR SHALL BE RESPONSIBLE TO DETERMINE THE PARTICULAR SCOPE OF WORK, ANY DISCREPANCIES, AND TO OBTAIN NECESSARY PERMITS AND ATTENTION OF THE ARCHITECT PRIOR TO SUBMITTING A BID SHALL BE INTERPRETED AT THE SOLE DISCRETION OF THE ARCHITECT.

SHEET TITLE
 PLUMBING
 ROUGH-INS
 SHEET #
 FS-3.0