DIVISION OF WORK

DESCRIPTION	DOES NOT APPLY	EXIST. TO REMAIN	LANDLORD FURN.	LANDLORD INST.	ULTA G.C. FURN.	ULTA G.C. INST.	ULTA FURN.	ULTA INST.	REMARKS
DIVISION 01: GENERAL REQUIREMENTS									
AS APPLICABLE					●	●			REFER TO GENERAL NOTES
DIVISION 02: SITE WORK									
DEMOLITION					●	●			SLAB CUTS AS REQUIRED AND AS NOTED. SEE TRENCHING DETAIL 6/A8.3. REMOVAL OF EXISTING GYPSUM BOARD FOR IN WALL BLOCKING INSTALLATION. G.C. TO PROVIDE DEMOLITION OF ALL EXISTING TENANT ITEMS NOT BEING REUSED BY ULTA, DEMOLITION DRAWINGS FOR MORE INFORMATION.
SITE WORK		●			●	●			AS REQUIRED FOR NEW CONSTRUCTION
PLYWOOD BARRICADES					●	●			TEMPORARY - AS REQUIRED BY LL
REMOVE ALL THINSETS AND ADHESIVES					●	●			SEE DEMOLITION DRAWINGS FOR MORE INFORMATION
DIVISION 03: CONCRETE									
CONCRETE SLAB					●	●			G.C. TO PROVIDE NEW SLAB AT TRENCH AREAS, AND AS INIDCATED ON PLANS. SEE TRENCHING DETAIL 6/A8.3. G.C. TO MAKE SLAB LEVEL TO WITHIN 1/8 INCH TOLERANCE IN 10 FEET, SMOOTH, SEALED AND READY TO ACCEPT INTERIOR FLOOR FINISHES. SEE ENGINEERING SHEETS AND ADDITIONAL DETAILS FOR UNDER-SLAB DISTRIBUTION PROVIDED BY G.C. UNDER THIS PERMIT.
CONCRETE PAD AT WATER HEATER					●	●			SEE PLUMBING DRAWINGS
CONCRETE RECEIVING PAD/LOADING DOCK		●			●	●			SEE PLANS FOR MORE INFORMATION
DIVISION 04: MASONRY									
MASONRY WALL		●			●	●			AS NEEDED FOR NEW CONSTRUCITON. SEE PLANS FOR MORE INFORMATION.
DIVISION 05: METALS									
STRUCTURAL FRAMING SYSTEMS		●			●	●			ULTA G.C. TO PROVIDE STRUCTURAL FRAMING SYSTEM AT MANAGER'S OFFICE, AND AS NEEDED FOR NEW CONSTRUCITON. SEE STRUCTURAL DRAWIGNS FOR MORE INFORMATION.
STEEL LINTELS, H-FRAMES, RTU-CURBS, MISC. FABRICATION.		●			●	●			SEE GENERAL NOTES ON SHEET CS-1, AND STRUCTURAL DRAWINGS.
REINFORCEMENT FOR HVAC EQUIPMENT		●			●	●			SEE STRUCTURAL DRAWINGS
DIVISION 06: WOOD AND PLASTICS									
ROUGH CARPENTRY					●	●			AS APPLICABLE TO EACH CONTRACTORS SCOPE OF WORK
FINISH CARPENTRY					●	●			AS APPLICABLE TO EACH CONTRACTORS SCOPE OF WORK
MILL WORK						●	●		
RESTROOM TRIM AND MOLDINGS					●	●			
WALL BLOCKING					●	●			SEE NOTES ON SHEET A1.1 AND A2.0
BLOCKING FOR PERIMETER WALL FIXTURES IN SALES AREA					●	●			FOR SURFACE MOUNTED CLEATS SEE SHEET A2.0
WALL BLOCKING FOR EXTERIOR WALL SIGNS		●			●	●			G.C. TO VERIFY WITH KIEFFER IF LOCATION OF EXISTING PLYWOOD IS SUFFICIENT, IF NOT, G.C. TO PROVIDE ADDITIONAL BLOCKING AS REQUIRED.
DIVISION 07: THERMAL AND MOISTURE CONTROL									
ROOF INSULATION		●			●	●			EXISTING TO REMAIN, G.C. TO PROVIDE NEW AS NEEDED FOR NEW CONSTRUCTION.
ROOF ACCESS AND LADDER	●								FIELD VERIFY LOCATION WITH ONSITE MALL MANAGEMENT.
INSULATION IN EXTERIOR PERIMETER WALLS AND DEMISING WALLS		●			●	●			SEE A2.0 FOR LOCATIONS
INSULATION IN INTERIOR PARTITION WALLS					●	●			SEE A2.0 FOR LOCATIONS
ROOF PATCHING					●	●			AS REQUIRED, BY LL APPROVED CONTRACTOR
DIVISION 08: DOORS, WINDOWS AND GLASS									
EXTERIOR DOORS, FRAMES AND HARDWARE		●			●	●			SEE DOOR AND HARDWARE SCHEDULES.
INTERIOR DOORS, FRAMES AND HARDWARE					●	●			ALL OTHER INTERIOR DOORS BY ULTA G.C. SEE DOOR HARDWARE SCHEDULES AND SEE LANDLORD DRAWINGS FOR REFERENCE ONLY.
STOREFRONT GLAZING SYSTEM		●			●	●			EXISTING 1" INSULATED GLASS IN CLEAR ANODIZED ALUMINUM FRAMES. G.C. TO BRING UP TO AS NEW CONDITION. SEE PLANS AND ELEVATIONS FOR MORE INFORMATION.
DOOR VISION PANELS WITH ONE WAY MIRRORS/GLAZING					●	●			SEE DOOR AND HARDWARE SCHEDULES
COLUMN ENCLOSURES					●	●			
STOREFRONT MODIFICATION					●	●			SEE PLANS AND ELEVATIONS
VESTIBULE SYSTEM, SOFFIT ABOVE, DOORS AND HARDWARE	●								
INTERIOR ENTRY ARCH PORTAL	●								
INTERIOR ENTRY ARCH DOORS AND HARDWARE	●								SEE DOOR AND HARDWARE SHEDULES
HANDRAILS	●								SEE DETAILS AND PLANS FOR LOCATIONS
DIVISION 09: FINISHES									
DEMISING PARTITION		●			●	●			SEE A2.0 FOR PARTITION REQUIREMENTS. G.C. TO PROVIDE FIRE SAFING TO MAINTAIN REQUIRED FIRE RATING. G.C. TO CONFIRM REQUIREMENTS WITH LOCAL FIRE MARSHAL INSPECTOR. REPAIR ANY EXISTING DEMISING PARTITION TO REMAIN AFTER INSTALLING BLOCKING TO MAINTAIN REQUIRED FIRE RATING.
METAL STUD / GYPSUM BOARD FURRING ON MASONRY PERIMETER WALLS		●			●	●			SEE A2.0 G.C. FOR PARTITION REQUIREMNTS. G.C. TO REMOVE EXISTING GYPSUM BOARD AS REQUIRED TO PROVIDE IN WALL MILLWORK BLOCKING AND REPLACE GYPSUM BOARD AT AN EXISTING WALLS TO REMAIN.
METAL STUD / GYPSUM BOARD (INTERIOR PARTITION WALLS)					●	●			SEE A2.0
FURRED GYPSUM BOARD ON MASONRY WALLS / CONCRETE					●	●			AS REQUIRED
ACOUSTICAL TILE CEILING					●	●			SEE A3.1 FOR LOCATIONS & NOTES. PROVIDE (1) CASE OF ACT FOR ATTIC STOCK
PORCELAIN TILE						●	●		SEE FINISH PLAN FOR LOCATIONS
VINYL STRIP FLOOR TILE VT-3						●	●		SEE FINISH PLAN & SCHEDULE FOR LOCATIONS. PROVIDE REMAINING VT-3 (NO GLUE ON BACK) FOR ATTIC STOCK. G.C. TO PROVIDE 3 YEARS INSTALLATION WARRANTY. SEE SHOP DRAWING SUBMITTAL TESTING AND INSPECTION REQUIREMENTS ON CS-3.
VINYL FLOOR TILE VT-8 AND VT-9					●	●			SEE FINISH PLAN FOR LOCATIONS, PROVIDE REMAINING VINYL TILE FOR ATTIC STOCK
WALL BASE (ALL PERIMETER WALL FIXTURES)					●	●			SEE FINISH PLAN FOR LOCATIONS, PROVIDE REMAINING WALL BASE FOR ATTIC STOCK
WALL BASE (ALL WALLS AND COLUMNS)					●	●			SEE FINISH PLAN FOR LOCATIONS, PROVIDE REMAINING WALL BASE (NO GLUE ON BACK) FOR ATTIC STOCK
FLOOR TRANSITION STRIPS					●	●			SEE FINISH PLAN FOR LOCATIONS
WALL COVERING VINYL						●	●		SEE ELEVATIONS FOR LOCATIONS
PAINTING EXTERIOR FACADE		●			●	●			SEE ELEVATIONS FOR MORE INFORMATION, PROVIDE (1) FULL GALLON OF EACH COLOR FOR ATTIC STOCK.
PAINTING OF INTERIOR GYPSUM BOARD AT STOREFRONT					●	●			SEE ELEVATIONS FOR LOCATION, PROVIDE (1) FULL GALLON OF EACH COLOR FOR ATTIC STOCK.
PAINTING INTERIOR PARTITIONS					●	●			SEE ELEVATIONS FOR LOCATION, PROVIDE (1) FULL GALLON OF EACH COLOR FOR ATTIC STOCK.
PAINTING INTERIOR DOORS AND FRAMES/WINDOW FRAMES					●	●			SEE ELEVATIONS FOR LOCATION, PROVIDE (1) FULL GALLON OF EACH COLOR FOR ATTIC STOCK.
PERIMETER WALL FIXTURES						●	●		SEE ELEVATIONS FOR LOCATIONS
FRP PANELS					●	●			MOP BASIN - SEE ELEVATIONS FOR LOCATIONS
WINDOW SHADES					●	●			
METAL PANELS AT INTERIOR STOREFRONT	●								
DIVISION 10: MISCELLANEOUS SPECIALTIES									
TOILET ROOM ACCESSORIES					●	●	●		SEE A6.3 DETAILS FOR LOCATION AND SCHEDULE
TOILET ROOM MIRRORS					●	●			SEE A6.3 DETAILS FOR LOCATION AND SCHEDULE
SKIN CARE MIRROR	●								
SALON STATION MIRRORS						●	●		
EXTERIOR SIGNS						●	●	●	FOR FULL SCOPE OF WORK REFER TO A7.1 AND E1.1
LED LETTER SET FOR INTERIOR MALL ENTRY	●								LED LETTER SET FOR INTERIOR MALL ENTRY FURNISHED BY ULTA VENDOR (KIEFFER SIGNS), INSTALLED BY LANDLORD G.C., FINAL ELECTRICAL WIRING AND CIRCUITING BY ULTA G.C.
CLINIQUE LIGHT BOX AND FABRIC GRAPHIC PANEL	●								FABRIC LIGHT BOX FURNISHED BY ULTA MILLWORK VENDOR (SEE CS3.0 FOR CONTACT). INSTALLED BY G.C. FINAL ELECTRICAL WIRING AND CIRCUITING BY ULTA G.C. FABRIC GRAPHIC PANEL FURNISHED BY ULTA AND INSTALLED BY G.C.
CASH COUNTER/RECEPTION DESK						●	●		SCRIBE TOE KICK BASE TO FLOOR
SALES AREA FIXTURES						●	●		
INTERIOR SIGNAGE AND GRAPHICS (NON-ILLUMINATED)						●	●	●	
INTERIOR SIGNAGE (ILLUMINATED)						●	●		
RECEIVING ROOM SHELVING, UPRIGHTS AND BRACKETS						●	●		
SOUND SYSTEM AND SPEAKERS						●	●	●	REFER TO ELECTRICAL FOR G.C. SCOPE OF WORK
SALON FIXTURES/SEATING/WALL/CABINETS						●	●		
OFFICE FIXTURES, SHELVING, UPRIGHTS AND BRACKETS						●	●		
SAFE						●	●		SECURELY ADHERE TO FLOOR, COORDINATE W/ INSTALLATION INSTRUCTIONS & ULTA
COFFEE MAKER						●	●		
REFRIGERATORS					●	●	●		C-17 FURNISHED BY G.C., C-10 FURNISHED BY TENANT
FIRE EXTINGUISHERS					●	●			COMPLY WITH LOCAL CODE REQUIREMENTS. G.C. MUST PURCHASE FIRE EXTINGUISHERS FROM ULTA VENDOR, SEE CONTACT INFORMATION ON SHEET CS-3
SECURITY SYSTEMS						●	●	●	
LOCKERS						●	●		SECURELY ADHERE TO WALL. COORDINATE W/ INSTALLATIONS INSTRUCTIONS & ULTA
SALON TIP BOX						●	●		TO BE LOCATED NEAR THE TOP INSIDE EDGE OF THE CABINET DOOR WITHIN THE CONCIERGE DESK AND CASHWRAP. SEE SHEET F1.1B.
DRAWING STORAGE TUBE					●	●			4" DIAMETER CAPPED PVC TUBE LOCATED NEAR ELECTRICAL PANELS
EXTERIOR AWNINGS							●	●	SEE SHEET A7.1
WALL STORAGE SYSTEM					●	●			SEE INTERIOR ELEVATIONS OF STAGING AREA. STORAGE SYSTEM TO BE ORDERED AT START OF CONSTRUCTION.
IT COSMETICS LIGHT BOX & FABRIC GRAPHIC PANEL	●								FABRIC LIGHT BOX FURNISHED BY ULTA MILWORK VENDOR (SEE CS3.0 FOR CONTACT), INSTALLED BY G.C., FINAL ELECTRICAL WIRING AND CIRCUITING BY ULTA G.C., FABRIC GRAPHIC PANEL SUPPLIED BY ULTA AND INSTALLED BY G.C.
SKINBAR LIGHT BOX						●	●		LIGHT BOX FURNISHED BY ULTA MILWORK VENDOR (SEE CS3.0 FOR CONTACT), INSTALLED BY G.C., FINAL ELECTRICAL WIRING AND CIRCUITING BY ULTA G.C.
MAC LIGHT BOX & FABRIC GRAPHIC PANEL	●								FABRIC LIGHT BOX FURNISHED BY ULTA MILWORK VENDOR (SEE CS3.0 FOR CONTACT), INSTALLED BY G.C., FINAL ELECTRICAL WIRING AND CIRCUITING BY ULTA G.C. FABRIC GRAPHIC PANEL SUPPLIED BY ULTA AND INSTALLED BY G.C.
LANCOME LIGHT BOX & FABRIC GRAPHIC PANEL						●	●		FABRIC LIGHT BOX FURNISHED BY ULTA MILWORK VENDOR (SEE CS3.0 FOR CONTACT), INSTALLED BY G.C., FINAL ELECTRICAL WIRING AND CIRCUITING BY ULTA G.C. FABRIC GRAPHIC PANEL SUPPLIED BY ULTA AND INSTALLED BY G.C.
DIVISION 15: MECHANICAL									
ROOF TOP UNITS/HVAC EQUIPMENT		●			●	●			SEE MECHANICAL DRAWINGS AND NOTES INCLUDES GAS PIPING.
ROOF DRAINAGE		●							SEE MECHANICAL DRAWINGS AND NOTES.
CONDENSATE DRAINAGE		●			●	●			SEE MECHANICAL DRAWINGS FOR LOCATIONS AND NOTES.
HVAC DISTRIBUTION					●	●			SEE MECHANICAL DRAWINGS FOR LOCATIONS AND NOTES.
WASHER DRYER VENTS					●	●			SEE MECHANICAL DRAWINGS FOR LOCATIONS AND NOTES.
GAS WATER HEATER INTAKE AND EXHAUST, 6" TYPE B VENT AND ROOF PENETRATION		●			●	●			SEE MECHANICAL DRAWINGS FOR LOCATIONS AND NOTES.
ONE 10" ROUND DUCT WITH ROOF CAP MODEL GREENHECK #GRS-10.		●			●	●			SEE MECHANICAL DRAWINGS FOR LOCATIONS AND NOTES.
ONE 10" DIAMETER EXHAUST VENT WITH GOOSE-NECK TERMINATION.		●			●	●			SEE MECHANICAL DRAWINGS FOR LOCATIONS AND NOTES.
ROOF MOUNTED EXHAUST FAN		●			●	●			SEE MECHANICAL DRAWINGS FOR LOCATIONS AND NOTES.
WATER SUPPLY STUB IN TO SPACE		●			●	●			SEE PLUMBING DRAWINGS FOR LOCATIONS AND NOTES. G.C. TO PROVIDE 2" WATER SERVICE STUBBED AT REAR OF SPACE TIGHT TO STRUCTURE WITH 50 TO 60 GPM (90 GPM MAX) FLOW, WATER METER THAT WILL BE LOCATED IN MANHOLE ON SITE. AND BACKFLOW PREVENTER TO BE PROVIDED IN THE SPACE.
WATER SUPPLY DISTRIBUTION					●	●			SEE PLUMBING DRAWINGS FOR LOCATIONS AND NOTES
SANITARY STUB IN TO SPACE		●			●	●			SEE PLUMBING DRAWINGS FOR LOCATIONS AND NOTES.
SANITARY ROOF VENTS		●			●	●			G.C. TO PROVIDE ONE NEW SANITARY ROOF VENT. SEE PLUMBING DRAWINGS FOR MORE INFORMATION.
SANITARY SEWER ROUGH-INS FOR PLUMBING FIXTURES					●	●			SEE PLUMBING DRAWINGS FOR LOCATIONS & NOTES. G.C. TO PROVIDE ULTA PROJECT MANAGER WITH ROD AND SCOPE VIDEO SCOPE OF SEWER LINES TO LANDLORD'S MAIN PRIOR TO CONSTRUCTION START AND TURNING SPACE OVER TO ULTA, COPY OF VIDEO TO BE PROVIDED TO PROJECT MANAGER AT TIME OF PUNCHLIST.
TOILET, URINAL, ELECTRIC WATER COOLERS					●	●			SEE PLUMBING DRAWINGS FOR LOCATIONS & NOTES, PLUMBING FIXTURE SCHEDULE
RESTROOM SINKS					●	●			SEE PLUMBING DRAWINGS FOR LOCATIONS & NOTES, PLUMBING FIXTURE SCHEDULE
SINKS IN MILLWORK					●	●			SEE PLUMBING DRAWINGS FOR LOCATIONS & NOTES, PLUMBING FIXTURE SCHEDULE
GAS LINE STUB IN FOR WH		●			●	●			SEE PLUMBING DRAWINGS FOR LOCATIONS AND NOTES. G.C. TO PROVIDE APPROPRIATELY SIZED LOW PRESSURE GAS LINE STUB INTO SPACE FOR WATER HEATER. G.C. TO VERIFY LOCATION OF ANY EXISTING STUB IN FIELD.
UTILITIES TO ROOF TOP UNITS		●			●	●			G.C.TO PROVIDE FULLY FUNCTIONING UNITS CONNECTED TO THE GAS AND ELECTRIC SERVICE. THEY ARE TO BE OPERATIONAL AND POWERED UP AS OF THE PREMISES DELIVERY DATE. THE G.C. SHALL COORDINATE A FACTORY START-UP FOR EACH HVAC UNIT AFTER INSTALLATION OF DUCTWORK IS COMPLETED.
GAS / ELECTRIC WATER HEATER					●	●			
SHAMPOO SINKS						●	●		
SPRINKLER MAIN AND SPRINKLER SYSTEM INCLUDING DESIGN, HEADS AND ACCESSORIES		●			●	●			G.C. WILL MODIFY EXISTING AUTOMATIC FIRE SPRINKLER SYSTEM TO HAVE MAINS THROUGHOUT TIGHT TO THE UNDERSIDE OF ROOF STRUCTURE MIN 15' A.F.F. AND TURNED UP HEADS AT THE TIME OF LANDLORD TURNOVER. PER LOCAL REQUIREMENTS G.C. TO PREPARE SPRINKLER SYSTEM DRAWINGS AND SUBMIT FOR SEPARATE PERMIT AS REQUIRED FOR MODIFICATION OF SYSTEM TO ACCOMMODATE INTERIOR TENANT LAYOUT. G.C. TO SUBMIT SPRINKLER DRAWINGS TO ULTA FOR REVIEW.
DIVISION 16: ELECTRICAL									
SERVICE/MAIN/SUB-PANELS / TRANSFORMERS		●			●	●			SEE ENGINEERING DRAWINGS FOR NOTES.
ADD'L SUB-PANELS DISTRIBUTION, J-BOXES, WIRING AND OUTLETS					●	●			SEE ENGINEERING DRAWINGS FOR NOTES
UNDERGROUND CONDUIT AND J-BOXES					●	●			SEE ENGINEERING DRAWINGS FOR NOTES
CIRCUIT BREAKERS					●	●			SEE ELECTRICAL ONE-LINE DIAGRAM NOTES ON E0-1
FLOOR BOXES						●	●		SEE ENGINEERING DRAWINGS FOR NOTES. SEE SPECIALITY LIGHTING GROUP VENDOR CONTACT INFORMATION ON CS-3
UNDERGROUND WIRING AND BOXES					●	●			SEE ENGINEERING DRAWINGS FOR NOTES
WIRING AND J-BOXES FOR FIXTURES					●	●			SEE ENGINEERING DRAWINGS FOR NOTES
EXTERIOR SIGN WIRING AND TIME CLOCKS					●	●			SEE ENGINEERING DRAWINGS FOR NOTES
STOREFRONT LIGHTING					●	●			SEE ENGINEERING DRAWINGS FOR NOTES
EXTERIOR SITE LIGHTING		●			●	●			SEE ENGINEERING DRAWINGS FOR NOTES
INTERIOR GENERAL LIGHTING WITH LAMPS						●	●		
WIRING AND J-BOX FOR INTERIOR LIGHTING AND TIMERS					●	●			SEE ENGINEERING DRAWINGS FOR NOTES
INTERIOR ACCENT LIGHTING WITH LAMPS						●	●		SEE ENGINEERING DRAWINGS FOR NOTES
EXIT AND EMERGENCY LIGHTING						●	●		SEE ENGINEERING DRAWINGS FOR NOTES
POWER REQUIREMENTS FOR MECHANICAL EQUIPMENT		●			●	●			SEE ENGINEERING DRAWINGS FOR NOTES. G.C. TO WIRE UNITS TO HIGHER VOLTAGE AND PROVIDE APPROPRIATE BREAKERS.
WEATHERPROOF RECEPTACLE AT EACH HVAC UNIT		●			●	●			
DOOR CHIME WITH TRANSFORMER AND PUSH BUTTON					●	●			BY G.C.
FIRE ALARM SYSTEM		●			●	●			AS REQUIRED BY LANDLORD AND LOCAL CODES. G.C. TO PREPARE FIRE ALARM DRAWINGS AND SUBMIT FOR SEPARATE PERMIT. SEE VENDOR CONTACT INFORMATION FOR APPROVED ULTA FIRE ALARM VENDOR -VECTOR.
CHECKPOINT SECURITY SYSTEM						●	●	●	CONDUIT BY G.C. IF REQUIRED BY CODE. REFER TO ELECTRICAL DRAWINGS AND NOTES FOR MORE INFORMATION
SECURITY SYSTEM (GENERAL)						●	●	●	CONDUIT BY G.C. IF REQUIRED BY CODE. REFER TO ELECTRICAL DRAWINGS AND NOTES FOR MORE INFORMATION.
CONDUIT, J-BOXES, COVERPLATES FOR SOUND SYSTEM					●	●			CONDUIT BY G.C. IF REQUIRED BY CODE. REFER TO ELECTRICAL DRAWINGS AND NOTES FOR MORE INFORMATION.
CONDUIT, J-BOXES, COVERPLATES FOR TELEPHONES					●	●			CONDUIT BY G.C. IF REQUIRED BY CODE. REFER TO ELECTRICAL DRAWINGS AND NOTES FOR MORE INFORMATION.
CONDUIT, SECURITY SYSTEM, J-BOXES COVERPLATES					●	●			CONDUIT BY G.C. IF REQUIRED BY CODE. REFER TO ELECTRICAL DRAWINGS AND NOTES FOR MORE INFORMATION.
TELEPHONE SERVICE CONDUIT STUB		●			●	●			
TELEPHONE BOARD					●	●			
TEMP LIGHTING DURING CONSTRUCTION PER **OSHA** STANDARDS					●	●			REGULATIONS (STANDARDS 29CFR) ILLUMINATIONS-1926.56

LEGEND

NOTE:
L.G.C LANDLORD GENERAL CONTRACTOR   G.C. GENERAL CONTRACTOR   V.I.F. VERIFY IN FIELD

NOTE:
1. G.C. TO PROVIDE FORK-LIFT WITH FORK EXTENSIONS ON SITE DURING CONSTRUCTION THROUGH FIRST WEEKEND OF STOCKING. SEE VENDOR CONTACT INFORMATION ON CS3.0 SHEET.
2. G.C. TO CONTACT LANDLORD REPRESENTATIVE FOR LANDLORD REQUIRED CONTRACTORS. SEE COVER SHEET FOR LANDLORD CONTACT INFORMATION.
3. G.C. TO FURNISH AND INSTALL TENANT SPACE ADDRESS PER LANDLORDS' REQUIREMENTS.
4. G.C. TO VERIFY SIZE AND SHAPE OF TENANT SPACE BEFORE LAYING OUT STORE.
5. G.C. TO PROVIDE 3/4" PLYWOOD PROTECTION UNDER ALL DEBRIS BOXES AND STORAGE CONTAINERS.
6. G.C. TO PERFORM FINAL CLEAN PRIOR TO PUNCHLIST WALK THROUGH. PRIOR TO STORE OPENING ULTA TO PERFORM PROFESSIONAL CLEANING AND FLOOR CLEANING THE WEDNESDAY BEFORE THE FRIDAY SOFT OPENING.
7. G.C. TO TOUCH UP PAINT PRIOR TO STORE OPENING.
8. G.C. TO USE ULTA VENDOR FOR FINAL CONSTRUCTION DUMPSTERS. SEE VENDOR CONTACT INFORMATION ON SHEET CS-3.
9. G.C. TO PROVIDE PHOTOGRAPHS TO ULTA CONSTRUCTION MANAGER. SEE REQUIRED PHOTO LIST ON SHEET CS-3. ALL PHOTOS ARE REQUIRED TO HAVE A DATE STAMP. ALL PHOTOS SHALL BE TAKEN AND PROVIDED TO CM PRIOR TO WALLS BEING ENCLOSED AND MIRRORS BEING INSTALLED TO ENSURE PROPER INSTALLATION.

Order Plans @ WWW.LDILine.com

RGLA
rgla solutions, inc.
5100 River Road, Ste 125
Schiller Park, IL 60176
p: 847.671.7452
f: 847.671.4200
www.rgla.com

REVISIONS:	DATE:
LL & ULTA REVIEW	06/03/2019
BID ISSUE	06/03/2019
PERMIT ISSUE	06/04/2019

robert g. lyon + associates, inc.
retail architecture
5100 River Road, Ste 125
Schiller Park, IL 60176
p: 847.671.7452
f: 847.671.4200
www.rgla.com

SEAL:

THE ABOVE DRAWINGS AND SPECIFICATIONS AND IDEAS, DESIGNS AND ARRANGEMENTS REPRESENTED THEREBY ARE AND SHALL REMAIN THE PROPERTY OF THIS OFFICE: AND NO PART THEREOF SHALL BE COPIED, DISCLOSED TO OTHERS OR USED IN THE CONNECTION WITH ANY WORK OR PROJECT OTHER THAN THE SPECIFIC PROJECT FOR WHICH THEY HAVE BEEN PREPARED AND DEVELOPED WITHOUT THE WRITTEN CONSENT OF THIS OFFICE. VISUAL CONTACT WITH THESE DRAWINGS OR SPECIFICATIONS SHALL CONSTITUTE CONCLUSIVE EVIDENCE OF ACCEPTANCE OF THESE RESTRICTIONS.

WRITTEN DIMENSIONS ON THESE DRAWINGS SHALL HAVE PRECEDENCE OVER SCALED DIMENSIONS: CONTRACTORS SHALL VERIFY AND BE RESPONSIBLE FOR ALL DIMENSIONS AND CONDITIONS ON THE JOB AND THIS OFFICE MUST BE NOTIFIED OF ANY VARIATIONS FROM THE DIMENSIONS AND CONDITIONS SHOWN BY THESE DRAWINGS. SHOP DETAILS MUST BE SUBMITTED TO THIS OFFICE FOR APPROVAL BEFORE PROCEEDING WITH FABRICATION.

©2018 RGLA SOLUTIONS, INC.
©2018 ROBERT G. LYON & ASSOCIATES, INC.

ULTA BEAUTY

ULTA #1613
SHOPPES OF MADISON
8201 HIGHWAY 72 WEST
SUITE C
MADISON, AL 35758

PROJECT
SPECIFICATIONS
AND DIVISION
OF WORK

DRAWN BY: IA
CHECKED BY: PK
JOB NUMBER: 19047
SHEET NAME: CS2.0