

- KEYNOTES:**
- 0-20V LED DIMMER SWITCH. FURNISH AND INSTALL THE SWITCH TO CONTROL THE LIGHTS IN THIS SPACE. RUN LOW VOLTAGE CONTROL CABLE IN CONDUIT TO DIMMABLE BALLAST.
 - THREE WAY 0-20V LED DIMMER SWITCH. FURNISH AND INSTALL THE SWITCH TO CONTROL THE LIGHTS IN THIS SPACE. RUN LOW VOLTAGE CONTROL CABLE IN CONDUIT TO DIMMABLE BALLAST.
 - EXISTING CORRIDOR LIGHT FIXTURE TO BE REPLACED WITH THE NEW FIXTURE. CONNECT THE FIXTURE TO THE EXISTING CORRIDOR LIGHT CIRCUIT THAT SERVES THIS SPACE. MAINTAIN ALL EXISTING LIGHTING CONTACTOR CONTROLS.
 - EXISTING CORRIDOR LIGHT FIXTURE TO BE REPLACED WITH THE NEW FIXTURE. CONNECT THE FIXTURE TO THE EXISTING CORRIDOR NIGHT LIGHT CIRCUIT THAT SERVES THIS SPACE. MAINTAIN ALL EXISTING LIGHTING CONTACTOR CONTROLS.
 - CONNECT THE NEW FIXTURES TO THE EXISTING 277V NIGHT LIGHTING CIRCUIT IN THE CORRIDOR. CONTRACTOR TO FURNISH AND INSTALL A UNSWITCHED 277V CONDUCTOR TO THE BATTERY PACK IN THESE FIXTURES.
 - FURNISH AND INSTALL THE CEILING MOUNTED DUAL TECHNOLOGY OCCUPANCY SENSOR. CONTRACTOR SHALL INTERRUPT THE HOT CONDUCTOR BEFORE THE LIGHT SWITCH CONTROLS IN THIS SPACE. FURNISH AND INSTALL THIS POWER PACK IN A NEMA 1 ENCLOSURE LOCATED ABOVE THE CEILING. UPON COMPLETION OF THE SENSOR THE LIGHT SWITCHES SHALL STILL CONTROL THE LIGHTS IN THE SPACE WITH THE OCCUPANCY SENSOR PROVIDING CONTROL. THE CEILING MOUNTED OCCUPANCY SENSOR SHALL BE LOCATED IN THE CENTER OF THE ROOM.
 - RUN CONTROL TO THREE WAY 0-20V DIMMER SWITCHES AT LOWER LEVEL PLAN. REFER TO SHEET E28A FOR ADDITIONAL INFORMATION.
 - RUN THE CIRCUIT THROUGH CONTACTOR "AS". CONTACTOR SHALL BE EDGM WITH H-0-A INTERNAL SWITCH. CONTACTOR SHALL BE CONTROLLED THROUGH THE HVAC EMS CONTROLS. RUN CONTRACTOR CONDUCTORS IN CONDUIT FROM THE CONTACTOR TO THE HVAC EMS PANEL. COORDINATE THE EXACT LOCATION OF THIS PANEL WITH THE HVAC CONTRACTOR PRIOR TO ROUGH-IN. CONTRACTOR SHALL RUN ONE ADDITIONAL UNSWITCHED CONDUCTOR THAT BYPASSES THE CONTACTOR CONTROL TO THE BATTERY PACKS IN THE FIXTURES.

Order Plans @ www.LDILine.com

PERKINS + WILL

1315 Peachtree St. NE
Atlanta, GA 30309
404.873.2300
404.872.5823
www.perkinswill.com

CONSULTANTS

CIVIL
Braedlove Land Planning
15 Simpson St. NW, Atlanta, GA 30308

STRUCTURAL
Uzun+Case
1230 Peachtree St. NE, Suite 2500, Atlanta, GA 30309

MEP
Matheson Ball & Associates
11295 Elkins Rd., Suite F3, Roswell, GA 30078

LANDSCAPING
Perkins+Will
1315 Peachtree St. NE, Atlanta, GA 30309

Camacho
3103 Medlock Bridge Road, Norcross, GA 30071

OWNER
KIPP Metro Atlanta Schools
504 Fair St SW Suite 300

FACILITY

CONTRACTOR


PROJECT

RELEASED FOR CONSTRUCTION 06/07/2019

KIPP ATLANTA COLLEGIATE - Addition and Renovations
98 Anderson Ave NW
Atlanta GA 30314



KEYPLAN



ISSUE CHART

DATE	ISSUE	DATE
	Job Number	
	Drawn	PAT
	Checked	PAT
	Approved	PAT
	TITLE	

FLOOR PLAN - THIRD FLOOR - PART A LIGHTING

SHEET NUMBER

E1.3A

Copyright © 2018 Perkins+Will