

- KEY NOTES:**
- COORDINATE THE LOCATIONS OF THE CUBICAL POWER/DATA LOCATIONS WITH THE OWNER AND THE EQUIPMENT INSTALLER PRIOR TO ROUGH-IN.
 - WALL MOUNT THE GFI RECEPTACLE AT 8" ABOVE THE COUNTER.
 - FURNISH AND INSTALL POWER AND DATA TO THE OWNER FURNISHED EQUIPMENT. COORDINATE THE LOCATIONS OF THE CUBICAL POWER/DATA LOCATIONS WITH THE OWNER AND THE EQUIPMENT INSTALLER PRIOR TO ROUGH-IN.
 - FURNISH AND INSTALL STRUCTURAL SUPPORT FOR PANEL INSTALLATIONS IN THE MIDDLE OF THE EXISTING ELECTRICAL. ANCHOR UNISTRUT SUPPORTS TO FLOOR AND STRUCTURE. MAINTAIN ALL NEC REQUIRED CLEARANCES.
 - FURNISH AND INSTALL A 208/1 VOLT 30A NEMA LS-30R RECEPTACLE FOR THE DATA RACK UPS. COORDINATE THE EXACT LOCATION OF THE RECEPTACLE WITH THE OWNER PRIOR TO ROUGH-IN.
 - FURNISH AND INSTALL A 208/1 VOLT 20A RECEPTACLE FOR THE DATA RACK UPS. COORDINATE THE EXACT LOCATION OF THE RECEPTACLE WITH THE OWNER PRIOR TO ROUGH-IN.
 - FURNISH AND INSTALL A 120 VOLT 20A RECEPTACLE FOR THE DATA RACK AT 72" ABOVE THE FINISHED AND ADDITIONAL 120 VOLT 20A RECEPTACLE AT 18" ABOVE THE FINISHED FLOOR. COORDINATE THE EXACT LOCATION OF THE RECEPTACLE WITH THE OWNER PRIOR TO ROUGH-IN.
 - EXISTING HVAC UNIT IS TO BE REPLACED BY THE HVAC CONTRACTOR. FURNISH AND INSTALL A NEW 30A/1P/FUSE DISCONNECT SWITCH AND CONNECT TO EXISTING CIRCUIT THAT SERVED THE DEMOLISHED HEATER. FURNISH AND INSTALL 3/4" C AND #10 CONDUCTORS TO MAINTAIN AND RECONNECT THE EXISTING CIRCUIT.
 - REMOVE THE EXISTING FIRE ALARM EQUIPMENT AT THIS LOCATION. MAINTAIN ALL DOWNSTREAM DEVICES.
 - LOCATION OF THE SWITCHBOARD "SSB" SHUNT THE SWITCH. LABEL SWITCH AS NOTED ON THE ELECTRICAL RISER DIAGRAM.

Order Plans @ www.LDLine.com

PERKINS + WILL

1315 Peachtree St. NE
Atlanta, GA 30309
404.873.2300
404.872.5823
www.perkinswill.com

CONSULTANTS

CIVIL
Braedlove Land Planning
15 Simpson St. NW, Atlanta, GA 30308

STRUCTURAL
Uzun+Case
1230 Peachtree St. NE, Suite 2500, Atlanta, GA 30309

MEP
Matheson Ball & Associates
11285 Elkins Rd., Suite F3, Roswell, GA 30078

LANDSCAPING
Perkins+Will
1315 Peachtree St. NE, Atlanta, GA 30309

Camacho
3103 Medlock Bridge Road, Norcross, GA 30071

OWNER
KIPP Metro Atlanta Schools
504 Fair St. SW Suite 300

FACILITY


CONTRACTOR

RELEASED FOR CONSTRUCTION 06/07/2019

KIPP ATLANTA COLLEGIATE - Addition and Renovations
98 Anderson Ave NW
Atlanta GA 30314



KEYPLAN



ISSUE CHART

NO.	DATE	BY
Job Number		PAT
Drawn		PAT
Checked		PAT
Approved		PAT
TITLE		

FLOOR PLAN - FIRST FLOOR - PART A - POWER

SHEET NUMBER

E2.1A

Copyright © 2018 Perkins+Will

① 01 - FIRST FLOOR - PART A - POWER
3/32" = 1'-0"