

- PARKING LEVEL FRAMING NOTES**
1. POST-TENSIONING REINFORCEMENT IS UNBONDED AND COMPLETELY ENCAPSULATED.
 2. POST-TENSIONING LAYOUT SHOWN ON S202 ALSO APPLIES TO LEVELS 3 AND 4, UNLESS NOTED OTHERWISE.
 3. TENDON FORCES SHOWN, PROVIDED IN KIPS FOR CONCENTRATED TENDON GROUPS AND IN KIPS PER FOOT FOR UNIFORM TENDONS, ARE EFFECTIVE (AFTER ALL LOSSES).
 4. POUR STRIPS TO REMAIN OPEN FOR 90 DAYS AFTER INITIAL CONCRETE POURS. REFER TO 185515 FOR ADDITIONAL REQUIREMENTS.

- SHEET NOTES**
1. SEE SHEET S201 FOR ABBREVIATIONS AND LEGENDS.
 2. SEE S201 SERIES FOR EDGE OF SLAB DRAWINGS, WHICH INCLUDE SLAB THICKNESS, ELEVATIONS, AND BRIT-SLAB EXTENTS.
 3. SEE SHEETS S301 AND S302 FOR BUILDING SECTIONS.
 4. SEE S5XX SERIES FOR CONCRETE SECTIONS AND DETAILS.
 5. SEE S533-S534 FOR COLUMN SCHEDULE.
 6. SEE S556-S557 FOR BRICK WALL ELEVATIONS AND DETAILS.
 7. SEE S6XX SERIES FOR STEEL SECTIONS AND DETAILS.
 8. SEE S7XX SERIES FOR MASONRY SECTIONS AND DETAILS.
 9. SEE S8XX SERIES FOR ELEVATOR SECTIONS AND DETAILS.
 10. REFER TO S401 FOR REINFORCEMENT QUANTITY ALLOWANCES TO BE USED IN PRICING.




Project
**THE CENTER FOR
 ADVANCED SURGICAL
 SERVICES (CASS)**
 88 JESSE HILL DRIVE
 ATLANTA, GA 30303

Prepared For
GRADY HEALTH SYSTEM
 80 JESSEE HILL DR. SE
 ATLANTA, GA 30303



Hok, Inc. - Oates & Kastbaum, Inc.
 191 Peachtree Street, NE, Suite 2250
 Atlanta, GA 30303 USA
 T+1 404 439 9000 F+1 404 439 9001

All reproduction & intellectual property rights reserved © 2019
 in Association with



Professional Seal

**NOT FOR
 CONSTRUCTION**

No.	Description	Date
1	ED - GMP	2019.07.01

Project No: 18.16013.00
 Sheet Title
**STRUCTURAL
 FRAMING PLAN - LEVEL
 3 - WEST**

Original is 30 x 42. Do not scale contents of this drawing.
 Sheet Number

S203A

1 STRUCTURAL FRAMING PLAN - LEVEL 3 - AREA A
 1/8" = 1'-0"

2019-07-02 5:13:41 PM

Order Plans @ www.LDILine.com