

FINISH SCHEDULE									
Designation	Type	Manufacturer	Product Name	Color	Finish	Size	Location	Comments	Contact
064023 INTERIOR ARCHITECTURAL									
PL01	PLASTIC LAMINATE	FORMICA	-	GRAYSTONE	MATTE	-	CLINICAL CASEWORK	-	LESLIE GALIFIANAKIS...
PL02	PLASTIC LAMINATE	WILSONART	D354-60	DESIGNER WHITE	MATTE	-	CLINICAL CASEWORK AND NURSE STATIONS	AEON SCRATCH RESISTANCE	DAVID MAY 770.527.2466
PL03	PLASTIC LAMINATE	WILSONART	8213K-28	PHANTOM COCOA	GLOSS LINE FINISH	-	LOBBY	AEON SCRATCH RESISTANCE	DAVID MAY 770.527.2466
PL04	PLASTIC LAMINATE	WILSONART	8214K-28	PHANTOM CHARCOAL	GLOSS LINE FINISH	-	PUBLIC WAITING CONCOURSE, TEAM WORKSTATIONS, NURS...	AEON SCRATCH RESISTANCE	DAVID MAY 770.527.2466
PL05	PLASTIC LAMINATE	WILSONART	-	BLUE	NURSE STATION...	-	-	-	-
064200 ARCHITECTURAL WOODWORK									
WD05	WOOD VENEER	MATERIALS INC	TABU	MI-H1253	20% SHEEN	-	LOBBY	-	KELLI TROUT 616.871.3350
WD06	WOOD VENEER	MATERIALS INC	TABU	MI-H1255	20% SHEEN	-	PUBLIC WAITING CONCOURSE	-	KELLI TROUT 616.871.3350
088000 GLAZING									
GF01	GLASS	-	1/4" TEMPERED GLASS, CLEAR	-	-	-	-	-	-
GF02	GLASS	-	5/8" TEMPERED GLASS, CLEAR	-	-	-	-	-	-
GF03	GLASS	FORMS AND SURFACES	VIVICHROMIS	ULTRA WHITE	OPALEX	-	GROUND FLOOR ELEVATOR LOBBY WALL PANELS	-	-
088753 DECORATIVE FILM									
DF01	INTERIOR GLAZING FILM	3M	FILM	DUSTED CRYSTAL	-	-	TEAM SORK STATIONS	-	JAMIE HAMILTON...
DF02	POLYESTER WINDOW FILM	LEVEL - NATIONAL...	L91907FWG TANGENT	SAFARI ON FILM	-	-	PUBLIC WAITING CONCOURSE	-	MAUREEN BLAIR 678.603.3788
DF03	POLYESTER WINDOW FILM	LEVEL - NATIONAL...	L32606 BLUESTEM GARDEN	CITRON	-	-	INFUSION SEMI PRIVATE	-	MAUREEN BLAIR 678.603.3788
DF04	INTERIOR GLAZING FILM	3M	FILM	-	-	-	CONFERENCE ROOMS AND PATIENT RESOURCE CENTER	-	-
RESIN PANEL									
AP02	POLYRESIN PANEL	LUMICOR	LUMINOUS	SEAGLASS	MATTE	-	PHARMACY	-	STEVE GIBBS 404.218.9911
AP03	POLYRESIN PANEL	LUMICOR	LUMINOUS	PACIFIC	MATTE	-	PHARMACY	-	STEVE GIBBS 404.218.9911
AP04	POLYRESIN PANEL	LUMICOR	LUMINOUS	MIMOSA + SEAGLASS	MATTE	-	PHARMACY	-	STEVE GIBBS 404.218.9911
AP05	POLYRESIN PANEL	LUMICOR	LUMINOUS	LAGO	MATTE	-	PHARMACY	-	STEVE GIBBS 404.218.9911
093000 TILING									
TL01	PORCELAIN WALL TILE	SPECIALTY TILE PRODUCTS INC	TECHNICOLOR	TC13 GREEN	-	2" x 15"	STAFF LOUNGE	-	ELIZABETH ROPER...
TL02	PORCELAIN WALL TILE	SPECIALTY TILE PRODUCTS INC	TECHNICOLOR	TC14 PETROLEUM	-	2" x 15"	STAFF LOUNGE	-	ELIZABETH ROPER...
TL03	PORCELAIN WALL TILE	SPECIALTY TILE PRODUCTS INC	TECHNICOLOR	TC15 TURQUOISE	-	2" x 15"	STAFF LOUNGE	-	ELIZABETH ROPER...
TL04	PORCELAIN WALL TILE	SPECIALTY TILE PRODUCTS INC	TECHNICOLOR	TC16 SKY	-	2" x 15"	STAFF LOUNGE	-	ELIZABETH ROPER...
TL05	PORCELAIN WALL TILE	CERAMIC TECHNICS	FORIANO	FLAGSTONE WHITE	-	-	PARKING ELEVATOR LOBBY WALL TILE	-	KELLY BOWEN 404.433.6997
TL06	PORCELAIN FLOOR TILE	CERAMIC TECHNICS	STUDIO ELEMENTS STATION	SHADOW NATURAL	-	-	PARKING ELEVATOR LOBBY FLOOR	-	KELLY BOWEN 404.433.6997
TL07	CERAMIC WALL TILE	CERAMIC TECHNICS	BASE STUDIO HUDSON	WHITE GLOSSY	-	4" x 12"	PUBLIC RESTROOM WALL TILE	-	KELLY BOWEN 404.433.6997
TL08	PORCELAIN FLOOR TILE	CERAMIC TECHNICS	TBD	-	-	12" x 24"	PUBLIC RESTROOMS FLOOR TILE	ALLOWANCE \$5-10 PER SQ FT MATERIAL...	KELLY BOWEN 404.433.6997
TL09	PORCELAIN TILE	CERAMIC TECHNICS	TBD	-	-	3" x 18"	LOBBY RECEPTION WALL TILE	ALLOWANCE \$5-10 PER SQ FT MATERIAL...	KELLY BOWEN 404.433.6997
TL10	PORCELAIN TILE	CERAMIC TECHNICS	TBD	-	-	12" x 24"	GROUND FLOOR PUBLIC RESTROOM WALL TILE	ALLOWANCE \$5-10 PER SQ FT MATERIAL...	KELLY BOWEN 404.433.6997
TL11	PORCELAIN TILE	CERAMIC TECHNICS	TBD	-	-	6" x 12"	EXAM ROOM RESTROOMS AND WET WALL TILE	ALLOWANCE \$5-10 PER SQ FT MATERIAL...	KELLY BOWEN 404.433.6997
TLB01	PORCELAIN BASE	CERAMIC TECHNICS	BULLNOSE TO MATCH TL06	-	-	-	PARKING ELEVATOR LOBBY BASE	-	-
TLB02	PORCELAIN BASE	CERAMIC TECHNICS	BULLNOSE TO MATCH TL08	-	-	-	RECEPTION BASE	-	-
TLB03	PORCELAIN BASE	CERAMIC TECHNICS	BULLNOSE TO MATCH TL 11	-	-	-	RESTROOMS BASE	-	-
095123 ACOUSTIC TILE CEILING									
ACT01	ACOUSTICAL CEILING TILE	ARMSTRONG	CLEAN ROOM VL	UNPERFORATED SQUARE	-	15/16" x 24"	LABS, CLEAN ROOMS, SOILED ROOMS, AND PROCEDURE	15/16" GRID, VINYL WRAPPED; CLEAN...	JOSEPH TEETER 770.262.5955
ACT02	ACOUSTICAL CEILING TILE	ARMSTRONG	OPTIMA	SQUARE LAY IN	-	24" x 24"	OFFICES, ADMIN, STAFF LOUNGE, boh	-	JOSEPH TEETER 770.262.5955
ACT03	ACOUSTICAL CEILING TILE	ARMSTRONG	OPTIMA HEALTH ZONE	-	-	24" x 24"	EXAM ROOMS	-	MARKER BOARD
ACT04	ACOUSTICAL CEILING PANEL	ARMSTRONG	ACOUSTIBUILT	-	-	-	LOBBY	-	-
ACT05	ACOUSTICAL CEILING TILE	HUNTER DOUGLASS	TECHSTYLE WHITE	-	-	24" x 48"	PUBLIC WAITING CONCOURSE	-	-
096513 RESILIENT BASE									
RFB01	RUBBER WALLBASE	JOHNSONITE	MILLWORK BASE SILHOUETTE	-	-	4" HIGH	PUBLIC CORRIDORS	-	MARJORIE BOSLEY...
RFB02	RUBBER WALLBASE	JOHNSONITE	RUBBER WALL BASE TRADITIONAL COVE	-	-	4" HIGH	RF09	-	MARJORIE BOSLEY...
RFB03	RUBBER WALLBASE	JOHNSONITE	RUBBER WALL BASE TRADITIONAL COVE	-	-	4"	RF23	-	-
RFB04	RUBBER WALLBASE	JOHNSONITE	RUBBER TOELESS BASE	-	-	4"	BOH SPACES	-	-
RFB05	RUBBER WALLBASE	JOHNSONITE	RUBBER TOELESS BASE	-	-	4"	STAIR	-	-
RFB06	RUBBER WALLBASE	JOHNSONITE	SANITARY WALL BASE	-	-	4"	PACU AND PREPOST	-	-
096723 INTEGRAL COVE BASE									
ICB01	SHEET VINYL	ARMSTRONG	WRAP SHEET VINYL IN FIELD AND OR TO CREATE INTEGRAL...	-	-	6"	OR	-	MARJORIE BOSLEY...
ICB02	SHEET VINYL	ARMSTRONG	WRAP SHEET VINYL IN FIELD AND OR TO CREATE INTEGRAL...	-	-	4"	PROCEDURE	-	-
ICB03	EPOXY INTEGRAL COVE BASE	-	-	-	-	4"	BOH	-	-
ICB04	ELASTOMETRIC INTEGRAL COVE...	-	-	-	-	4"	ELECTRICAL AND MECHANICAL	-	-
096519 RESILIENT SHEET FLOORING									
RF04	LVT	ARMSTRONG FLOORING	DECORART REJUVENATIONS AMBIGU	38503 ALCHEMY PRINCESS...	W/ DIAMOND...	6' 7" WIDTH, UP TO 82'...	-	-	PATRICIA BENTSON...
RF05	LVT	ARMSTRONG FLOORING	COLORART MEDINTECH	H532 GRAYED BLUE	W/ DIAMOND...	6' 7" WIDTH, UP TO 98.4 FT	OPERATION ROOM ACCENT FLOORING	-	PATRICIA BENTSON...
RF06	LVT	ARMSTRONG FLOORING	COLORART MEDINTECH	H5304 NATURAL GRAY...	W/ DIAMOND...	6' 7" WIDTH, UP TO 98.4 FT	-	-	PATRICIA BENTSON...
RF07	LVT	PATCRAFT	1320V ORGANIC HUE	00410 STEEL	-	6' WIDE SHEET	-	-	SCOTT PRESSMAN...
RF08	LVT	PATCRAFT	1320V ORGANIC HUE	00420 CORNFLOWER	-	6' WIDE SHEET	PACU & PREPOST GENERAL FLOORING	-	SCOTT PRESSMAN...
096519 RESILIENT TILE FLOORING									
RF09	LVT	PATCRAFT	METALLIX	00570 PEWTER	-	9" x 36"	PUBLIC WAITING CONCOURSE	-	SCOTT PRESSMAN...
RF10	LVT	PATCRAFT	METALLIX FACET	00570 PEWTER	-	12" x 32.5"	PUBLIC WAITING CONCOURSE	-	SCOTT PRESSMAN...
RF11	LVT	PATCRAFT	METALLIX	00400 ALKALINE BLUE	-	9" x 36"	PUBLIC WAITING CONCOURSE	-	SCOTT PRESSMAN...
RF12	LVT	PATCRAFT	METALLIX FACET	00400 ALKALINE BLUE	-	12" x 32.5"	PUBLIC WAITING CONCOURSE	-	SCOTT PRESSMAN...
RF13	LVT	PATCRAFT	METALLIX	00380 SLATE TEAL	-	9" x 36"	PUBLIC WAITING CONCOURSE	-	SCOTT PRESSMAN...
RF14	LVT	PATCRAFT	METALLIX FACET	00380 SLATE TEAL	-	12" x 32.5"	PUBLIC WAITING CONCOURSE	-	SCOTT PRESSMAN...
RF15	LVT	PATCRAFT	METALLIX	00330 IONIC GREEN	-	9" x 36"	PUBLIC WAITING CONCOURSE	-	SCOTT PRESSMAN...
RF16	LVT	PATCRAFT	METALLIX FACET	00330 IONIC GREEN	-	12" x 32.5"	PUBLIC WAITING CONCOURSE	-	SCOTT PRESSMAN...
RF17	LVT	PATCRAFT	METALLIX	00450 STEEL BLUE	-	9" x 36"	PUBLIC WAITING CONCOURSE	-	SCOTT PRESSMAN...
RF18	LVT	PATCRAFT	METALLIX FACET	00450 STEEL BLUE	-	12" x 32.5"	PUBLIC WAITING CONCOURSE	-	SCOTT PRESSMAN...
RF19	LVT	PATCRAFT	METALLIX	00450 STEEL BLUE	-	9" x 36"	PUBLIC WAITING CONCOURSE	-	SCOTT PRESSMAN...
RF20	VCT	ARMSTRONG FLOORING	MIGRATIONS BBT	T3501 PLATINUM GRAY	-	12" x 12"	BOH	-	PATRICIA BENTSON...

GENERAL FINISH SCHEDULE NOTES

- A. GENERAL NOTES:**
- CONTRACTOR IS RESPONSIBLE FOR STORING ALL MATERIALS PRIOR TO INSTALLATION, AS WELL AS REMAINING AT-TIC STOCK PER MANUFACTURER'S INSTRUCTION. CONTRACTOR WILL BE RESPONSIBLE FOR ANY DAMAGE INCURRED DUE TO IMPROPER STORAGE, AND REPLACE AT NO COST TO OWNER.
 - REFER TO THE PROJECT SPECIFICATIONS FOR DESCRIPTION OF MATERIAL QUALITY AND INSTALLATION METHODS. ALL FINISHES SHALL BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S SPECIFICATIONS AND RECOMMENDATIONS.
 - ALL SURFACES WHICH ARE TO RECEIVE FINISHES ARE TO BE CLEAN, SMOOTH, AND PREPARED TO ACCEPT SPECIFIED FINISH. ALL FINISH SUB CONTRACTORS ARE RESPONSIBLE FOR INSPECTION OF WORK SURFACE CONDITION PRIOR TO INSTALLATION. SEE WALL AND FLOOR FINISH PLANS FOR EXTENT OF WORK POINTS.
 - ALL INTERIOR FINISHES SHALL MEET OR EXCEED "CLASS A" FIRE RATING.
 - CONTRACTOR IS RESPONSIBLE FOR PATCHING AND REPAIRING ANY DAMAGE TO FINISHED SURFACES DURING CONSTRUCTION OF INTERIOR FINISHES.
- B. FLOORING:**
- ALL SUB FLOORING MATERIAL TO BE INSTALLED BY CONTRACTOR RESPONSIBLE FOR INSPECTION. SUB FLOOR TO BE INSTALLED WITH FLOORING MANUFACTURER'S MOISTURE PHASE AND FLOOR JOINTS PRIOR TO INSTALLATION TO MAINTAIN WARRANTY. ADDITIONAL FLOOR PREPARATION MAY BE REQUIRED TO TRENCH FLOOR EQUIPMENT.
 - NO FLOORING PRODUCT SUBSTITUTIONS WILL BE ALLOWED UNDER ANY CIRCUMSTANCES WITHOUT THE KNOWLEDGE, REVIEW AND APPROVAL FROM THE INTERIOR DESIGNER.
 - CONTRACTOR TO BE RESPONSIBLE FOR USE OF AT-TIC STOCK PROVIDED BY OWNER. FINISHING MAY BE SUBJECT TO AVAILABILITY OF STOCK AND SHOULD BE CONFIRMED PRIOR TO THE START OF PROJECT.
- C. PAINT:**
- ALL WALLS SHALL BE EGGSHELL FINISH UNLESS NOTED OTHERWISE. ALL WALLS SHALL BE PT11 UNLESS OTHERWISE NOTED.
 - TYPICAL ALL DOOR FRAMES AND WINDOW FRAMES TO BE PAINTED PT11 UNLESS OTHERWISE NOTED.
 - CONTRACTOR SHALL SUBMIT PAINT SAMPLES FOR APPROVAL TO THE INTERIOR DESIGNER PRIOR TO PURCHASE OF INSTALLATION. SAMPLES TO BE PREPARED IN ACCORDANCE WITH THE SPECIFICATION USING ONE (1) COAT OF PRIMER AND TWO (2) COATS OF PAINT COLOR WITH SPECIFIED SHEEN. MOCKUP SAMPLES TO BE SUBMITTED IN A TIMELY MANNER ALLOWING DESIGNER TO REQUEST ADDITIONAL MOCKUPS AS REQUIRED.
 - ALL ACCENT COLORS ARE TO BE APPLIED WITH MINIMUM OF ONE (1) PRIMER COAT AND TWO (2) COATS OF SPECIFIED PAINT. IF NEEDED APPLY ADDITIONAL COATS FOR FULL OPAQITY. FINISHED ACCENT WALLS ARE TO BE THOROUGHLY COVERED WITH ACCENT PAINT FREE FROM STREAKING AND NOTICABLE DETECTION OF DRYWALL IMPERFECTIONS INCLUDING TAPE AND MUD. PROVIDE HARD STRAIGHT EDGE LINE WHERE THE ACCENT COLOR MEETS ADJACENT WALL COLOR MATERIALS.
- D. WALL PROTECTION:**
- SHEET WALL PROTECTION SHALL BE FACTORY CUT.
- E. MILLWORK:**
- ALL MILLWORK CABINET INTERIOR SURFACES SHALL BE WHITE MELAMINE UNLESS OTHERWISE NOTED. MILLWORK CABINET DOOR BACKS AND EDGES TO BE PLASTIC LAMINATE TO MATCH CABINET FACE. ALL MILLWORK OPEN SHELVES, BROCHURE SLOTS, AND CUBBIES TO HAVE MATCHING PLASTIC LAMINATE ON ALL SIDES AND BACK.
 - PLASTIC LAMINATE WOOD GRAIN SHALL RUN VERTICAL UNLESS OTHERWISE NOTED. ALL WOOD GRAIN LAMINATE SHALL RUN IN THE SAME DIRECTION.
 - AS APPLICABLE ALL BASES AT MILLWORK CASEWORK SHALL BE 4" HIGH APPLY RUBBER COVE BASE AT ALL HARD FLOORING SURFACES UNLESS OTHERWISE NOTED.
 - ALL BACKSPASHES AND COUNTERS AT SINK LOCATIONS TO BE SOLID SURFACE CORIAN UNLESS OTHERWISE NOTED.
- F. ELEVATOR CAB FINISHES:**
- COORDINATE ALL ELEVATOR CAB FINISHES WITH INTERIOR DESIGNER.
 - ELEVATOR CAB WALL FINISHES TO RECEIVE PACKAGE FROM FORMS AND SURFACES AND ELEVATOR CAB FLOORING TO BE RESILIENT LUXURY VINYL TILE.
- G. BASE:**
- ALL HEAT WELDED INTEGRAL COVE BASES SHALL COVE STICK SUPPORT.



Project
**THE CENTER FOR
 ADVANCED SURGICAL
 SERVICES (CASS)**
 80 GILMER STREET SE
 ATLANTA, GA 30303


Prepared For
GRADY HEALTH SYSTEM
 80 JESSE HILL DR. SE
 ATLANTA, GA 30303



Helmut Obata & Kastbaum, Inc.
 133 Peachtree Street, NE, Suite 4800
 Atlanta, GA 30303 USA
 T+1 404 439 9000 F+1 404 439 9001

All reproduction & intellectual property rights reserved © 2019
 An Association with

Key Plan



Professional Seals

**NOT FOR
 CONSTRUCTION**

No.	Description	Date
1	ED - GMP	2019-07-03

Project No: 18-16013.00
 Sheet Title

**INTERIOR FINISH
 SCHEDULE**

Original is 20 x 43. Do not scale contents of this drawing
 Sheet Number

A220.1