DOOR SCHEDULE LVL 6

OPENING NUMBER	ROOM ID	ROOM NAME	DOOR PANELS – DOOR PANEL TYPE – PANEL 1	DOOR PANEL TYPE – PANEL 2	DOOR PANEL MATERIAL	DOOR PANEL FINISH	DOOR PANEL OR OPENING DIMENSIONS – WIDTH – PANEL 1	WIDTH – PANEL 2	HEIGHT	DOOR FRAMES – FRAME TYPE	FRAME MATERIAL	FRAME FINISH	FRAME GLAZING PANELS – FRAME SIDELITE COUNT	SINGLE LITE WIDTH	FRAME SIDELITE WIDTH	FRAME SIDELITE HEIGHT	THROAT	LEAD LINING	DOOR HARDWARE GROUP	FIRE RATING (MIN)	SMOKE CONTROL	STC RATING	REVISION	COMMENTS
LEVEL 6																								
6006	6006	WHEELCHAIR STOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							5 1/4"							
6018	6018	STAFF / SERVICE ELEVATOR LOBBY	PNL-N	PNL-N			3' - 0"	3' - 0"	7' - 0"	FRM-01							7 1/4"							
6018A	6018	STAFF / SERVICE ELEVATOR LOBBY	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6100	5291	COOR.	PNL-TG1	PNL-TG 1			3' - 0"	3' - 0"	8' - 0"	FRM-01							4 7/8"							
6101	5291	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6103	6103	OFFICE, FIN. COUN.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6105	5291	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6111	6111	CONTROL ROOM	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6113	6113	DENTAL LAB ORAL FIT	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6113A	6113	DENTAL LAB ORAL FIT	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6114	6114	PAT. TLT.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6117A	6117	PREP/RECOVERY	PNL-F				4' - 0"		7' - 0"	FRM-01							4 7/8"							
6117B	6200	ENT/AUDIOLOGY	PNL-F				4' - 0"		7' - 0"	FRM-01							4 7/8"							
6118	6118	PROCEDURE	PNL-F				4' - 0"		7' - 0"	FRM-01							4 7/8"							
6119	6119	EQUIP.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6124	6124	SOILED	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6126	6126	MEDS	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6127	6904	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6129	6904	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							8 1/2"			1HR				
6131	6131	OMFS 6	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6133	6133	OMFS 5	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6135	6135	OMFS 4	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6136	6136	ST. TLT.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6137	6137	OMFS 3	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6139	6139	OMFS 2	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6141	6141	OMFS 1 (SN)	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6143	6143	EQUIP.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6200	5291	COOR.	PNL-TG1	PNL-TG 1			3' - 0"	3' - 0"	8' - 0"	FRM-01							4 7/8"							
6200A	6200A	TLT.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6201	5291	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6203	6203	OFFICE, RN	PNL-D				3' - 0"		8' - 0"	FRM-01							4 7/8"							
6209	6209	ENT 1 (S.N.)	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6211	6211	ENT 2	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6213	6213	ENT 3	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6214	6214	PAT. TLT.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6215	6215	AUDIOLOGY WORKROOM	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6217	6217	HEARING AID TESTING	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6219	6219	HEARING AID TESTING	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6221	6221	IDF ROOM	PNL-F				3' - 0"		7' - 0"	FRM-01							8 1/2"			1HR				
6224	6224	SOILED	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6225	6905	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6226	6226	CLEAN	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6227	6905	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6229	6904	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							8 1/2"			1HR				
6231	6200	ENT/AUDIOLOGY	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6234	6234	PROCEDURE	PNL-F				4' - 0"		7' - 0"	FRM-01							4 7/8"							
6236	6236	ST. TLT.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6237	6200	ENT/AUDIOLOGY	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6239	6200	ENT/AUDIOLOGY	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6241	6200	ENT/AUDIOLOGY	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6291	6491	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"			SMK	SMK			
6300	6491	COOR.	PNL-TG1	PNL-TG 1			3' - 0"	3' - 0"	8' - 0"	FRM-01							4 7/8"							
6300A	6300A	TLT.	PNL-D				3' - 0"		8' - 0"	FRM-01							4 7/8"							
6301	6491	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6305	6305	OFFICE, FIN. COUNC.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6307	6491	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6309	6309	GEN SURG EXAM 1 (SN)	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6311	6311	GEN SURG EXAM 2	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6313	6313	GEN SURG EXAM 3	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6314	6314	ST. TLT.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6315	6315	GEN SURG EXAM 4	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6317	6317	GEN SURG EXAM 5	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6319	6319	EXAM ROOM	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6324	6324	SOILED	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6325	XXXX	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6326	6326	CLEAN	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6327	XXXX	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6329	XXXX	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6331	6331	GEN SURG EXAM 12	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6333	6333	GEN SURG EXAM 11	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6334	6334	PROCEDURE	PNL-F				4' - 0"		7' - 0"	FRM-01							4 7/8"							
6335	6335	GEN SURG EXAM 10	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6336	6336	PAT. TLT.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6337	6337	GEN SURG EXAM 9	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6339	6339	GEN SURG EXAM 8	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6341	6341	GEN SURG EXAM 7 (SN)	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6342	6342	OFFICE	PNL-D				3' - 0"		8' - 0"	FRM-01							4 7/8"							
6391	6491	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6400	6491	COOR.	PNL-TG1	PNL-TG 1			3' - 0"	3' - 0"	8' - 0"	FRM-01							4 7/8"							
6400A	6400A	TLT.	PNL-D				3' - 0"		8' - 0"	FRM-01							4 7/8"							
6401	6491	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 [illegible]							
6403	6491	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/[illegible]							
6409	6409	GI EXAM 1 (SN)	PNL-F				3' - 0"		7' - 0"	FRM-01							[illegible]8"							
6411	6411	GI EXAM 2	PNL-F				3' - 0"		7' - 0"	FRM-01							[illegible]7/8"							
6413	6413	GI EXAM 3	PNL-F				3' - 0"		7' - 0"	FRM-01							[illegible]7/8"							
6414	6414	PAT. TLT.	PNL-F				3' - 0"		7' - 0"	FRM-01							[illegible]							
6415	6415	GI EXAM 4	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6417	6417	GI EXAM 5	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6419	6419	GI EXAM 6	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6421	6506	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6423	6506	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6424	6424	CLEAN	PNL-F				3' - 0"		7' - 0"	FR[illegible]							4 7/8"							
6425	6506	COOR.	PNL-F				3' - 0"		7' - 0"	[illegible]							4 7/8"							
6426	6426	SOILED	PNL-F				3' - 0"		[illegible]	FRM-0[illegible]							4 7/8"							
6427	6506	COOR.	PNL-F				[illegible] 0"		7' - 0"	[illegible]RM-01							4 7/8"							
6429	6506	COOR.	PNL-F				[illegible]		7' - [illegible]	FRM-01							4 7/8"							
6431	XXXX	GI CLINIC	PNL-F				3[illegible]		[illegible] - 0"	FRM 01							4 7/8"							
6433	XXXX	GI CLINIC	PNL-F				[illegible]		[illegible] - 0"	FRM 01							4 7/8"							

DOOR SCHEDULE LVL 6

OPENING NUMBER	ROOM ID	ROOM NAME	DOOR PANELS – DOOR PANEL TYPE – PANEL 1	DOOR PANEL TYPE – PANEL 2	DOOR PANEL MATERIAL	DOOR PANEL FINISH	DOOR PANEL OR OPENING DIMENSIONS – WIDTH – PANEL 1	WIDTH – PANEL 2	HEIGHT	DOOR FRAMES – FRAME TYPE	FRAME MATERIAL	FRAME FINISH	FRAME GLAZING PANELS – FRAME SIDELITE COUNT	SINGLE LITE WIDTH	FRAME SIDELITE WIDTH	FRAME SIDELITE HEIGHT	THROAT	LEAD LINING	DOOR HARDWARE GROUP	FIRE RATING (MIN)	SMOKE CONTROL	STC RATING	REVISION	COMMENTS
6434	6434	PROCEDURE	PNL-F				4' - 0"		7' - 0"	FRM-01							4 7/8"							
6435	XXXX	GI CLINIC	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6436	6436	ST. TLT.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6437	XXXX	GI CLINIC	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6439	XXXX	GI CLINIC	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6441	XXXX	GI CLINIC	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6475			PNL-F				3' - 6"		8' - 0"	FRM-01							1' - 6"							
6492	6491	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"			SMK	SMK			
6500	6595	COOR.	PNL-N	PNL-N			3' - 0"	3' - 0"	7' - 0"	FRM-01							4 7/8"			SMK	SMK			
6500A	6500A	TLT.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6502	6502	PAT. TLT.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6503A	6503	EXAM 18	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6503B	3371	OPHTHALMOLOGY	PNL-F				3' - 6"		7' - 0"	FRM-50							4 3/4"							
6504	6504	PAT. TLT.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6505A	6505	EXAM 19	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6505B	3371	OPHTHALMOLOGY	PNL-F				3' - 6"		7' - 0"	FRM-50							4 3/4"							
6506	6506	COOR.	PNL-F	PNL-F			3' - 6"	3' - 6"	8' - 0"	FRM-05							4 7/8"			SMK	SMK			
6506	6506	EQUIP	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6507A	6507	EXAM 20	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6507B	3371	OPHTHALMOLOGY	PNL-F				3' - 6"		7' - 0"	FRM-50							4 3/4"							
6508	3371	OPHTHALMOLOGY	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6509A	6509	EXAM 21	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7[illegible]							
6509A	6000	PUBLIC WAITING															[illegible]				SMK			
6509B	3371	OPHTHALMOLOGY	PNL-F				3' - 6"		7' - 0"	FRM-50							4 [illegible]							
6511A	6511	EXAM 22	PNL-F				3' - 0"		7' - 0"	FRM-01							4 [illegible]							
6511B	3371	OPHTHALMOLOGY	PNL-F				3' - 6"		7' - 0"	FRM-50							4 3[illegible]							
6512	3371	OPHTHALMOLOGY	PNL-F				3' - 6"		7' - 0"	FRM-50							4 3/4"							
6513	6513	TEAM WORK	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6513A	6513A	ST. TLT.	PNL-F				3' - 0"		7' - 0"	FRM-01							[illegible]7/8"							
6514	6595	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"			SMK	SMK			
6517	6513	TEAM WORK	PNL-TG1				3' - 6"		7' - 0"	FRM-50							4 3/4"							
6517A	6517A	ST. TLT.	PNL-F				3' - 0"		7' - 0[illegible]	[illegible]01							4 7/8"							
6517B	6521	TEAM WORK	PNL-TG1				3' - 6"		[illegible] 0"	[illegible]							4 3/4"							
6523A	6523	EXAM 17	PNL-F				3' - 0"		7' - 0"	FRM-[illegible]							4 7/8"							
6523B	3237	OPHTHALMOLOGY	PNL-F				3' - 6"		7' - 0"	FRM-50							4 3/4"							
6524	3237	OPHTHALMOLOGY	PNL-F				3' - 6"		7' - 0"	FRM-50							4 3/4"							
6525A	6525	EXAM 16	PNL-F				3' - 0"		[illegible] - 0"	FRM-01							4 7/8"							
6525B	3237	OPHTHALMOLOGY	PNL-F				3' - 6"		[illegible]	FRM-50							4 3/4"							
6526	3237	OPHTHALMOLOGY	PNL-F				3' - 6"		[illegible]	FRM-50							4 3/4"							
6527A	6527	EXAM 15	PNL-F				3' - 0"		7' [illegible]	FRM-0[illegible]							4 7/8"							
6527B	3237	OPHTHALMOLOGY	PNL-F				3' - 6"		7' - 0[illegible]	[illegible]50							4 3/4"							
6528	3237	OPHTHALMOLOGY	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6529A	6529	EXAM 14	[illegible]F				3' - 0"		7' - [illegible]	FRM-01							4 7/8"							
6529B	3237	OPHTHALMOLOGY	PNL[illegible]				3' - 6"		7' - 0"	FRM-50							4 3/4"							
6530	3237	OPHTHALMOLOGY	PNL-[illegible]				[illegible] - 0"		7' - 0"	FRM-01							4 7/8"							
6531A	6531	EXAM 13	PNL-[illegible]				[illegible]		7' - 0"	FRM-01							4 7/8"							
6531B	3237	OPHTHALMOLOGY	PNL-F				[illegible] - 6"		7' - 0"	FRM-50							4 3/4"							
6534	3237	OPHTHALMOLOGY	PNL-F				4' - 0"		7' - 0"	FRM-01							4 7/8"							
6535A	6535	OPHTH. EXAM 6	[illegible]F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6535B	6500	OPHTHALMOL[illegible]	[illegible]				3' - 6"		7' - 0"	FRM-50							4 3/4"							
6537A	6537	EXAM 5	PNL-[illegible]				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6537B	6500	OP[illegible]HALMOLOGY	PNL-F				3' - 6"		7' - 0"	FRM-50							4 3/4"							
6538A	6538	[illegible] WORK	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6539A	6539	EX[illegible]	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6539B	6500	OPHT[illegible]OGY	PNL-F				3' - 6"		7' - 0"	FRM-50							4 3/4"							
65[illegible]0	[illegible]00	OPHTH[illegible]	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6541A	[illegible]	EXAM 3[illegible]	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6541B	650[illegible]	[illegible]PHTHA[illegible]OLOGY	PNL-F				3' - 6"		7' - 0"	FRM-50							4 3/4"							
[illegible]542	6500	[illegible]OLOGY	PNL-F				3' - 6"		7' - 0"	FRM-50							4 3/4"							
[illegible]43A	6543	EXA[illegible]	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
[illegible]43B	6500	OPHTHA[illegible]OLOGY	PNL-F				3' - 6"		7' - 0"	FRM-50							4 3/4"							
65[illegible]4	6500	OPHTHALMOLOGY	PNL-F				3' - 6"		7' - 0"	FRM-50							4 3/4"							
65[illegible]A	6545	EXAM 1	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
[illegible]	6500	OPHTHALMOLOGY	PNL-F				3' - 6"		7' - 0"	FRM-50							4 3/4"							
[illegible]	6500	OPHTHALMOLOGY	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
654[illegible]	XXXX	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6549	XXXX	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6557	XXXX	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6559	XXXX	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							8 1/2"			1HR				
6560	6560	TREATMENT RM.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6561A	6561	EXAM 7	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6561B	3080	OPHTHALMOLOGY	PNL-F				3' - 6"		7' - 0"	FRM-50							4 3/4"							
6562	3080	OPHTHALMOLOGY	PNL-F				3' - 6"		7' - 0"	FRM-50							4 3/4"							
6563A	6563	EXAM 8	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6563B	3080	OPHTHALMOLOGY	PNL-F				3' - 6"		7' - 0"	FRM-50							4 3/4"							
6564	3080	OPHTHALMOLOGY	PNL-F				3' - 6"		7' - 0"	FRM-50							4 3/4"							
6565A	6565	EXAM 9	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6565B	3080	OPHTHALMOLOGY	PNL-F				3' - 6"		7' - 0"	FRM-50							4 3/4"							
6566	6566	PAT. TLT.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6567A	6567	EXAM 10	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6567B	3080	OPHTHALMOLOGY	PNL-F				3' - 6"		7' - 0"	FRM-50							4 3/4"							
6569A	6569	EXAM 11	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6569B	3080	OPHTHALMOLOGY	PNL-F				3' - 6"		7' - 0"	FRM-50							4 3/4"							
6571A	6571	EXAM 12	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6571B	3080	OPHTHALMOLOGY	PNL-F				3' - 6"		7' - 0"	FRM-50							4 3/4"							
6572	6595	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6574	6595	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6576	6595	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6580	6595	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6582	6595	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6591	6595	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6595	6595	COOR.	PNL-N	PNL-N			3' - 0"	3' - 0"	7' - 0"	FRM-01							4 7/8"			SMK	SMK			
6599	6699	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							8 1/2"			1HR				
6699R	6699	COOR.	PNL-F				3' - 6"		8' - 0"	FRM-01							1' - 6"							
6701B	6701	STAIR 1	PNL-F				3' - 0"		7' - 0"	FRM-01							7 1/4"			2HR				
6703	6703	STAIR 3	PNL-F				3' - 6"		7' - 0"	FRM-01							8 1/2"			2HR				
6900	6900	PUBLIC ELEVATOR LOBBY	PNL-F	PNL-F			4' - 0"	4' - 0"	9' - 0"	FRM-05							4 7/8"			SMK	SMK			
6905	6905	COOR.	PNL-F	PNL-F			3' - 6"	3' - 6"	8' - 0"	FRM-05							4 7/8"			SMK	SMK			
6910	6910	CONFERENCE ROOM	PNL-FG	PNL-FG			3' - 0"	3' - 0"	8' - 0"	FRM-01							4 7/8"							
6950	6991	COOR.	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6950A	6950	STAFF LOUNGE	PNL-F				3' - 0"		7' - 0"	FRM-01							4 7/8"							
6991	6991	COOR.	PNL-F	PNL-F			3' - 6"	3' - 6"	8' - 0"	FRM-05							4 7/8"			SMK	SMK			
7702	6702	STAIR 2	PNL-F				3' - 0"		7' - 0"	FRM-01							8 1/2"							
G601D	6701	STAIR 1	PNL-F				3' - 6"		7' - 0"	FRM-01							7 1/4"			2HR				

Order Plans @ WWW.LDILine.com

2019-07-03 4:55:11 PM

Grady

Project
THE CENTER FOR ADVANCED SURGICAL SERVICES (CASS)
80 GILMER STREET SE
ATLANTA, GA 30303

Prepared For
GRADY HEALTH SYSTEM
80 JESSE HILL DR. SE
ATLANTA, GA 30303

Hellmuth, Obata & Kassabaum, Inc.
133 Peachtree Street, NE, Suite 4800
Atlanta, GA 30303 USA
t +1 404 439 9000 f +1 404 439 9001

All reproduction & intellectual property rights reserved © 2019

In Association with

Key Plan



Professional Seals

NOT FOR CONSTRUCTION

No.	Description	Date
1	DD - GMP	2019-07-03

Project No: 18.16013.00

Sheet Title

DOOR SCHEDULE - LEVEL 6

Original is 30 x 42. Do not scale contents of this drawing.

Sheet Number

A903