## ROOM FINISH SCHEDULE

| SPACE | | FLOOR | | BASE | | DOOR/FRAME FNISH | | WALLS | | | | | | | | |
|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|---|
| | | | | | | DOOR | FRAME | NORTH | | SOUTH | | EAST | | WEST | | |
| ROOM NUMBER | ROOM NAME | MATERIAL | COLOR | MATERIAL | COLOR | PAINT | PAINT | MATERIAL | COLOR | MATERIAL | COLOR | MATERIAL | COLOR | MATERIAL | COLOR | REMARKS |
| G303 | RETAIL PHARMACY | RESILIENT SHEET | RS-1 | MATCH RS | IN | PLD-1 | PT-1 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | LEVEL -5 FINISH |
| G304 | OFFICE | VINYL COMPOSITE TILE | VCT | RUBBER BASE | RB-1 | PLD-1 | PT-1 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | LEVEL -5 FINISH |
| G305 | RECEIVING | RESILIENT SHEET | RS-1 | MATCH RS | IN | AL | PT-1 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | LEVEL -5 FINISH |
| 5521 | ASSEMBLY AND REFILL | RESILIENT SHEET | RS-1 | MATCH RS | IN | PLD-1 | PT-1 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | LEVEL -5 FINISH |
| 5525 | SURGERY PHARMACY BULK STORAGE | RESILIENT SHEET | RS-1 | MATCH RS | IN | PLD-1 | PT-1 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | LEVEL -5 FINISH |
| 8571 | SUPERVISOR OFFICE | VINYL COMPOSITE TILE | VCT | RUBBER BASE | RB-1 | PLD-1 | PT-1 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | LEVEL -5 FINISH |
| 8572 | CONSULT & PICK-UP | VINYL COMPOSITE TILE | VCT | RUBBER BASE | RB-1 | PLD-1 | PT-1 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | LEVEL -5 FINISH |
| 8574 | PHARMACY OFFICE | VINYL COMPOSITE TILE | VCT | RUBBER BASE | RB-1 | PLD-1 | PT-1 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | LEVEL -5 FINISH |
| 8575 | NON STERILE (NON HAZARDOUS) | RESILIENT SHEET | RS-1 | MATCH RS | IN | - | - | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | LEVEL -5 FINISH |
| 8576 | STAFF BREAK | RESILIENT SHEET | RS-1 | MATCH RS | IN | - | - | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | LEVEL -5 FINISH |
| 8577 | RETAIL INFUSION PHARMACY | RESILIENT SHEET | RS-1 | MATCH RS | IN | - | - | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | LEVEL -5 FINISH |
| 8578 | STAFF TOILET | CERAMIC TILE | CT | CT | CT | PLD-1 | PT-1 | CT / DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | LEVEL -5 FINISH |
| 8580 | NON-HD SUPPLIES | RESILIENT SHEET | RS-1 | MATCH RS | IN | PLD-1 | PT-1 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | LEVEL -5 FINISH |
| 8582 | ANTE ROOM | RESILIENT SHEET | RS-1 & RS-2 | MATCH RS | IN | AL | AL | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | LEVEL -5 FINISH; RS-1 ON CLEAN SIDE OF DEMARCATION LINE AND RS-2 ON DIRTY SIDE OF DEMARCATION LINE |
| 8582A | NON - HD COMPOUNDING | RESILIENT SHEET | RS-1 | MATCH RS | IN | AL | AL | WP-1 / DRYWALL | WP-1 / PT2 | WP-1 / DRYWALL | WP-1 / PT2 | WP-1 / DRYWALL | WP-1 / PT2 | WP-1 / DRYWALL | WP-1 / PT2 | LEVEL -5 FINISH; PAINTED 2 PART EPOXY PAINT IN ALL CLEAN ROOMS |
| 8582B | HD COMPOUNDING | RESILIENT SHEET | RS-1 | MATCH RS | IN | AL | AL | WP-1 / DRYWALL | WP-1 / PT2 | WP-1 / DRYWALL | WP-1 / PT2 | WP-1 / DRYWALL | WP-1 / PT2 | WP-1 / DRYWALL | WP-1 / PT2 | LEVEL -5 FINISH |
| 8583 | WORK AREA | RESILIENT SHEET | RS-1 | MATCH RS | IN | - | - | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | LEVEL -5 FINISH |
| 8586 | DISPATCH | RESILIENT SHEET | RS-1 | MATCH RS | IN | PLD-1 | PT-1 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | LEVEL -5 FINISH |
| 8587 | RECEIVING/ BREAKDOWN | RESILIENT SHEET | RS-1 | MATCH RS | IN | PLD-1 | PT-1 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | LEVEL -5 FINISH |
| 8587A | BULK STORAGE MEDS - BULK STORAGE IV FLUIDS | RESILIENT SHEET | RS-1 | MATCH RS | IN | - | - | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | LEVEL -5 FINISH |
| 8588 | HD DRUG STOR. / N.S.(HAZARDOUS) COMP. | RESILIENT SHEET | RS-1 | MATCH RS | IN | AL | PT-1 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | DRYWALL | PT-2 | LEVEL -5 FINISH |

## FINISH LEGEND

| TAG | FINISH MATERIAL | MANUFACTURER, PRODUCT, COLOR | SIZE | COMMENTS |
|---|---|---|---|---|
| BASE | | | | |
| IN | FLASH COVE INTEGRAL WALL BASE | MATCH RESILIENT FLOORING | | FLASH COVED TO 6-INCHES A.F.F. |
| RB-1 | RUBBER BASE | MANINGTON, EDGE (TYPEIV), 4-INCH HIGH COLOR: #918 FLAX | | ALL VCT LOCATIONS |
| CEILINGS | | | | |
| ACT-1 | ACOUSTICAL CEILING TILE | ARMSTRONG, CORTEGA SECOND LOOK, 704A TEGULAR, WHITE | REFER TO CEILING PLAN | NON-STERILE AREAS |
| | CEILING GRID | ARMSTRONG | PRELUDE XL 15/16TH | NON-STERILE AREAS |
| FLOORS | | | | |
| CT-1 | CERAMIC TILE | TBD - TO BE COORDINATE WITH HOK INTERIORS | | |
| CT-2 | CERAMIC TILE | TBD - TO BE COORDINATE WITH HOK INTERIORS | | |
| RS-1 | RESILIENT SHEET FLOORING | MANNINGTON, BIOSPEC MD, LINEN 15420 | | ANTE ROOM, COMPOUNDING ROOMS |
| RS-2 | RESILIENT SHEET FLOORING | MANNINGTON, BIOSPEC MD, GRANITE 15425 | | ANTE ROOM |
| VCT-1 | VINYL COMPOSITION TILE | ARMSTRONG, IMPERIAL TEXTURE / SANDRIFT WHITE 51585 | 12" X 12" | OFFICE, CONSULT ROOM |
| MISCELLANEOUS | | | | |
| PLD-1 | DOOR - WOOD | STAINED TBD - TO BE COORDINATED WITH HOK INTERIORS | | |
| | EYEWASH | BRADLEY BARRIER-FREE SWING-DOWN EYE & EYE/FACE WASH UNIT S19-SERIES | REFER TO PLUMBING DRAWINGS | |
| PL-1 | PLASTIC LAMINATE | WILSONART, 7935-07 SHAKER CHERRY | | VERTICAL SURFACES, TYPICAL CABINETRY |
| PL-2 | PLASTIC LAMINATE | WILSONART, 4588K-07 KALAHARI TOPAZ | | ALTERNATE TO SOLID SURFACES FOR COUNTERTOPS AND WORK SURFACES, VERIFY WITH OWNER |
| SS-1 | SOLID SURFACE MATERIAL | CORIAN, FLINT | | COUNTERTOPS AND WORK SURFACES |
| SS-2 | SOLID SURFACE MATERIAL | CORIAN, CAMEO WHITE | | COUNTERTOPS AND WORK SURFACES |
| | STAINLESS STEEL SINK | ELKAY STAINLESS STEEL WALL HUNG SINGLE BOWL HAND WASH SINK | EWS2520SACMC | |
| | STAINLESS STEEL SINK AND DRAIN BOARD | ELKAY STAINLESS STEEL WALL HUNG SERVICE SINK | ESS4924R1 | |
| WALLS | | | | |
| CG-1 | CORNER GUARD, 90 DEGREE AND END WALL PARTITION | STAINLESS STEEL | | PROVIDE CORNER GUARDS AT ALL OUTSIDE CORNERS ON GYP.BD. WALLS U.N.O.; TO BE SURFACE MOUNTED; ADHESIVE APPLIED; TOP EDGE TO BE SEALED WITH A CLEAR SILICONE |
| PT-1 | PAINT | SHERWIN-WILLIAMS, SW-7037, BALANCED BEIGE | | DOOR FRAMES/TRIM - LATEX SEMI-GLOSS |
| PT-2 | PAINT | SHERWIN-WILLIAMS, SW-7011, NATURAL CHOICE | | GENERAL WALL NEUTRAL; DRWYALL AT LEVEL-5 FINISH. PAINTED 2 PART EPOXY AS NOTED ON ROOM FINISH SCHEDULE. |
| WP-1 | RIGID SHEET - SMOOTH FINISH | C/S ACROVYN, PROTECTIVE WALL COVERING, COLOR: TBD | FULL HEIGHT | FULL HEIGHT SMOOTH FINISH, REFER TO DETAIL 1/PH840, 4/PH840 AND 5/PH801 |

**NOTE:**
PROVIDE 2-PART WATER BASED EPOXY PAINT ON WALLS AND CEILINGS, PER SPECIFICATIONS TO THE FOLLOWING ROOMS:
- NON-HD COMPOUNDING
- HD COMPOUNDING
- HD SUPPLIES AND
- ANTE-ROOM

**NOTE:**
FINISHES, COLORS AND GRADES OF MATERIALS ARE INDICATED FOR BIDDING PURPOSES. THE HOSPITAL MAY CHANGE THE EXACT MANUFACTURER(S), MATERIAL, MODEL NUMBER AND COLORS. PRIOR TO ORDERING, VERIFY WITH OWNER.

## GENERAL NOTES - FINISH

1. STANDARDS AND PROCEDURES FOR THE PREPARATION AND APPLICATION OF INTERIOR FINISHES ARE DEFINED IN THE PROJECT MANUAL. FINISH (SUB) CONTRACTORS ARE REQUIRED TO READ, UNDERSTAND AND FOLLOW ALL RELEVANT SECTIONS OF THE PROJECT MANUAL.
2. FINISH MATERIALS ARE LISTED IN THE LEGEND COMPONENT OF THE FINISH SCHEDULE. SPECIFICATIONS ARE INCLUDED IN THE PROJECT MANUAL. ANY CONFLICTS OR DISCREPANCIES BETWEEN THESE TWO SHOULD BE BROUGHT TO THE ARCHITECT'S ATTENTION IMMEDIATELY.
3. NO FINISH MATERIAL SUBSTITUTIONS WILL BE ACCEPTED EXCEPT IN THE SPECIFIC CIRCUMSTANCES ENUMERATED IN THE PROJECT MANUAL.
4. PAINTED HOLLOW METAL DOORS AND FRAMES TO BE PAINTED TO MATCH ADJACENT WALL COLOR UNLESS NOTED OTHERWISE. MATERIAL, FINISH AND COLOR INFORMATION FOR ALL OTHER DOORS AND FRAMES IS CONTAINED IN THE DOOR SCHEDULE AND ITS ASSOCIATED LEGENDS. IF WALLS ON OPPOSITE SIDES OF DOOR FRAME ARE DIFFERENT COLORS THE PAINT COLORS SHOULD BE SPLIT AT THE JAMB OF THE FRAME.
5. ALL VERTICAL TRANSITIONS BETWEEN DIFFERING WALL FINISHES ARE TO BE MADE AT INSIDE CORNERS (UNLESS NOTED OTHERWISE).
6. FLOORING MATERIAL DESIGNATED FOR STAIRS IS TO INCLUDE STAIR AND ALL ASSOCIATED TREADS, RISERS, LANDINGS, ETC. (UNLESS NOTED OTHERWISE).
7. PAINT DESIGNATED FOR METAL STAIR COMPONENTS IS TO INCLUDE ALL EXPOSED METAL COMPONENTS ASSOCIATED WITH THE STAIR SYSTEM ITSELF, ALL EXPOSED STRUCTURAL STEEL COMPONENTS SUPPORTING THE STAIR SYSTEM (UNLESS NOTED OTHERWISE), AND ALL EXPOSED METAL COMPONENTS OF THE HANDRAIL AND GUARDRAIL SYSTEMS (UNLESS NOTED OTHERWISE). UNDERSIDES OF STAIR RUNS AND LANDINGS ARE CONSIDERED "EXPOSED" IN ALL SITUATIONS.
8. FOR CLARITY, SOME FINISH INFORMATION HAS BEEN PRESENTED GRAPHICALLY IN THE FORM OF FINISH AND FLOORING PLANS. SHOULD THERE BE A DISCREPANCY BETWEEN THE FINISH SCHEDULE AND THESE PLANS, THE ARCHITECT SHOULD BE NOTIFIED IMMEDIATELY. FOR THE PURPOSE OF BIDDING, INFORMATION DETAILED ON THE FINISH FLOOR PLANS AND FLOORING PLANS IS TO TAKE PRECEDENCE OVER THE FINISH SCHEDULE UNTIL FURTHER CLARIFICATION CAN BE GIVEN. FOR AREAS NOT SPECIFICALLY DETAILED ON THESE PLANS, THE FINISH SCHEDULE PERTAINS.
9. PAINT DESIGNATED FOR EXPOSED OVERHEAD STRUCTURE IS TO INCLUDE ALL EXPOSED COMPONENTS INCLUDING (BUT NOT EXCLUSIVE TO) DECKING, STRUCTURAL MEMBERS, MECHANICAL AND ELECTRICAL DELIVERY SYSTEMS, FIRE PROTECTION SYSTEMS (EXCLUDING SPRINKLER HEADS), AND ALL OTHER MISCELLANEOUS BUILDING SYSTEMS LOCATED OVERHEAD. EACH OF THE AFOREMENTIONED CATEGORIES IS TO INCLUDE ANY AND ALL ASSOCIATED SUPPORTS, FASTENERS, HANGERS, STRUTS, BRACES, BRACKETS, ETC.
10. WHERE RESILIENT BASE IS SPECIFIED (VINYL OR RUBBER) PROVIDE COVE PROFILE BASE AT ALL RESILIENT FLOORS AND STRAIGHT BASE FOR ALL CARPET AREAS (UNLESS OTHERWISE NOTED). HEIGHT AND COLOR TO BE AS INDICATED ON FINISH LEGEND.
11. REFER TO REFLECTED CEILING PLANS AND SPECIFICATION MANUAL FOR ALL CEILING MATERIAL AND FINISH INFORMATION.
12. ALL DRYWALL SOFFITS TO BE PAINTED FLAT CEILING WHITE UNLESS NOTED OTHERWISE ON CEILING PLANS.
13. CERAMIC WALL TILE TO EXTEND FULL WIDTH AND FULL HEIGHT FOR ANY AND ALL SCHEDULED WALLS (UNLESS NOTED OTHERWISE).
14. FOR EPOXY OR INTUMESCENT PAINT COLOR REFER TO PAINT SCHEDULE NUMBERS.
15. ON FINISH SCHEDULE CELLS: SLASH MARKS INDICATE DIFFERENCES IN FINISH MATERIAL WHILE COMMAS INDICATE DIFFERENCES IN PATTERN OR COLOR WITHIN A SPECIFIC MATERIAL.
16. APPROPRIATE METAL OR VINYL TRANSITION STRIPS MUST BE PROVIDED AT ALL FINISH MATERIAL FLOORING CHANGES. GENERAL CONTRACTOR TO SUBMIT SHOP DRAWINGS FOR ALL FLOORING TRANSITIONS AND AREAS IN WHICH FLOORING PATTERNS ARE SHOWN. SEE FLOOR FINISH PLANS, DETAILS AND NOTES FOR SPECIFIC INFORMATION.
17. WALL PAINT INDICATED FOR CURTAIN WALL LOCATIONS APPLIES TO ALL ASSOCIATED DRYWALL COMPONENTS (CURBS, HEADERS, BULKHEADS, ETC.) AND SHOULD NOT BE INTERPRETED AS APPLYING TO CURTAIN WALL COMPONENTS OR GLASS.
18. FLOORING CONTRACTOR(S) IS RESPONSIBLE FOR COORDINATING FINISHED FLOOR ELEVATIONS WITH ALL/ANY FLOOR MOUNTED COMPONENTS (RECEPTACLES, ACCESS PANELS, ETC.) SO THAT COMPONENTS ARE INTEGRATED AND FLUSH.

## GENERAL NOTES - INTERIOR ELEVATIONS

A. COORDINATE ALL WORK, DEMO & NEW WITH PME DRAWINGS – SEE PME DRAWINGS FOR OTHER REQUIREMENTS NOT SHOWN ON INTERIOR ELEVATIONS. NOTIFY ARCHITECT OF DISCREPANCIES FOR CLARIFICATION.
B. PATCH & REPAIR EXISTING WALLS TO REMAIN AS NECESSARY
C. SEE DOOR AND WINDOW SCHEDULES FOR GLAZING TYPES.
D. SEE FINISH SCHEDULE FOR FINISH INFORMATION.
E. SEE EQUIPMENT PLAN FOR ALL EQUIPMENT INFORMATION. COORDINATE WITH EQUIPMENT VENDOR TO ENSURE PROPER SPACE ALLOCATION AND ALL ITEMS NEEDED FOR INSTALLATION OF EQUIPMENT.
F. PATCH & REPAIR EXISTING WALLS TO REMAIN AS NECESSARY.
G. ALL BASE CABINETS ARE 24" DEEP U.N.O.
H. ALL EXPOSED ENDS OF CASEWORK AND INSIDE FACES OF OPEN CASEWORK ARE TO BE FINISHED WITH THE SAME FINISH AS THE FACE OF CABINET.
I. CASEWORK MANUFACTURER SHALL VERIFY / MEASURE ALL FIELD CONDITIONS PRIOR TO FABRICATION OF CASEWORK / COUNTERTOPS. ANY ALTERATIONS TO THE CASEWORK AS THE RESULT OF FIELD CONDITIONS SHALL BE APPROVED BY THE ARCHITECT AND OWNER PRIOR TO FABRICATION. CONTRACTOR/ MANUFACTURER SHALL COORDINATE WITH CONTRACTOR INSTALLATION OF BLOCKING AND SUPPORT BRACKETS.
J. ALL DIMENSIONS SHOWN ARE TO FACE OF FINISH.
K. ALL MOUNTING HEIGHTS ARE ABOVE FINISH FLOOR (A.F.F.).
L. ALL FULL HEIGHT CABINETS ARE 24" DEEP U.N.O.
M. ALL COUNTERTOPS ARE TO INCLUDE A CONTINUOUS MATCHING 4" BACKSPLASH U.N.O. ALL BACKSPLASHES ASSUMED TO INCLUDE SIDESPLASHES AT ADJOINING WALLS AND/OR OTHER VERTICAL INTERRUPTIONS.
N. ALL OUTBOARD EXPOSED CORNERS OF COUNTERTOPS TO RECEIVE 1 1/2" RADIUS, U.N.O.
O. GENERAL CONTRACTOR IS RESPONSIBLE FOR PROVIDING IN-WALL BLOCKING ADEQUATE FOR THE SUPPORT OF ALL CABINETRY NOTED HEREIN. IN ADDITION, THE CONTRACTOR SHALL PROVIDE ADEQUATE IN-WALL BLOCKING FOR ANY/ALL FINISH CARPENTRY OR ANCILLARY COMPONENTS (INCLUDING BUT NOT LIMITED TO WALL [illegible], MILLWORK, CUSTOM CASEWORK, GRAPHIC PANELS, BANNERS, ETC.) DESIGNATED AND DETAILED HEREIN AS RIGIDLY ATTACHED TO WALL ASSEMBLIES OR OTHER STRUCTURAL COMPONENTS. SEE SPECIFICATIONS FOR BLOCKING REQUIREMENTS. NOTE: SPECIFIC TYPES OF BLOCKING ARE SHOWN IN DETAIL DRAWINGS FOR CLARITY – THIS IS NOT TO BE TAKEN AS A FULL ACCOUNTING. GENERAL/TYPICAL BLOCKING MAY OR MAY NOT BE SHOWN.
P. POWER AND DATA OUTLETS TO BE PROVIDED BELOW COUNTERS, WITH DESKTOP/ACCESS GROMMETS; LOCATIONS TO BE IDENTIFIED IN THE FIELD. ASSUME TWO PER [illegible] LENGTH OF WORKSPACE U.N.O.
Q. ELECTRICAL OUTLETS ARE TO BE 18" A.F.F. AND CENTERED IN SPACES U.N.O. – SEE PME DRAWINGS.
R. LIGHT SWITCHES ARE TO BE CENTERED IN SPACE AND 3'-6" A.F.F. U.N.O. – SEE PME DRAWINGS.
S. PROVIDE BLIND CABINETS WHERE APPLICABLE.
T. PROVIDE SCRIBES / FILLERS BETWEEN ALL WALLS AND CABINET ENDS, U.N.O. PROVIDE MINIMUM 2" FILLERS BETWEEN THE CORNER CABINETS IN AN "L" SHAPE CONFIGURATION.
U. PROVIDE CORNER CLOSURE PIECE UNDER THE WALL CABINETS IN AN "L" SHAPE CONFIGURATION.
V. PROVIDE FINISH ENDS/SIDES FOR ALL EXPOSED END CABINETS.

## CODED NOTES - INTERIOR ELEVATIONS

1. COUNTER MOUNTED SINK - SEE PLUMBING DRAWINGS.
2. WALL MOUNTED SINK - SEE PLUMBING DRAWINGS.
3. P-LAM ADA PLUMBING GUARD - SEE DETAIL.
4. INTEGRATED INSULATION PROTECTION BELOW SINK – SEE PME DRAWINGS.
5. PAPER TOWEL DISPENSER, O.F.C.I. - SEE MOUNTING HEIGHTS.
6. WALL MOUNTED SOAP DISPENSER, O.F.C.I. - SEE MOUNTING HEIGHTS.
7. HAND GEL DISPENSER, O.F.C.I. - SEE MOUNTING HEIGHTS.
8. DESK TOP PHONE - SEE PME DRAWINGS
9. EXISTING/RELOCATED EQUIPMENT TO REMAIN – SEE EQUIPMENT DRAWINGS.
10. NEW EQUIPMENT – SEE EQUIPMENT DRAWINGS.
11. PYXIS MAIN EQUIPMENT TERMINAL - SEE EQUIPMENT DRAWINGS.
12. PYXIS EQUIPMENT - SEE EQUIPMENT DRAWINGS.
13. CLINICAL REFERIGERATOR – SEE EQUIPMENT DRAWINGS.
14. CLINICAL FREEZER – SEE EQUIPMENT DRAWINGS.
15. 36" REFRIGERATOR – SEE EQUIPMENT DRAWINGS.
16. 12" X 12" STACKED PURSE LOCKERS – SEE EQUIPMENT DRAWINGS.
17. PNEUMATIC TUBE STATION – SEE EQUIPMENT DRAWINGS.
18. LIGHT FIXTURE LOCATION – SEE PME DRAWINGS.
19. LIGHT SWITCH LOCATION – SEE PME DRAWINGS.
20. PLUMBING FIXTURE - SEE PME DRAWINGS
21. POWER OUTLET/DATA CONNECTION LOCATION - SEE PME DRAWINGS.
22. FIRE EXTINGUISHER CABINET
23. BASE AS SPECIFIED - SEE FINISH SCHEDULE
24. P-LAM CABINETRY WITH LOCKS ON ALL DOORS AND DRAWERS - SEE FINISH SCHEDULE.
25. P-LAM COUNTERTOP (PL-1) WITH BACK/SIDE SPLASH - SEE FINISH SCHEDULE. PROVIDE GROMMET(S) AS NEEDED AND VERIFY LOCATION(S) WITH OWNER PRIOR TO MANUFACTURING.
26. APRON TO MATCH COUNTERTOP FINISH/MATERIAL
27. TRANSACTION COUNTERTOP - SEE FINISH SCHEDULE.
28. P-LAM WALL CABINETRY WITH BLOCKING - SEE CASEWORK DETAILS.
29. P-LAM FILLER PANELS - SEE FINISH SCHEDULE.
30. P-LAM END PANEL SUPPORT – SEE FINISH SCHEDULE.
31. LINE OF PLASTIC LAMINATED SLOPED TOP - SEE CASEWORK DETAILS.
32. LINE OF SOFFIT - SEE REFLECTED CEILING PLANS.
33. DASHED LINE OF PENCIL DRAWER – SEE FURNITURE SPECIFICATIONS
34. CONCEALED STEEL ANGLE MOUNTING BRACKET - SEE SECTION DETAIL.
35. SURFACE MOUNTED STEEL COUNTERTOP SUPPORT BRACKET – SEE SECTION DETAIL.
36. SHELF AND ROD (PL-1) - SEE DETAIL.
37. ADA SHELF AND ROD (PL-1) - SEE DETAIL.
38. RIGID SHEET WALL PROTECTION (WP-1) - SEE FINISH SCHEDULE.
39. CORNERGUARD - SEE FINISH SCHEDULE

Grady

Project
CASS Pharmacies

88 Jesse Hill Drive
Atlanta, GA 30303

Prepared For
GRADY HEALTH SYSTEM

Hellmuth, Obata & Kassabaum, Inc.
133 Peachtree Street, NE, Suite 4800
Atlanta, GA 30303 USA
t +1 404 439 9000 f +1 404 439 9001

All reproduction & intellectual property rights reserved © 2019

In Association with

Key Plan




Professional Seals

**NOT FOR CONSTRUCTION**

| No. | Description | Date |
|---|---|---|
| 1 | DD - GMP | 2019-07-03 |

Project No: 18534.01

Sheet Title

FINISH LEGEND, SCHEDULE & ELEVATIONS - PHARMACY

Original is 30 x 42. Do not scale contents of this drawing.

Sheet Number
PH900

7/1/2019 2:29:05 PM

Order Plans @ WWW.LDLine.com