**ROOF PLAN NOTES**

1. GENERAL CONTRACTOR TO INSTALL AND SEAL ROOF PENETRATIONS, CURBS AND SLEEPERS.
2. HVAC VENDOR TO PROVIDE ROOF CURBS AND VENDOR IS RESPONSIBLE FOR PROVISION/ COORDINATION OF ROOF PENETRATIONS REQUIRED FOR EQUIPMENT INSTALLATION. SEE A541
3. FLASH PLUMBING VENT AND ELECTRICAL PIPES, SEE A541. SEE MECH. AND ELEC. DWGS. FOR LOCATIONS.
5. NEW ROOF MEMBRANE TO BE INSTALLED BY MANUFACTURER APPROVED LICENSED ROOFING CONTRACTOR. REFER TO DETAILS AS INDICATED ON THIS AND OTHER SHEETS.
6. GC TO PROVIDE POWER AND BLOCKING FOR ALL BUILDING SIGNAGE. COORDINATE WITH SIGN VENDOR.
7. ROOF DRAINS AND OVERFLOW DRAINS, SEE A541. SEE ALSO MECH. DWGS.
8. ROOF SCUPPER, SEE A541
9. LINEN CHUTE, SEE A541
10. ROOF SLOPE FOR EPDM TO BE MIN. 1/4" PER 1'-0". COORDINATE WITH ROOF MEMBRANE SUPPLIER.

STANDING SEAM METAL ROOF

1" / 1'-0"

EPDM ROOF SYSTEM

A200 1

BUILDING SIGNAGE

LINEN CHUTE

SLOPE

PROVIDE 5" POLYISO ROOF INSULATION (MIN R-30). ADD ADDITIONAL 1 1/4 LB. EPS UNDERNEATH AS NECESSARY TO ACHIEVE DESIRED ROOF SLOPE OF 1/4" PER FOOT.

3'-0" WIDE WALKWAY PADS PER ROOD MANUFACTURER'S REQUIREMENT FOR WARRANTY - PROVIDE PADS TO ALL MECHANICAL EQUIPEMENT AS REQUIRED.

3'-0"

RD ORD

1'-6"

1'-0"

A201 2

A201 1

ROOF SCUPPER

CRICKET AS REQ.

(16 SQ. FT. MIN.)

BUILDING SIGNAGE

1 2 3 4 5 6 7 8 8.8 9 9.2 10 11 12 13 14 15 16 16.2 17

A B C D E F G H

1 ROOF PLAN
1/8" = 1'-0"

Order Plans @ WWW.LDILine.com

| No. | Description | Date |
|---|---|---|
| | | |

DISCLAIMER
Meister Architects PC, is providing, by agreement with certain parties, materials stored electronically. The parties recognize that data stored electronically may be modified, altered, or corrupted, intentionally or unintentionally, that documents, or other information recorded on or transmitted as electronic media (including but not necessarily limited to the CAD drawings provided herein) may contain hidden errors or omissions, either intentional or unintentional, due to, among other causes, transmission, conversion, media degradation, software error, or human alteration. Accordingly, all such documents are provided to the parties for informational purposes only and without representation or warranty of any kind. Any reliance thereon is deemed to be a waiver and release of any claims against Meister Architects PC unless a separate agreement is executed by the parties. Service sets are the only true documents of record.

MEISTER·COX ARCHITECTS
INFO@MEISTER-COX.COM
PHONE: 610-375-1331 FAX: 610-375-4555
1522 PENN AVENUE WYOMISSING, PA 19610
WWW.MEISTER-COX.COM

ROOF PLAN

HOLIDAY INN EXPRESS & SUITES
INTERSECTION OF HAYNES PLACE & LAMM RD.
WILSON, NC 27893

| | |
|---|---|
| STATUS: | BIDDING |
| PROJ. DATE: | 06-07-19 |
| PROJ. NO. | 18-176 |
| PRINTED: | 6/7/2019 7:10:26 PM |
| DRAWN BY: | RFF |
| CHECKED BY: | TGC |
| SHEET NO. | A115 |
| SCALE: | 1/8" = 1'-0" |

N:\Active Projects\Hospitality\2018 Holiday Inn Express - Wilson, NC\Drawings CAD-Revit\18-176.rvt