1. ERECT PARTITIONS IN ORDER OF RATING PRIORITY BEGINNING WITH HIGHEST RATED PARTITION. CONSTRUCTION OF HIGHER RATED PARTITIONS SHALL BE CONTINUOUS PAST OR THROUGH LOWER RATED INTERSECTING PARTITION.
2. WATER-RESISTANT GYPSUM BACKING BOARD SHALL BE USED BEHIND AND 2'-0" IN EACH DIRECTION FROM THE CENTERLINES OF ALL PLUMBING FIXTURES WHERE NO CERAMIC TILE SCHEDULED UNLESS OTHERWISE NOTED.
3. CEMENTITIOUS BACKERBOARD SHALL BE USED AT ALL CERAMIC TILE SHOWER LOCATIONS UNLESS OTHERWISE NOTED. GLASS MAT FACED BACKER BOARD SHALL BE USED IN ALL OTHER LOCATIONS TO RECEIVE TILE FINISHES UNLESS OTHERWISE NOTED.
4. METAL STUDS BEHIND CERAMIC TILE INSTALLATIONS SHALL BE A MIN. THICKNESS OF 20 GAGE.
5. FIRE BLOCKING NOT REQUIRED IN NON-COMBUSTIBLE FRAMING PER NORTH CAROLINA STATE BUILDING CODE SECTION 717.2.
6. SEE PLANS FOR LOCATIONS OF SMOKE BARRIERS, SMOKE PARTITIONS AND RATED PARTITIONS.
7. REFER TO TESTING AGENCIES FIRE RESISTANCE DIRECTORY, CURRENT EDITION FOR SPECIFIC CONSTRUCTION REQUIREMENTS OF LISTED ASSEMBLIES.
8. GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING FIRE AND SMOKE SEALED PENETRATIONS IN ACCORDANCE WITH A TESTED AND APPROVED PENETRATION SEALING SYSTEM SPECIFIC FOR THE PARTITION, FIRE RATING AND THE PENETRATING ELEMENTS.
9. CABLES PENETRATING RATED PARTITIONS WITH OR WITHOUT SLEEVES SHALL BE SECURED ON BOTH SIDES OF THE PARTITION. METHOD OF SECURING THE CABLES SHALL BE AS NECESSARY TO PRECLUDE ANY MOVEMENT OF THE CABLE DISTURBING THE INTEGRITY OF THE PENETRATION FIRE-STOPPING ASSEMBLY.
10. ALL PARTITIONS NOTED FOR ACOUSTICAL BATTS, PROVIDE FLEXIBLE SEALANT AT ALL INTERSECTIONS OF GYPSUM BOARD TO OTHER MATERIALS AND AT ALL PENETRATIONS. OFFSET ALL OUTLET BOXES AND PROVIDE STUD BARRIERS BETWEEN BOXES PER GYPSUM ASSOCIATION PUBLICATION GA-600, LATEST EDITION.
11. FOR WALL FRAMING FOR FIRE DAMPERS IN RATED WALLS, COORDINATE EXACT FRAMING REQUIREMENTS WITH FIRE DAMPER MANUFACTURER.

PARTITION NOTES



PARTITION KEY

PARTITION 0SF4B | 0 HR | 1 1/2" = 1'-0"



NOT RATED

PARTITION 0SF4A | 0 HR | 1 1/2" = 1'-0"



NOT RATED

PARTITION 0SF4B | 0 HR | 1 1/2" = 1'-0"



NOT RATED

PARTITION 0SF4A | 0 HR | 1 1/2" = 1'-0"



NOT RATED

PARTITION 0SF2A | 0 HR | 1 1/2" = 1'-0"



NOT RATED

STC RATING: 40
SOUND TEST: NGC 2013022
STUDS @ 16" O.C.

PARTITION 0S6 | 0 HR | 1 1/2" = 1'-0"

PARTITION 0S4B | 0 HR | 1 1/2" = 1'-0"



NOT RATED

PARTITION 0S4A | 0 HR | 1 1/2" = 1'-0"

PARTITION 0S4B | 0 HR | 1 1/2" = 1'-0"



NOT RATED

STC RATING: 46
SOUND TEST: NGC 2015005
STUDS @ 16" O.C.

PARTITION 0S4 | 0 HR | 1 1/2" = 1'-0"

Order Plans @ www.LDILine.com

ODa
overcash demmitt
2010 south tryon st. suite 1a
charlotte north carolina 28203
office.704.332.1615
web.www.odarch.com

STEPHEN F. OVERCASH
REGISTERED ARCHITECT
19576
NORTH CAROLINA
CHARLOTTE
06.27.2019

Hustle House

ODA Project No. 183324

Charlotte, NC

FOR CONSTRUCTION

06.28.2019

REVISIONS

No.	Description	Date
	FOR CONSTRUCTION	06.28.19

BUILDING ASSEMBLIES

G-201