



- ACCESS CONTROL AND SURVEILLANCE VIDEO**
- ① FOB READER
  - ② MAGLOCK (BY OTHERS)
  - ③ ELECTRIC STRIKE (BY OTHERS)
  - ④ TELEPHONE ENTRY PANEL DOORING 1837  
(1) DATA CABLE TO MCR OR BCR FOR PHONE  
(1) DATA CABLE TO MCR OR BCR FOR DATA
  - ⑤ INDOOR IP MEGAPIXEL CAMERA - PoE 5 MP MIN  
(1) DATA CABLE TO MCR OR BCR AS NOTED
  - ⑥ OUTDOOR IP MEGAPIXEL CAMERA - PoE 5 MP MIN  
(1) DATA CABLE TO MCR OR BCR AS NOTED
  - ⑦ ELEVATOR CAMERA FROM TRAVEL CABLE INTERFACE IN EMR TO NEAREST BCR VIA (1) 1" CONDUIT  
(2) CAT6 CABLES  
(1) RG-6 CABLE  
(1) 6 STRAND SINGLE MODE FIBER

\* SEE SHEET T-200 FOR CAMERA MOUNTING TYPE DETAILS \*

XX — CAMERA TYPE  
 XX — MOUNTING TYPE  
 MOUNTING TYPE:  
 1A - WALL MOUNTED CAMERA - MOUNT @ A MIN. 10'-0" A.F.F.  
 1B - CEILING MOUNTED CAMERA  
 1C - FLUSH MOUNTED CAMERA

① 00-GROUND FLOOR PLAN

SCALE: 3/32" = 1'-0"

**CAMERA NOTES:**  
 1. ALL ELEVATORS IN PARKING DECK WILL HAVE (1) CAMERA LOCATED IN EACH CAB "NOT SHOWN ON SCHEDULE".  
 2. SEE MAIN BUILDING FOR ADDITIONAL CAMERAS "NOT SHOWN ON SCHEDULE".

LYRIC AT NORTON COMMONS - CAMERA/BCR								4 CAMERAS
RISER/BCR	GROUND FLOOR	FIRST FLOOR	SECOND FLOOR	THIRD FLOOR	FOURTH FLOOR	FIFTH FLOOR	TOTAL CAMERAS	
BCR 1H	3	1	0	0	0	0	4	
							4	

**READER NOTES:**  
 1. ELEVATOR 1 WILL HAVE (1) READER LOCATED IN THE CAB "NOT SHOWN ON SCHEDULE". ELEVATOR 2 WILL NOT HAVE A READER IN THE CAB SINCE THE GARAGE IS SECURED AT EVERY LEVEL.  
 2. SEE MAIN BUILDING FOR ADDITIONAL READERS "NOT SHOWN ON SCHEDULE".

LYRIC AT NORTON COMMONS - READER/BCR								10 READERS
RISER/BCR	GROUND FLOOR	FIRST FLOOR	SECOND FLOOR	THIRD FLOOR	FOURTH FLOOR	FIFTH FLOOR	TOTAL READERS	
BCR 1H	2	2	2	2	2	0	10	
							10	

**CAMERA AND ACCESS CONTROL NOTES:**  
 1. THE CAMERAS AND ACCESS CONTROL LOCATED IN BCR 1H WILL BE REQUIRED TO BE RAN BACK TO THE NETWORK SWITCH IN THE MCR LOCATED IN BUILDING 3 ONCE THIS PHASE HAS BEEN COMPLETED.  
 2. BOTH THE DKS 1837 ACCESS CONTROLLER AND CAMERA SWITCH WILL BE WIRED BACK TO THE MCR OVER FIBER ONLY.  
 3. THE NVR WILL BE TEMPORARILY LOCATED IN BCR 1H, ONCE THE MCR IN BUILDING 3 HAS BEEN COMPLETED THE NVR WILL NEED TO BE LOCATED IN THE MCR.  
 4. A COMPUTER TOWER AND MONITOR WILL NEED TO BE TEMPORARILY ADDED IN BCR 1H.

Order Plans @ www.LDILine.com

**INFINISYS**  
**MULTIFAMILY TECHNOLOGY**  
 1825 Business Park Blvd, Suite 204  
 Daytona Beach, FL 32114 USA  
 386.236.1500  
 E-Mail: [cam@infm.com](mailto:cam@infm.com)

NOTICE: This drawing is the property of INFINISYS. All information that is not generally known shall be confidential except to the extent the information has been previously established. This drawing may not be reproduced, copied, or used as the basis for manufacture or sale without written permission. This design is an architectural CAD drawing provided by charlan brock associates, for this project and are used with their permission.  
 Copyright 2019 Infinsys. All rights reserved.

Lyric at Norton Commons  
 Prospect, Kentucky  
 Bristol Development Group  
 381 MacIlroy Station Rd, Suite 204  
 Franklin, TN 37067

**charlan • brock associates**  
 architects • planners  
 1770 fennell street  
 maitland florida 32751 7208  
 407.660.8900 f:407.875.9948  
 www.cbarchitects.com

LOW VOLTAGE  
 GROUND FLOOR  
 PLAN

date: 01-11-2019  
 job no: 3789.15  
 drawn by: G.UBIENSKI  
 reviewed by: T.STENDER  
 issue history:  
 Δ Date

SCHEMATIC SET  
**T-100**