



- GENERAL NOTES:**
- E.C. TO LABEL EACH RECEPTACLE AND EXHAUST FAN SWITCH WITH CIRCUIT NUMBER AND INTENDED USE.
 - ALL GFI RECEPTACLES SHALL BE DUPLEX RECEPTACLES. NO WIRED INDICATOR LIGHT. LEVITON #6596-W OR APPROVED EQUAL. NO FEED-THRU PROTECTION PERMITTED. SEE DETAIL 2E1.
 - WHERE WEATHERPROOF COVERS ARE DENOTED, PROVIDE GLE-IN-LAKE COVERS. ALL RECEPTACLES SHALL BE MOUNTED 18" AFF. UNLESS OTHERWISE NOTED.
 - E.C. TO COORDINATE INSTALLATION OF ALL ROOF LIGHTING FIXTURES WITH ROOFING CONTRACTOR TO PROVIDE A STRUCTURALLY SOUND AND WEATHERPROOF "LEAK FREE" INSTALLATION. ALL CONDUITS IN PARAPET WALL, NO EXPOSED CONDUITS OR EXTRA ROOF PENETRATIONS.
- KEYNOTES:** (X)
- MAIN DISCONNECT PROVIDED WITH UNIT. POWERED CONVENIENCE OUTLET PROVIDED WITH UNIT.
 - E.C. SHALL PROVIDE COMPLETE CONDUIT/CONDUCTOR SYSTEM FROM MDP TO UNIT VIA DISCONNECT.
 - OWNER SHALL PROVIDE COMPLETE CONDUIT/CONDUCTOR SYSTEM FROM MDP TO SINGLE POINT CONNECTION AT UNIT.
 - PROVIDE SUPPORT RACK ATTACHED TO UNIT AS REQUIRED TO MOUNT ELECTRICAL EQUIPMENT.
 - E.C. SHALL PROVIDE (6) LIGHTING FIXTURES (BASIS OF DESIGN - VAPOLET VFM420LW-LP-PG). PROVIDE WEATHERPROOF SWITCH WITH TIMER NEAR ACCESS LADDER AND DOOR. FIXTURES AND SWITCHES TO BE SURFACE MOUNTED 6" BELOW TOP OF WALL OR 48" ABOVE FLOOR IN TOWER. PROVIDE COMPLETE CONDUIT/CONDUCTOR SYSTEM FOR FIXTURES AND SWITCHES BACK TO POWER PANEL IN ELECTRICAL ROOM.
 - ELECTRICAL CONTRACTOR SHALL REFER TO DETAIL 2E3 FOR INSTALLATION OF ANTENNAS ON TOWER WALL.

1 ELECTRICAL ROOF POWER & LIGHTING PLAN
E3 1/4" = 1'-0"

Order Plans @ WWW.LDILINE.COM

1925 Prospect Ave.
Orlando, FL 32814
P (407) 661-9100
F (407) 661-9101
www.c-p.com

4
Chalaci & Peterson
Architects Engineers Planners

CLIENT NAME
WAWA
260 W. BALTIMORE PIKE
WAWA, PA 19063

PROJECT NAME
W50FB-VA 2018 01-MA
STORE #6668-SUD
10891 DAVIDSON PLACE
MANASSAS, VA 20109

SHEET TITLE
ELECT. ROOF POWER & LIGHTING PLAN

| No. | Description | Date |
|-----|-----------------|------------|
| 1 | PERMIT SET | 01/04/2019 |
| 1 | PERMIT COMMENTS | 03/15/2019 |
| | BID SET | 06/27/2019 |

PROJECT NO.
2170354

DATE
01/04/2019

DRAWN
M.L.B.

CHECKED
J.P.M.