

EQUIPMENT & FIXTURE SCHEDULE

SHEET NOTES:

NO.	QNTY	ACCESSORIES & OPERATIONS	MANUFACTURER	MODEL NUMBER	PROVIDED BY	INSTALLED BY	CONNECTED BY	NOTES
A1.0	(1)	POST MIX ICE/BEVERAGE DISPENSER - 8 HEAD	CORNELIUS	INTELLICARB 2323	-	VENDOR	-	WITH DROP IN ICE BIN; PEPSI
A2.0	(1)	(2) VALVE, MINUTE MAID, JUICE DISPENSER	LANCER	85-3332	-	VENDOR	-	WITH PORTION CONTROL; CDCA COLA
A3.0	(1)	INTEGRITY AUTOMATIC AIRPOD COFFEE BREWER	BLOOMFIELD	8773	-	VENDOR	-	INCLUDE (3) 775SS-ALM SITE GLASS AIRPOTS; ROYAL CUP
A4.0	(3)	APW WARMER, FOOD, ELECTRIC	APW WYOTT	W-5V	-	CS	-	
A5.0	(1)	TEA BREWER	BUNN	T86	-	VENDOR	-	ROYAL CUP
A5.1	(2)	4 GALLON TEA DISPENSING URNS	BUNN	TDD-N-4	-	VENDOR	-	ROYAL CUP
A6.0	(1)	POS W/ CASH DRAWER	RTG	-	-	OPS	-	
A6.1	(2)	POS	RTG	-	-	OPS	-	
A7.0	(1)	CORDESS PHONE HANDSET & REMOTE BASE	-	-	-	VENDOR	-	
A7.1	(1)	CORDESS PHONE HANDSET & PRIMARY BASE	-	-	-	VENDOR	-	
A8.0	(1)	15'X30.5'X54" CUSTOM MILLWORK TO GO CABINET	-	-	-	CS	-	
A9.0	(5)	11X22 TRASH CAN	RUBBERMAID (3C)	SLIM JIM GRAY	-	GC	-	(2) WITH SWING TOPS
A9.1	(2)	CENTURION 35 GALLON TRASH CAN (9.5X19.5X27.5)	CARLISLE	34393523	-	GC	-	
A10.0	(3)	45" TICKET RAIL	PH SPARK	DSR-4	-	GC	-	
A11.0	(2)	2AP (FAST) 1/2 (MODEL 400) BUTTON FRY TIMER	Z640120HFC	-	-	CS	-	
A12.0	(3)	2 PAN; KITCHEN PRINTER (NOT THERMAL)	CONCEPT SERVICES	CUSTOM	-	OPS	-	
A13.0	(3)	(3) PAN; WALL MOUNT CONDIMENT FANS	CONCEPT SERVICES	CUSTOM	-	CS	-	
A13.1	(1)	(4) PAN; WALL MOUNT CONDIMENT FANS	CONCEPT SERVICES	CUSTOM	-	CS	-	
A14.0	(5)	SOAP DISPENSER	BORRICK	B-2111	-	GC	-	
A15.0	(3)	IN-SIGHT TOUCH-LESS HARD ROLL TOWEL DISPENSER	BUNZL	IS409990	-	GC	-	8" WHITE SCOTT ROLL TOWEL
A15.1	(2)	RECESSED TOWEL DISPENSER	BORRICK	B-359	-	GC	-	
A16.0	(1)	COUNTER TOP TO GO CUP DISPENSER	DISPENSE RITE	RFL-1255	-	CS	-	
A17.0	(1)	TO GO LIDS/STRAWS DISPENSER	-	-	-	CS	-	
A18.0	(1)	BUS CART	LAKESIDE	2503	-	VENDOR	-	
A19.0	(-)	BAG IN BOX	-	-	-	VENDOR	-	SODA SUPPLIER; "VERIFY ELECTRICAL WITH VENDOR"
A20.0	(1)	D/CER	NEMCO	56500-1	-	CS	-	
A21.0	(1)	SLICER	NEMCO	56600-2	-	CS	-	
A22.0	(1)	BUMP SCREEN	-	-	-	OPS	-	
A23.0	(1)	AIR CURTAIN	MARS	ST048-11A-BG	-	GC	-	WITH 99-014 CONTROLLER; *BY OTHERS
A24.0	(1)	SAFE	CORPORATE SAFE	R20205-SR2	-	CS	-	@ MANAGER'S DESK
A25.0	(1)	WFI	-	-	-	VENDOR	-	@ MANAGER'S DESK
A26.0	(LOT)	DSHWASHER RACK - TRAYS/PANS	VOLRATH	TR2.3.5 AS REQ'D	-	VENDOR	-	DISH AND GLASS
A27.0	(1)	CO2 BULK TANK	NUCOZ	-	-	VENDOR	-	IN LOCKABLE BOLT DOWN WEATHER ENCLOSURE; PAINT TO MATCH EXISTING BUILDING METALS

CONTRACTOR SHALL CONFIRM ALL ELECTRICAL, PLUMBING, GAS, BLOCKING, ETC. REQUIREMENTS WITH EQUIPMENT SUPPLIERS AND VENDORS.

THE ICE MACHINE SHALL BE SET IN PLACE BY KITCHEN EQUIPMENT SUPPLIER. REMOTE CONDENSER SHALL BE SET BY THE CONTRACTOR. REFRIGERATION PIPING, START UP, AND CHECK TO BE DONE BY THE CONTRACTOR. COUNTER TOP EQUIPMENT SHALL BE ON 6" HIGH LEGS, BE SEALED TO COUNTER OR BE PORTABLE.

FLOOR MOUNTED EQUIPMENT SHALL BE ON 6" HIGH LEGS, ON CASTERS OR SEALED TO THE FLOOR.

EQUIPMENT NOT ON CASTERS SHALL BE SEALED TO THE WALL AND/OR TO ADJOINING EQUIPMENT, OR PROVIDE SPACE TO FACILITATE CLEANING.

EVERY ITEM SHALL BE NATIONAL SANITATION FOUNDATION (NSF) APPROVED OR APPROVED EQUAL. ALL FOOD PREP TABLES SHALL BE STAINLESS STEEL. PLASTIC LAMINATE SURFACES SHALL NOT BE USED FOR DIRECT FOOD CONTACT.

ALL FOOD SURFACE EQUIPMENT SHALL BE INSTALLED IN ACCORDANCE WITH THE STANDARDS AND PROCEDURES AS SET FORTH BY NSF. THESE PROCEDURES ARE ILLUSTRATED IN THE INSTALLATION MANUAL FOR FOOD SERVICE EQUIPMENT DEVELOPED BY NSF.

ALL SPLASH BLOCKS SHALL BE 5" AWAY FROM ADJACENT WALL TO AVOID DARK ENCLOSED AREAS OR SPLASH BACKS SHALL BE SEALED TO THE WALL WITH AN APPROVED SILICONE OR SIMILAR CAULKING MATERIAL.

ALL SHELVING FOR SANITARY STORAGE PANS SHALL BE CREATED AT MINIMUM OF 15" ABOVE THE FLOOR AND SHALL BE 1/2" TO 2" FROM ADJACENT WALL AND AISLE TO ALLOW FOR CLEANING.

ALL KITCHEN EQUIPMENT SHALL BE INSTALLED PER THE MANUFACTURERS SPECIFICATIONS.

GC SHALL PROVIDE ALL NECESSARY ANCHORS IN CEILING TOPS FOR EQUIPMENT, ELECTRICAL CORDS, PLUMBING, ETC. CONTRACTORS SHALL COORDINATE WITH OWNER AND KITCHEN EQUIPMENT MANUFACTURER'S WRITTEN INSTRUCTIONS. EQUIPMENT SUPPLIER SHALL BE RESPONSIBLE FOR DELIVERY, UNCRATING AND SETTING IN PLACE OF THE KITCHEN EQUIPMENT. THE GC SHALL MAKE FINAL CONNECTIONS OF THE KITCHEN EQUIPMENT TO PLUMBING AND ELECTRICAL AS REQUIRED.

KITCHEN EQUIPMENT VENDOR SHALL COORDINATE PLANS, SCHEDULES, AND ELEVATIONS.

ISSUED FOR CONSTRUCTION

JOB NO. L1907

NORWOOD ARCHITECTS

807 101051511 NW
Atlanta, Georgia 30318
ph. 478-921-0302 fax. 478-921-0301 www.norwoodarchitects.com

HUDDLE HOUSE
EVO 2000 RESTAURANT
2029 HWY 78 E JASPER, AL
WALKER CO. 35501

NO.	ISSUE DATE
	PERMIT SET 07/12/2019

DRAWING NUMBER
A700
ISSUED FOR CONSTRUCTION

Order Plans

