



- KEY NOTE LEGEND**
- (A) SAWCUT AND REMOVE EXISTING ASPHALT PAVING.
  - (B) REMOVE EXISTING FENCE
  - (C) REMOVE EXISTING STRUCTURE AND CONCRETE PAVING.
  - (D) EXISTING SANITARY SEWER TO REMAIN
  - (E) EXISTING GAS MAIN TO REMAIN
  - (F) EXISTING VAULT TO REMAIN
- DEMOLITION LIMITS

- NOTES:**
1. All existing improvements shall be demolished inside the limits of demolition limits unless specified otherwise.
  2. All existing utilities shall remain UNLESS SHOWN TO BE REMOVED.
  3. Contractor shall safeguard all existing utilities within adjacent right-of-way and constructing limits.
  4. All demolition of existing improvements shall be hauled off and disposed of in a legal manner.
  5. Burning of debris on site is not permitted.
  6. Contractor shall have all utilities located on and adjacent to the site prior to beginning work. all utilities shown are approximate.
  7. Demolished pavement shall be hauled off and disposed of in a legal manner.
  8. Contractor shall sawcut existing paving along construction limits. Contractor shall replace paving in like kind assuring smooth transition and positive drainage.
  9. **Excavations.** All excavations shall be made and kept in compliance with the requirements of the U.S. Department of Labor Occupational Safety and Health Administration (OSHA) as defined in 29 CFR Part 1926 and other appropriate standards and regulations. These regulations require that excavations greater than 5 feet in depth be sloped, benched, sheeted or braced to protect employees working in the excavation against the risk of cave-ins. The contractor shall protect existing structures and improvements from start to finish of excavation.
  10. Excavation safety and proper adherence to Federal, state and local regulations is the responsibility of the excavation contractor. It is the responsibility of the contractor to develop the excavation plan and safety requirements for all excavations associated with this project using the soil conditions at the time of construction to determine the appropriate soil type and protection requirements.
  11. No work shall be permitted beyond the construction limits.
  12. Contractor shall repair any items damaged shown to remain after construction or as a result of construction related activities.

Order Plans @

WWW.LDILine.com

NO.	REVISIONS DESCRIPTION	DATE

<b>SITE DEMOLITION PLAN</b>		<b>HUDDLE HOUSE</b>		U.S. HWY 78, JASPER, AL	
FOR		<b>HUDDLE HOUSE</b>		SANDY SPRINGS, GEORGIA	
DRAWN BY	TT	SCALE	1" = 20'	LAST FIELD SURVEY DATE	1/8/18
CHECKED BY	DAR	DWG. NAME	COORDINATE FILE		
CREW CHIEF	TB	FIELD BOOK/PAGE			

**GONZALEZ - STRENGTH & ASSOCIATES, INC.**  
 CIVIL ENGINEERING, LAND SURVEYING, PLANNING, TRAFFIC & TRANSPORTATION  
 2176 PARKWAY LAKE DRIVE  
 HOOVER, ALABAMA 35244  
 PHONE: (205) 942-2486  
 FAX: (205) 942-3033  
 www.Gonzalez-Strength.com  
 © Copyright 2006

FOR PLAN REVIEW ONLY  
 NOT FOR CONSTRUCTION  
 JUNE 14 2019

DWG. NO.  
**C1 - R0**  
 PROJECT  
**19-0256**