RESERVED FOR CLERK OF COURTS RECORDING INFORMATION

SURVEYOR CERTIFICATION

This plat is a retracement of an existing parcel or parcels of land and does not subdivide or create a new parcel or make any changes to any real property boundaries. The recording information of the documents, maps, plats, or other instruments which created the parcel or parcels are stated hereon. RECORDATION OF THIS PLAT DOES NOT IMPLY APPROVAL OF ANY LOCAL JURISDICTION, AVAILABILITY OF PERMITS, COMPLIANCE WITH LOCAL REGULATIONS OR REQUIREMENTS, OR SUITABILITY FOR ANY USE OR PURPOSE OF THE LAND. Furthermore, the undersigned land surveyor certifies that this plat complies with the minimum technical standards for property surveys in Georgia as set forth in the rules and regulations of the Georgia Board of Registration for Professional Engineers and Land Surveyors and as set forth in O.C.G.A. Section 15-6-67.

Bradley D. Cash
Georgia Registered
Land Surveyor # 2845

SITE PHOTOGRAPHS



① ② ③ ④

VICINITY MAP

SITE LOCATION – LATITUDE: 33° 47' 54.7" LONGITUDE: 83° 44' 44.0"



GENERAL NOTES

THIS SURVEY HAS BEEN PREPARED FOR THE EXCLUSIVE USE OF THE PERSON OR ENTITIES NAMED HEREON. NO EXPRESS OR IMPLIED WARRANTIES WITH RESPECT TO THE INFORMATION SHOWN HEREON IS TO BE EXTENDED TO ANY PERSONS OR ENTITIES OTHER THAN THOSE SHOWN HEREON.

THIS PROPERTY IS NOT LOCATED IN A SPECIAL FLOOD HAZARD AREA BASED ON THE FLOOD INSURANCE RATE MAP FOR THIS AREA. THE MAP NUMBER FOR THIS AREA IS 13297C0170E, AND THE DATE OF SAID MAP IS DECEMBER 8, 2016. THIS DETERMINATION WAS MADE BY GRAPHICALLY DETERMINING THE POSITION OF THIS SITE ON SAID FIRM MAPS UNLESS OTHERWISE NOTED.

DATUM
THE DATUM FOR THIS SITE WAS ESTABLISHED UTILIZING GLOBAL POSITIONING SYSTEMS, AND BASED ON POSITIONAL VALUES FOR THE VIRTUAL REFERENCE STATION NETWORK DEVELOPED BY eGPS SOLUTIONS. THE HORIZONTAL REFERENCE FRAME IS NORTH AMERICAN DATUM OF 1983(HARN)-STATE PLANE COORDINATE SYSTEM OF GEORGIA-WEST ZONE. THE VERTICAL REFERENCE FRAME IS NORTH AMERICAN VERTICAL DATUM OF 1988. ANY DIRECTIONS OR DIMENSIONS SHOWN ARE A RECTANGULAR, GROUND LEVEL PROJECTION OF THE STATE PLANE COORDINATE SYSTEM.

NO ZONING REPORT OR ZONING LETTER WAS PROVIDED TO THE SURVEYOR. THE SITE IS ZONED "BG" (HIGHWAY COMMERCIAL DISTRICT) PER SURVEY REFERENCE NUMBER 2.
THE MINIMUM YARD SETBACKS ARE: FRONT – 35 FEET;
SIDE – 15 FEET; AND REAR – 20 FEET.

PLEASE NOTE: ZONING AND SETBACKS SHOULD BE CONFIRMED AND VERIFIED BY PLANNING AND ZONING PRIOR TO DESIGN OR CONSTRUCTION ACTIVITIES.

THERE ARE NO SPECIMEN TREES ON THIS SITE.

SURVEY REFERENCES

1> ALTA/NSPS ALAND TITLE SURVEY FOR PDM OPERATING ECAMPNY, LLC, ET AL., PREPARED BY GEOSURVEY, LTD., DATED 2/22/2017 AND LAST REVISED 9/21/17.
2> SUBDIVISION PLAT FOR MONROE WMZ PARTNERS, LLC, PREPARED BY GEOSURVEY, LTD., DATED 8/16/2017, RECORDED IN PLAT BOOK 113, PAGE 109.
3> ALTA/NSPS ALAND TITLE SURVEY FOR MONROE WMZ PARTNERS, LLC, PREPARED BY GEOSURVEY, LTD., DATED 8/16/2017 AND LAST REVISED 9/21/17.

TITLE EXCEPTIONS

THE FOLLOWING EXCEPTIONS ARE LISTED IN PART II, SCHEDULE B OF A COMMITMENT FOR TITLE INSURANCE, AS PREPARED BY FIRST AMERICAN TITLE INSURANCE COMPANY, 2–98696, EFFECTIVE DATE 12/26/2018.

(g) Right of Way Easement from R. S. Aycock to The Walton Electric Membership Corporation, a corporation, dated June 1, 1938, recorded March 20, 1940, recorded in Deed Book 22, Page 288, Records of Walton County, Georgia.
AFFECTS SITE– BLANKET EASEMENT.

(h) Right of Way Agreement from R. S. Aycock to Transcontinental Gas Pipe Line Corporation, a Delaware corporation, dated June 14, 1941, filed for record June 24, 1949 at 8:30 a.m., recorded in Deed Book 31, Page 197, aforesaid Records.
DOES NOT AFFECT SITE.

(i) Right of Way Agreement from R. E. Aycock to Transcontinental Gas Pipe Line Corporation, a Delaware corporation, dated September 2, 1965, filed for record September 17, 1965 at 8:30 a.m., recorded in Deed Book 53, Page 208, aforesaid Records.
DOES NOT AFFECT SITE.

(j) Interparcel Access Easement Agreement by and between Wal-Mart Stores East, LP, a Delaware limited partnership, and Evelyn Phillips Ewing a/k/a Della Evelyn Ewing, dated as of June 30, 2003, filed for record July 1, 2003 at 10:14 a.m., recorded in Deed Book 1710, Page 448, aforesaid Records.
DOES NOT AFFECT SITE.

(k) Grading, Construction, Slope and Access Easement Agreement by and between Evelyn Phillips Ewing a/k/a Della Evelyn Ewing and Wal-Mart Stores East, LP, a Delaware limited partnership, dated as of June 30, 2003, filed for record July 1, 2003 at 10:14 a.m., recorded in Deed Book 1710, Page 461, aforesaid Records.
DOES NOT AFFECT SITE.

(l) Consent to Use Easement Area by and between Della Evelyn Ewing, a.k.a. Evelyn Phillips Ewing, Wal-Mart Stores East, LP and Transcontinental Gas Pipe Line Corporation, a Delaware corporation, dated June 30, 2003, filed for record July 1, 2003 at 10:14 a.m., recorded in Deed Book 1710, Page 475, aforesaid Records.
DOES NOT AFFECT SITE.

(m) Conveyance of Access Rights from Evelyn Phillips Ewing a/k/a Della Evelyn Ewing and Wanda J. Ewing, Jr. to Department of Transportation, dated July 25, 2003, filed for record August 28, 2003 at 11:36 a.m., recorded in Deed Book 1788, Page 308, aforesaid Records.
AFFECTS SITE– TRACT ABLE TO PLOT.

(n) Prohibition Agreement and Grant of Easements by and between Monroe WMZ Partners, LLC, a Georgia limited liability company and Home Depot U.S.A., Inc., a Delaware corporation, undated, filed for record June 9, 2006 at 2:50 p.m., recorded in Deed Book 2120, Page 280, aforesaid Records, as amended by that certain First Amendment to Restriction Agreement and Grant of Easements by and between Monroe WMZ Partners, LLC, a Georgia limited liability company and Home Depot U.S.A., Inc., a Delaware corporation, dated as of August 11, 2006, filed for record August 14, 2006 at 12:26 p.m., recorded in Deed Book 2347, Page 54, aforesaid Records, as further amended by that certain Second Amendment to Restriction Agreement and Grant of Easements by and between Monroe WMZ Partners, LLC, a Georgia limited liability company and Home Depot U.S.A., Inc., a Delaware corporation, dated as of January 28, 2010, filed for record February 12, 2010 at 10:25 a.m., recorded in Deed Book 3128, Page 395, aforesaid Records; but omitting any restriction based on race, color, religion, sex, handicap, familial status, or national origin unless and only to the extent that said coverage (a) is exempt under Chapter 42, Section 3607 of the United States Code or (b) relates to handicap but does not discriminate against handicapped persons.
AFFECTS SITE– NOT ABLE TO PLOT.

(o) Right-of-Way Easement from Monroe WMZ Partners, LLC to Walton Electric Membership Corporation, a corporation, dated October 10, 2006, filed for record July 23, 2007 at 8:08 a.m., recorded in Deed Book 2748, Page 406, aforesaid Records.
AFFECTS SITE– BLANKET EASEMENT.

(p) All those matters as disclosed by that certain plat recorded in Plat Book 100, Page 42, aforesaid Records.
AFFECTS SITE– NOT ABLE TO PLOT (DOCUMENT ILLEGIBLE)

(q) All those matters as disclosed by that certain plat recorded in Plat Book 113, Page 109, aforesaid Records.
DOES NOT AFFECT SITE.

(r) All matters as disclosed by that certain survey entitled "ALTA/NSPS Land Title Survey for PDM Operating Company, LLC, Arby's Restaurant Group, Inc., First American Title Insurance Company", prepared by GeoSurvey, Ltd., bearing the seal and certification of Bradley D. Cash, Georgia Registered Land Surveyor No. 2845, dated February 22, 2017, last revised September 21, 2017, being designated as Job No. 20175442.
AFFECTS SITE– AS PLOTTED.

LEGEND

STANDARD ABBREVIATIONS

A/C	AIR CONDITIONER
B/V	BOBBY VALVE
BSL	BUILDING SETBACK LINE
C	CURB INLET
CMP	CORRUGATED METAL PIPE
CMF	CONCRETE MONUMENT FND
CO	SANITARY CLEANOUT
CPED	COMMUNICATION PEDESTAL
CTP	CRIMPED TOP PIPE
DI	DROP INLET
DIP	DUCTILE IRON PIPE
DWCB	DOUBLE WING CATCH BASIN
FNC	FENCE
FND	FOUND
GM	GAS METER
WM	WATER METER
JB	JUNCTION BOX
MH	MANHOLE
OHP	OVERHEAD POWER
OTP	OPEN TOP PIPE
PM	POWER METER
POB	POINT OF BEGINNING
POC	POINT OF COMMENCEMENT
RCP	REINFORCED CONCRETE PIPE
RBR	IRON REINFORCING BAR
RRS	5/8"ROBAR SET
SS	SANITARY SEWER
SWCB	SINGLE WING CATCH BASIN
TRANS	ELECTRIC TRANSFORMER

STANDARD SYMBOLS

- OVERHEAD TRAFFIC SIGNAL LIGHT
- POWER POLE
- GUY WIRE
- POWER LINE
- LIGHT POLE
- ELECTRIC TRANSFORMER
- WATER VAULT
- GAS VALVE
- GAS METER
- WATER VALVE
- WATER METER
- FIRE HYDRANT
- UNDERGROUND ELECTRIC LINE
- UNDERGROUND GAS LINE
- UNDERGROUND COMMUNICATION LINE
- UNDERGROUND WATER LINE
- PHOTO POSITION INDICATOR
- REGULAR PARKING SPACE COUNT
- TRAFFIC SIGNAL BOX
- TREE POSITION INDICATOR



PROPERTY DESCRIPTION

All that tract or parcel of land lying or being in Land Lots 28 and 29, 3rd District, City of Monroe, Walton County, Georgia, and being more particularly described as follows:

Commencing at the intersection of the southwesterly right-of-way of Georgia Highway 138/Spring Street (variable right-of-way) and the southeasterly right-of-way of West Spring Street (variable right-of-way); thence along said right-of-way of West Spring Street North 49 degrees 20 minutes 00 seconds West, 182.77 feet to a 1/2-inch rebar with cap found (Georgia West Zone Coordinates of North 1,391,803.66, East 2,424,844.50); thence, said point being the True Point of Beginning; thence leaving said right-of-way of West Spring Street North 40 degrees 40 minutes 00 seconds West a distance of 196.00 feet to a point; thence departing said right-of-way North 49 degrees 03 minutes 42 seconds East, a distance of 263.94 feet to a point; thence South 29 degrees 23 minutes 23 seconds East, a distance of 62.50 feet to a point; thence South 41 degrees 08 minutes 10 seconds East, a distance of 107.19 feet to a 1/2-inch rebar with cap found; thence South 47 degrees 40 minutes 39 seconds West, a distance of 31.97 feet to a point; thence South 50 degrees 15 minutes 11 seconds West, a distance of 76.89 feet to a point; thence South 53 degrees 35 minutes 34 seconds West, a distance of 58.99 feet to a point; thence South 49 degrees 30 minutes 08 seconds West, a distance of 60.77 feet to a point, said point being the True Point of Beginning.

Said tract of land contains 0.923 Acres.

ALTA SURVEYOR CERTIFICATION

To: Southbound Development Group, Inc.
First American Title Insurance Company

This is to certify that this map or plat and the survey on which it is based were made in accordance with the 2016 Minimum Standard Detail Requirements for ALTA/NSPS Land Title Surveys, jointly established and adopted by ALTA and NSPS, and includes Items 1, 2, 3, 4, 5, 6(a), 7(a), 7(b-1), 8, 9, 11, & 13 of Table A thereof. The field work was completed on February 21, 2019.

Date: February 21, 2019

Bradley D. Cash
Georgia Registered
Land Surveyor # 2845

UTILITY NOTE

THE UNDERGROUND UTILITIES SHOWN HEREON ARE BASED ON LOCATION OF MARKINGS PROVIDED BY:

UTILISURVEY, LLC
154 GRANT ROAD
FAYETTEVILLE, GEORGIA 30215

THE UNDERGROUND UTILITIES (EXCEPT THE LOCATION OF EXISTING DRAINAGE, SEWER AND IRRIGATION UTILITIES AS WELL AS UNDERGROUND FUEL STORAGES TANKS) WERE LOCATED BY UTILISURVEY, LLC, UTILIZING RADIO FREQUENCY TECHNIQUE. THIS TECHNIQUE IS CAPABLE OF LOCATING METALLIC UTILITIES AND TRACER WIRES. ANY NON-METALLIC UTILITIES (WITHOUT TRACER WIRE) ARE NOT LOCATED.

THE SURVEYOR MAKES NO GUARANTEES THAT THE UNDERGROUND UTILITIES SHOWN COMPRISE ALL SUCH UTILITIES IN THE AREA, EITHER IN-SERVICE OR ABANDONED. UNDERGROUND UTILITIES NOT OBSERVED OR REPORTED UTILIZING THIS TECHNIQUE MAY EXIST ON THIS SITE BUT NOT BE SHOWN AND MAY BE FOUND UPON EXCAVATION. THE SURVEYOR FURTHERMORE NOT WARRANT THAT THE UNDERGROUND UTILITIES SHOWN ARE IN THE EXACT LOCATION INDICATED ALTHOUGH THE SURVEYOR DOES CERTIFY THAT THEY ARE LOCATED AS ACCURATELY AS POSSIBLE FROM INFORMATION AVAILABLE.

INFORMATION REGARDING MATERIAL AND SIZE OF UTILITIES IS BASED ON RECORDS ACQUIRED FROM THE UTILITY OWNERS.

IF YOU DIG

811 Know what's **below.** **Call** before you dig. Dial 811 Or Call 800-282-7411

UTILITY PROVIDERS

Gas
City of Monroe
215 North Broad Street
Monroe, GA 30655
(770) 267-1429
Chris Schmitt

Electric
City of Monroe
215 North Broad Street
Monroe, GA
(770) 267-1429
Chris Schmitt

Water
City of Monroe
215 North Broad Street
Monroe, GA 30655
(770) 267-1429
Chris Schmitt

Construction
City of Monroe
215 North Broad Street
Monroe, GA 30655
(770) 267-1429
Chris Schmitt

Wastestream Communication
750 N Jefferson St NE
Milledgeville, GA 31061
(888) 599-1166
www.windstream.com

Comcast
(770) 559-6879
Sandra Adamss

GRAPHIC SCALE

0 15 30 75 150
1" = 30'

CLOSURE STATEMENT

THE FIELD CLOSURE UPON WHICH THIS PLAT IS BASED WAS A CLOSURE PRECISION OF ONE FOOT IN 66,726, AND WAS ADJUSTED USING THE LEAST SQUARES METHOD. A TRIMBLE S+8 TOTAL STATION AND TRIMBLE TSC-3 DATA COLLECTOR WERE USED TO COLLECT THE FIELD DATA.

THIS PLAT HAS BEEN CALCULATED FOR CLOSURE AND WAS FOUND TO BE ACCURATE WITHIN ONE FOOT IN 225,424 FEET. BDC, PLS.

GeoSurvey, Ltd.
Land Surveying • 3D Laser Scanning
1660 Barnes Mill Road
Marietta, Georgia 30062
Phone: (770) 795-9900
Fax: (770) 795-8880
www.geosurvey.com
EMAIL: info@geosurvey.com
Certificate of Authorization #LSF-000621

ALTA/NSPS LAND TITLE SURVEY OF

#2130 West Spring Street

FOR

Southbound Development Group, Inc.

First American Title Insurance Company

GS JOB NO:	20175442	DRAWING SCALE:	1"= 30'
FIELD WORK:	MN	CITY: MONROE	STATE: GA
DRAWN BY:	EDC	COUNTY:	WALTON
REVIEWED:	JRC	LAND LOT:	29 & 8
DWG FILE: 20175442-04.dwg		DISTRICT:	3rd

SURVEY DATE: 2/21/2019

No.	Date	Description
REVISIONS		

Order Plans @ WWW.LDLine.com

PREPARED BY
Kimley»Horn
© 2019 KIMLEY-HORN AND ASSOCIATES, INC.
3930 ELLIS ROAD, SUITE 350
PEACHTREE CORNERS, GEORGIA 30092
PHONE (770) 825-0744
WWW.KIMLEY-HORN.COM

PREPARED FOR
SOUTHBOUND DEVELOPMENT GROUP
3542 VANET ROAD,
ATLANTA, GA 30341
PHONE: (404) 987-2402

PROJECT
SPRING STREET EXCHANGE
MONROE OUTPARCEL
2130 WEST SPRING STREET, MONROE, GA 30656
LAND LOT 8, 3 DISTRICT

No.	ISSUANCE AND REVISION DESCRIPTIONS	DATE	BY

GEORGIA REGISTERED PROFESSIONAL ENGINEER No. 033045 PROFESSIONAL LAND SURVEYOR

GSWCC NO. (LEVEL II)	0000022363
DRAWN BY	DEW
DESIGNED BY	RWB
REVIEWED BY	BLH
DATE	08/08/2019
PROJECT NO.	014023009

TITLE
SURVEY

SHEET NUMBER
C0-01

Drawing name: K:\ATL_Civil\014023009_Monroe, GA\CAD\PlanSheets\C0-00 - CIVIL COVER SHEET.dwg C0-01 - GENERAL NOTES Aug 06, 2019 10:56am by: david.woodson

This document, together with the concepts and designs presented herein, as an instrument of service, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Kimley-Horn and Associates, Inc. shall be without liability to Kimley-Horn and Associates, Inc.