RUSKIN®

2800 Dr. Greenes Rd. • Kansas City, MO 64120 • (816) 761-7476 • FAX (816) 765-8955

INSTALLATION INSTRUCTIONS
1½ HOUR UL CLASSIFIED
CURTAIN TYPE FIRE DAMPERS
MODELS CFD-1HEDZ, IBDT, IBDT1, and IBDT2

APPLICATION

This fire damper shall be shown on this sheet and installed with a 1½ hour fire damper label and are approved for use in fire walls or floors with ratings of less than 3 hours. Fire Dampers require a fusible or factory-installed sleeve. Select a sleeve of sufficient length to permit attachment with perforated mounting angles, to duct work on each side of wall or floor opening.

(All sizes apply to galvanized and stainless steel construction unless indicated otherwise)

DYNAMIC FIRE DAMPERS – Listed and Classified models

See detail on damper for maximum air flow and pressure.

MODEL CFD-1HEDZ MAXIMUM SIZE

Single Section
Vertical or Horizontal Installation – 33"w x 58" h (838 x 914).

Single Section
Out of Wall (vertical) Installation – 20"w x 46"h (508 x 1016)

Multiple Section Assembly
Vertical Installation, galvanized steel construction – 120"w x 90"h (3048 x 1828).
Vertical Installation, stainless steel construction – 86"w x 72"h (2515 x 1829).
Horizontal Installation – 144"w x 30"h or 90"w x 54"h (3048 x 762 or 2286 x 1372).

MODELS IBDT1, IBDT2, AND CFD-1T 6435SW/W SIZE

Single Section
Vertical Installation – 43"w x 49"h (1016 x 1219).

Single Section
Out of Wall (vertical) Installation – 36"w x 42"h (914 x 1219).

MODELS IBDT, IBDT1, AND IBDT2 MAXIMUM SIZE

Single Section
Vertical Installation – 46"w x 46"h (1016 x 1219).
Horizontal Installation – 82"w x 22"h (1854 x 559).

Single Section
Out of Wall (vertical) Installation – 36"w x 48"h (914 x 1219).

INSTALLATION SUPPLEMENTS

Refer to the appropriate Ruskin installation supplement instructions for additional requirements:

- S-and-Difference No. 14050
- Electrical
- Sealing of Openings in Fire Rated Walls or Floors
- Mullion Frame-Mounting Angles
- Metal Stud Framing for Fire Dampers in Drywall Partitions
- Metal Stud Framing for Fire Dampers in Drywall Design No. HW08
- Wood Stud Framing for Fire Dampers in Drywall Partitions

Note:
Optional side sleeve has preformed 1" x 3" elongated slots for attachment to adjacent damper. Sleeve and damper are factory assembled. Field assembly not required.

Ductwork flow: Ruskin CFD-1HEDZ, IBDT, IBDT1, IBDT2 dampers are designed to close against airflow in either direction.

Ductwork flow: Ruskin CFD-1HEDZ, IBDT, IBDT1, IBDT2 dampers are designed to close against airflow in either direction.

Dimensions: Inches (millimeters)

Tolerances: Fractional ± 1/16", two place decimals ± .02", three place decimals ± .010", millimeters ± 0.5 mm.

Specifications subject to change without notice.

Printed in U.S.A.

1. **Responsible Clearances**
   Responsible clearances as outlined for UL fire penetration-rated assemblies. This opening is the wall or floor must be a minimum of ½" per foot (1" per 305) larger than the overall damper/sleeve assembly size for galvanized steel damper, and a minimum ¾" per foot (6 per 305) for stainless steel damper. The maximum opening size is 2" (51) larger than this minimum clearance dimensional value. Example: Opening for a 24" x 24" damper/sleeve assembly can be 26½" x 26½" minimum up to 28½" x 28½" maximum. All openings must be at least ½" (6) larger than the damper/sleeve assembly.

2. **Fasteners and Mullion Section Assembly**
   Use No. 10 (M5) bolts or screws, ½" (13) long, with integral washers or equivalent as illustrated in figures 2 and 4, and spaced as follows when joining individual damper to make multiple section mullion assemblies or when fastening damper to duct sleeve:
   Vertical Mount (in wall):
   Galvanized steel dampers — 12" (305) spacing
   Stainless steel dampers — 8" (203) spacing
   Horizontal Mount (in floor):
   All dampers — 8" (203) spacing
   Multiple section horizontal mount dampers require a 14 gage thick x 4½" (2 x 114) wide steel mullion plate approximately between the damper frames with ¼" (13) long welds staggered approximately and spaced on maximum 8" (152) centers. The mullion plate must be same material as the damper. The mullion length must be equal to the damper width if less is shown requiring damper fastening. Stiffening are not required for assembly. Blank connecting or two dampers attached end-to-end or three dampers attached side-by-side as illustrated in figure 5.

3. **Duct Wall Installation and Fasteners**
   Dampers are designed to be installed within the wall. In out of wall installation is required the loading edge of the damper frame must be set inside at 11" (279) from the wall but the sleeve shall not reflect more than 15" (406) from the wall. If the damper is to be installed out of the wall, note the following methods. The following shall be followed: 16" (305) c.c. max. minimum 3 per side.
   a. Mounted steel or concrete walls to sheet metal gypboard, use min-mum #10 screws.
   b. In UL439 or UBSF 79-S-11 sheet metal/asbestos saw minimum #10 screws.
   c. In masonry wall construction use #10 self-tapping concrete anchors.

4. **Damper Sleeves**
   Damper sleeve must be minimum 26 gage (.64) up to a maximum 10 gage (3.8) steel. Sleeve thickness must be equal to or thicker than the duct connected to it. Sleeve gage requirements are listed in the SMACNA Fire, Smoke and Radiation Damper Installation Guide For HVAC Systems and in NFPA90A. If a breakaway style (nonsleeve connection is not used, sleeve must be 14 gage (1.8) minimum for dampers up to 36" wide or 24" height and 16 gage (2) minimum when damper exceeds 36" wide or 24" high. Sleeve must be fastened to damper as illustrated in figure 2). Sleeve must not extend more than 6" (152) out of the wall in a Rated Erection – Dampers equipped with factory installed sleeve does may extend 16" (406) out of the wall or floor on the exposed side. Sleeve must terminate on both sides of the wall or floor within the dimensions shown in figures 1 and 3.

5. **Installation for Out of Wall**
   For dampers out of the wall, fiberfrax insulation and the rated gypsum wallboard shall be applied to the top and sides of the sleeve. The fiberfrax insulation shall be minimum 1½" (9) thick and glued (with rubber cement) to top and both sides of sleeve. The fiberfrax shall extend through the wall opening and terminate at the damper frame edge closest to the wall. The fire rated gypsum wallboard shall be a minimum 5/8" (12) thick and shall cover the fiberfrax insulation except it shall not extend through the wall opening. The wallboard shall be attached to the damper sleeves using 2 rows of #8 sheet metal screws spaced a maximum 12" (305) c.c. A minimum of 2 screws per row, per side is required. Each row shall be a maximum 2" (51) from the edge of the wallboard.

5. **Damper Orientation**
   Use "Up Flow" and "Down Flow" labels when using 24" sleeve on Dynamic CFD and IBDT2, consider for proper damper orientation. For blade operation, see arrow on damper end. Ensure proper damper orientation.

7. **Mounting Angles**
   Ruskin Flat-Iron Frame Mounting Angles can be used as shown in the supplemental installation instructions in one of the following conventional mounting angles:
   Galvanized dampers 20" x 66" or 66" x 20" (1676 x 1524 or 1524 x 1676) or smaller require minimum of 1½" x 1½" x 16 gage (38 x 38 x 1.6) conventional mounting angles. Number 1 to 20 gage damper sleeve with No. 10 (M5) bolts or screws, ½" (13) long, lock washers or spot welds as detailed in figures 1 and 3 on sleeve or bottom.
   Galvanized steel dampers — 12" (305) spacing
   Stainless steel dampers — 8" (152) spacing
   Mounting angles shall overlap the wall or floor a minimum of 1" (25). Do not fasten angles together at intersect at ions of the damper/sleeve assembly.

6. **Ductsleeve Connections**
   a. **Break-away Ductsleeve Connections**
   Pocketlock® slips must use one or more of the connections depicted below.
   A minimum of two #10 sheet-metal screws on each side and



   (no bottom), located in the center of the slip gasket and penetrating both sides of the slip gasket may be used. Connections using fixing clips, pop rivets or the like at bottom with fast drive tabs up to 25" (635) long on the radius may also be used.

   b. **Round and Oval Break-away Connections**
   Round and flat oval break-away connections must use screws at 4" (102) wide drawband or 6½" sheet metal screws spaced equally around the circumference or the duct as follows:
   • Duct diameters 22" (559) and smaller = minimum 3 screws.
   • Duct diameters over 22" (559) and including 76" (1549) = Maximum 6 screws.
   • Duct diameters over 76" (1549) and up to and including 191" (4851) total perimeter = Maximum & screws. For flat oval ducts, the diameter is considered the largest (major) dimension of the duct.

   Note: When optional sealing of these joints is desired, the following sealants may be applied in accordance with the sealant manufacturer's instructions:
   Hardcast, Inc. – Iron Grip 601 — Eco-Duct-Seal-44-02
   Proseal — PS20865T

   c. **Flanged Break-away Style Duct Sleeve C connections.**
   Flanged connection systems manufactured by Ductmate, Nexus or Ward are approved break-away connections when installed as depicted.
   TDC (by Lockformed) and TDF (by Single) flanged connections are approved break-away connections when installed per the flange manufacturer's instructions.

   d. **Non Break-away Ductsleeve Connections**
   If other duct sleeve connections are used, the sleeve shall be a minimum of 16 gage (1.6) for dampers up to 36" (914) wide x 24" (610) high and 14 gage (2.0) for dampers exceeding 36" (914) wide x 24" (610) high.

8. **Installation and Maintenance**
   To ensure optimum operation and performance, the damper must be installed as it is square and free from racking. Do not compress or stretch the damper frame into the duct or opening. Lift or handle the damper using sleeve or frame. Do not lift damper using blades. Each fire damper should be examined on a regular basis to ensure it is not jammed or blocked, or in accordance with NFPA recommendations. Care should be exercised to ensure that actuators are performing safely and do not cause system damage.



VERTICAL INSTALLATION

FIGURE 1



FIGURE 2



Drawing depicts damper with field installed sleeve. For dampers with factory installed sleeve, see (S99SDS), 40, 80 Installation Instructions.

HORIZONTAL INSTALLATION

FIGURE 3



FIGURE 4



Drawing depicts damper with field installed sleeve. For dampers with factory installed sleeve, see (S99SDS), 40, 80 Installation Instructions.

(D-)IBDT, IBDT1, IBDT1, IBDT2 OUT OF THE WALL INSTALLATION



RUSKIN®

9900 Dr. Greenes Rd.
Kansas City, MO 64120
(816) 761-7476
www.ruskin.com

INSTALLATION

Refer to applicable Ruskin installation instructions for damper and sleeve.

1. Sleeve
   a. Sleeve to conventional mounting angles
2. Breakaway sleeve to duct connections.
3. Fasteners – 12" (305) c.c. max. minimum 3 per side.
   a. In metal stud or sheet metal walls or drywall partitions, use minimum #10 screws.
   b. In UL439 or UBSF drywall construction use minimum #10 screws.
   c. In masonry wall construction use #10 self tapping concrete anchors.
4. Installation for Out of Wall

For dampers with blades out of the wall, fiberfrax insulation and the rated gypsum wallboard shall be applied to the top and sides of the sleeve. The fiberfrax insulation shall be minimum 1½" (9) thick and glued (with rubber cement) to top and both sides of sleeve. The fiberfrax shall extend through the wall opening and terminate at the damper frame edge closest to the wall. The fire rated gypsum wallboard shall be a minimum 5/8" (12) thick and shall cover the fiberfrax insulation except it shall not extend through the wall opening. The wallboard shall be attached to the damper sleeve using 2 rows of #8 sheet metal screws spaced a maximum 12" (305) c.c. A minimum of 2 screws per row, per side is required. Each row shall be a maximum 2" (51) from the edge of the wallboard.

System No. CAJ1001
(Formerly System No. 49)
F Rating—3 Hr
T Rating—0 Hr



1. **Floor or Wall Assembly**—Min 4-1/2 in. thick lightweight or normal weight (100-150 pcf) concrete. Wall may also be constructed of any UL Classified **Concrete Block** Assembly. Max diam of opening is 25 in.
   See **Concrete Blocks** (CAZT) category in the Fire Resistance Directory for names of manufacturers.
1A. **Steel Sleeve**—(Optional, not shown)—Nom 12 in. (or smaller) Schedule 40 (or heavier) steel pipe sleeve cast into concrete floor or wall. Sleeve may extend a max of 10 in. above top of floor or ground either surface of wall. Sleeve may be used only when floor or wall assembly is min 4-1/2 in. thick. **T Rating is 0 Hr when sleeve is used.**
2. **Pipe or Conduit**—Nom 20 in. (or smaller) steel pipe or conduit. For steel pipe, nom 6 in. diam (or smaller) rigid steel conduit or Type M or heavier copper pipe, nom 4 in. diam (or smaller) cast iron pipe or steel conduit. Max one pipe or conduit per through opening. Max annular space between pipe or conduit and edge of through opening is zero in. (point contact). Pipe or conduit to be rigidly supported on both sides of floor or wall assembly.
3. **Packing Material**—Polyethylene backer rod or nom 1 in. thickness of tightly-packed ceramic (alumina silica) fiber blanket, mineral wool or glass fiber insulation material used as a permanent form. Packing material to be recessed from top surface of floor or from both surfaces of wall as required to accommodate the thickness of caulk fill material (Item 4). As an alternate when pipe size is 10 in. diam or less, when max annular space is 1 in., a min 1 in. thickness of tightly-packed ceramic fiber blanket or mineral-wool batt packing material may be recessed min 1 in. from bottom surface of floor or from either side of wall.
4. **Fill, Void or Cavity Materials**—**Caulk**—Applied to fill the annular space to the min thickness shown in the following table:

Min Pipe Or Conduit Diam In.	Max Pipe Or Conduit Diam In.	Packing Material Type (6) Thickness In.	Min Caulk Thickness In.
1	1	1 CF or MW	1/2 (6)
1	1	CF or MW	1/2 (6)
10	2-1/2	3R, CF, OF or MW	1 (6)

(a) Polyethylene backer rod.
CF—Ceramic fiber blanket.
OF—Glass fiber insulation.
MW—Mineralwool batt.
(b) Caulk installed flush with top surface of floor or both surfaces of wall
(c) Caulk installed flush with bottom surface of floor or one surface of wall
Minnesota Mining & Mfg. Co.—Type CP 25N/S
*Bearing the UL Classification Marking

3M Fire Protection Products
This material was extracted by 3M Fire Protection Products from the 1996 edition of the UL Fire Resistance Directory.

FILE NAME = XHEZ.C-AJ-1001
COPYRIGHT 2004 UNDERWRITERS LABORATORIES, INC.
REPRINTED FROM THE UL ONLINE CERTIFICATIONS DIRECTORY WITH PERMISSION FROM UNDERWRITERS LABORATORIES INC.

System No. CAJ5001
(Formerly System No. 91)
F Ratings—1, 1½, 2 and 3 Hr (See Item 4)
T Ratings—0, 1/2, 3/4, and 1 Hr (See Items 1A and 4)
L Rating At Ambient—2 CFM per sq ft
L Rating At 400 F—less than 1 CFM per sq ft



1. **Floor or Wall Assembly**—Min 2-1/2 in. thick reinforced lightweight or normal weight (100-150) pcf concrete. Wall may also be constructed of any UL Classified **Concrete Blocks**". Max diam of opening is 13 in.
   See **Concrete Blocks** (CAZT) category in the Fire Resistance Directory for names of manufacturers.
1A. **Steel Sleeve**—(Optional, not shown)—Nom 8 in. (or smaller) Schedule 10 (or heavier) steel sleeve cast or grouted into floor or wall assembly. Sleeve may extend a max of 2 in. above top of floor or beyond either surface of wall. Sleeve may be used only when floor or wall assembly is min 4-1/2 in. thick. **T Rating is 0 Hr when sleeve is used.**
2. **Through Penetrant**—Nom 4 in. diam (or smaller) Type L for hard-drawn copper pipe, nom 12 in. diam (or smaller) service weight or heavier) cast iron soil pipe, nom 12 in. diam (or smaller) Class 50 or heavier) ductile iron pressure pipe or nom 12 in. diam (or smaller) Schedule 10 (or heavier) steel pipe contained in the opening and rigidly supported on both sides of the floor or wall assembly.
3. **Pipe Covering**—Nom 1 or 2 in. thick fiberglass cylindrical heavy density (min. 3.5 pcf) glass fiber mat jacketed on the outside with an all service jacket. Longitudinal joints sealed with metal fasteners or factory-applied self-sealing lap tabs. Transverse joints secured with metal fasteners with butt strip tape sealed with the product.
   See **Pipe and Equipment Coverings—Materials**"(S19021) category in Building Materials Directory for names of manufacturers. Any pipe covering material meeting the above specifications and bearing the UL Classification Marking with a Flame Spread Index of 25 or less and a Smoke Developed Index of 50 or less may be used.
4. **Firestop System**—The details of the firestop system shall be as follows:
   A. **Packing Material**—Min 1 in. thickness of firmly packed mineral wool or batt insulation used as a permanent form. Packing material to be recessed from top surface of floor or sleeve or from both surfaces of wall as required to accommodate the required thickness of caulk fill material (Item 5).
   B. **Fill, Void or Cavity Material**"—**Caulk**—Applied to fill the annular space flush with the top surface of the floor or sleeve or flush with both surfaces of wall. When nom pipe covering thickness is 1 in., min thickness of caulk fill material is 1 in. When nom pipe covering thickness is 1 in., min thickness of caulk fill material is 1 in. The fourth F and T Ratings of the firestop system are dependent upon the thickness of the floor or wall, the size of pipe, the thickness of pipe covering material and the size of the annular space (between the pipe covering material and the edge of the circular through opening), as shown in the following table:

Min Floor Or Wall Thickn. In.	Max Pipe Diam In.	Nom Pipe Covering Thickn. In.	Annular Space In.	F Rating Hr	T Rating Hr
2-1/2	4	1	1/2 to 3-3/8	2	1
4-1/2	6	2	1/2 to 3-3/8	2	1-1/2
2-1/2	12	1	1/2 to 1-1/2	3	1/2
4-1/2	12	1	1/2 to 2-3/8	3	1

Minnesota Mining & Mfg. Co.—CP 25WB+.
*Bearing the UL Classification Marking

3M Fire Protection Products
This material was extracted by 3M Fire Protection Products from the 1996 edition of the UL Fire Resistance Directory.

FILE NAME = XHEZ.C-AJ-5001
COPYRIGHT 2004 UNDERWRITERS LABORATORIES, INC.
REPRINTED FROM THE UL ONLINE CERTIFICATIONS DIRECTORY WITH PERMISSION FROM UNDERWRITERS LABORATORIES INC.

NOTE:
DETAILS ARE FOR REFERENCE ONLY. DAMPERS TO BE INSTALLED PER MANUFACTURER'S U.L. APPROVED INSTALLATION INSTRUCTIONS FOR THE DAMPER FURNISHED. DAMPERS TO BE BY RUSKIN, PREFCO, SAFE AIR, NATIONAL CONTROLLED AIR, UNITED AIR, OR NAILOR. FIRESTOPPING PRODUCTS TO BE BY 3M, DOW CORNING, OR CERTAINTEED.

NOTE:
INSTALL FIRE DAMPER IN ACCORDANCE WITH THE MANUFACTURER'S INSTALLATION DETAILS. DO NOT VARY FROM THOSE INSTRUCTIONS IN ANY WAY. DO NOT FIRESTOP THE GAP BETWEEN THE FIRE DAMPER SLEEVE AND THE PENETRATION UNLESS SPECIFICALLY REQUIRED BY THE DAMPER MANUFACTURER'S INSTALLATION INSTRUCTIONS.

NOTE:
REPRINTED FROM THE 2004 FIRE RESISTANCE DIRECTORY WITH PERMISSION FROM UNDERWRITER'S LABORATORIES INC. COPYRIGHT 2004 UNDERWRITER'S LABORATORIES INC.

NOTE:
THIS TYPICAL FIRE/SMOKE DAMPER DETAIL IS GENERIC GUIDANCE ONLY. INSTALL FIRE/SMOKE DAMPER IN ACCORDANCE WITH THE MANUFACTURER'S INSTALLATION DETAILS. DO NOT VARY FROM THOSE INSTRUCTIONS IN ANY WAY. DO NOT FIRESTOP THE GAP BETWEEN THE FIRE/SMOKE DAMPER SLEEVE AND THE PENETRATION UNLESS SPECIFICALLY REQUIRED BY THE MANUFACTURER'S INSTALLATION INSTRUCTIONS.

Order Plans @ WWW.LDILine.com

cra
222 cloister court
chapel hill, nc 27514
919.401.8586
www.cra-ae.com

RN&M ENGINEERS
Reece, Noland & McElrath, Inc.
44 Main Street
Canton, North Carolina 28716

NORTH CAROLINA REGISTERED SEAL 23439 ENGINEER MARK R. MCELRATH

Renovation of
920 Corporate Drive
Orange County Schools
920 Corporate Drive
Hillsborough, North Carolina

no. revisions

The use of these plans and specifications for any purpose not intended by the architect is prohibited. Any use, reproduction or publication by any method, in whole or in part, is prohibited. Title to the plans and specifications remains with the architect and they are not to be used on any other project. Visitors to the site must not rely upon the plans and specifications and construction shall not proceed without the written verification of the contractor.

drawn DJM checked MRM

U.L. DETAILS

sheet
M0.3

project no. 2019016.00

date 7.22.19

Construction Document Bid Set