EQUIPMENT SCHEDULE

ITEM NO	QTY	EQUIPMENT CATEGORY	MANUFACTURER	MODEL NUMBER	EQUIPMENT REMARKS	PLUG	DIRECT	NEMA	ELECTRICAL AFF (IN)	AMPS	HP	VOLTS	PHASE	ELEC REMARKS	HOT WATER SIZE (IN)	HOT WATER AFF (IN)	COLD WATER SIZE (IN)	COLD WATER AFF (IN)	COLD WATER FILT SIZE	DIRECT DRAIN SIZE (IN)	DIRECT DRAIN AFF (IN)	INDIR DRAIN SIZE (IN)	PLUMBING REMARKS	SUPPLIED BY:	SET IN PLACE BY:	FINAL CONNECTION BY:	ITEM NO
1	1	4 COMPARTMENT SINK	JOHN BOOS & CO	-	-	-	-	-	-	-	-	-	-	-	0.5"	18"	0.5"	18"	-	-	-	3"	-	HRS	HRS	GC	1
2	1	2 COMPARTMENT SINK	BK RESOURSES	BKS-2-1620-12-18R	-	-	-	-	-	-	-	-	-	-	0.5"	18"	0.5"	18"	-	-	-	3"	-	HRS	HRS	GC	2
3	48	CHAIR	OWS	M33-BLK	BLACK METAL BACK W/BLACK VYNYL SEAT	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	3
4	1 LOT	WALK-IN COOLER SHELVING	INTERMETRO	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	4
5	2	HAND SINK	JOHN BOOS & CO	PBHSW-14101SSLR	2 SIDE SPLASHES & FAUCET	-	-	-	-	-	-	-	-	-	0.5"	18"	0.5"	18"	-	1.5"	15"	-	-	HRS	GC	GC	5
6.1	2	DUNNAGE RACK	WINHOLT	-	FOR WALK-IN COOLER	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	6.1
6.2	2	FAN RACK	CHANNEL	SSPR-3E	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	6.2
7	1	3' EXHAUST HOOD (CONDENSATE HOOD)	CAPTIVE-AIR	CUSTOM	EXHAUST FAN REQUIREMENTS	-	X	-	DFA	7.0	1/3	120	1	-	-	-	-	-	-	-	-	-	-	HRS	HRS	GC	7
8	1	ICE MAKER	HOSHIZAKI	KM-300BAJ	NO BIN SELF CONTAINED	X	-	5-15P	48"	8.4	-	115	1	-	-	-	-	36"	0.5"	-	-	3"	GC TO PROVIDE DRAIN & SUPPLY LINES	HRS	HRS	GC	8
9	1	MICROWAVE	PANASONIC	NE1054	-	X	-	5-15P	24"	13.4	-	120	1	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	9
10	1	MOP SINK	-	CUSTOM	BY OTHERS	-	-	-	-	-	-	-	-	-	0.5"	36"	0.5"	36"	-	-	-	4"	HRS TO SUPPLY SERVICE FAUCET	HRS	GC	GC	10
11	3	18" WORK TABLE	BK RESOURSES	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	11
12.1	1	FOOD PROCESSOR	ROBOT COUPE	R2NCLR	FINE SERRATED BLADE	X	-	5-15P	24"	7.0	1	120	1	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	12.1
12.2	1	FOOD PROCESSOR	ROBOT COUPE	CL50E	-	X	-	5-15P	24"	12.0	1 1/2	120	1	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	12.2
13	2	2 TIER WIRE SHELVING (24"/24"D X 6'W)	INTERMETRO	-	INSTALLED BY GC	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	GC	NA	13
14	3	CONVEYOR TOASTER	PRINCE CASTLE	297-T12P	-	X	-	5-15P	24"	13.0	-	120	1	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	14
15	1	POS MILLWORK (3'10"W X 30"D)	CUSTOM	-	FINISHES TO BE DETERMINED BY OWNER	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	15
16	1	MANAGER DESK	CUSTOM	-	BY OWNER	X	-	5-15P	48"	15.0	-	120	1	-	-	-	-	-	-	-	-	-	-	OWNER	OWNER	NA	16
17	2	4' WORK TABLE	BK RESOURSES	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	17
18	1 LOT	DRY STORAGE	INTERMETRO	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	18
19.1	2	72" MEGA TOP SANDWICH PREP - DRAWERS LEFT	CONTINENTAL	SW72-30M-FB-D	-	X	-	5-15P	24"	9.0	1/4	120	1	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	19.1
19.2	1	72" MEGA TOP SANDWICH PREP - DRAWERS RIGHT	CONTINENTAL	SW72-30M-FB-D	-	X	-	5-15P	24"	9.0	1/4	120	1	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	19.2
20	2	SOUP WARMER	VOLLRATH	72090	-	X	-	5-15P	24"	12.0	-	120	1	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	20
21	2	6' WORK TABLE	BK RESOURSES	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	21
22	21	TABLE TOP (2'W X 30"D)	EVERYDAY	-	LAMINATE TABLE TOP	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	22
23.1	4	SINGLE BOOTH SEAT	AAF	-	BLACK VINYL - 42" HIGH	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	23.1
23.2	2	DOUBLE BOOTH SEAT	AAF	-	BLACK VINYL - 42" HIGH	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	23.2
24	1	2 TIER WIRE SHELVING (21"/24"D X 6'W)	INTERMETRO	-	BACKER BOARD IN THE WALL REQUIRED	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	24
25	1	2 TIER WIRE SHELVING (21"/24"D X 6'W)	INTERMETRO	-	BACKER BOARD IN THE WALL REQUIRED	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	25
26	10	TABLE TOP (30"W X 4'D)	EVERYDAY	-	LAMINATE TABLE TOP	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	26
27	1	POS MILLWORK (9'6"W X 30"D)	CUSTOM	-	FINISHES TO BE DETERMINED BY OWNER	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	27
28	5	POS	BY OTHERS	-	VERIFY REQUIREMENTS W/ OWNER	X	-	5-15P	18"	15.0	-	120	1	-	-	-	-	-	-	-	-	-	-	OWNER	OWNER	OWNER	28
29	1	REACH-IN REFRIGERATOR	TRUE	T-23-HC	-	X	-	5-15P	48"	3.0	1/3	120	1	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	29
30	1	WALK-IN COOLER (10' X 12')	NORLAKE	-	CONDENSING UNIT	-	X	-	DFA	31.7	3	208-230	3	-	-	-	-	-	-	-	-	-	-	HRS	GC	GC	30
30A	1	WALK-IN COOLER	NORLAKE	-	EVAPORATOR COIL, LIGHTS, SWITCH & DOOR HEATER	-	X	-	DFA	3.2	1/4	115	1	-	-	-	-	-	-	-	-	3"	-	HRS	HRS	GC	30A
31	2	TRASH RECEPTACLE	CUSTOM	-	FINISHES TO BE DETERMINED BY OWNER	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	31
32	6	CUP DISPENSER	DISPENSE RITE	SLR-2 (7 1/8" RING)	MOUNTED BACK OF POS COUNTER(5 1/4" CUT OUT)	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	32
33	1	FOOD MIXER	GLOBE	SP8	-	X	-	5-15P	84"	5.0	1/4	120	1	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	33
34	1	DOUBLE STACK STEAMER	ACCUTEMP	E62083E150 DBL	STAND INCLUDED/REQUIRED PSI 30-60	X	-	14-50P	96"	42.0	-	208	3	DOUBLE POWER SUPPLY	-	-	-	18"	0.75"	-	-	3"	DOUBLE DRAIN LINES/SINGLE WATER SUPPLY	HRS	HRS	GC	34
35	1	WORKTOP FREEZER 67 1/4"	TRUE	TWT-67F	-	X	-	5-15P	24"	7.0	1/2	120	1	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	35
36	1	2 TIER WIRE SHELVING (21"/24"D X 9'W)	INTERMETRO	-	BACKER BOARD IN THE WALL REQUIRED	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	36
37	1	2 TIER WIRE SHELVING (21"/24"D X 17'W)	INTERMETRO	-	BACKER BOARD IN THE WALL REQUIRED	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	37
38	1	ICE MACHINE @ BEVERAGE STATION	HOSHIZAKI	KMD-860MAJ	3 WIRE WITH NEUTRAL FOR 115V, STANDARD	X	-	-	84"	9.9	-	208-230	1	GC TO PROVIDE ELECTRICAL CORD	-	-	-	78"	0.5"	-	-	3"	GC TO PROVIDE DRAIN & SUPPLY LINES	HRS	GC	GC	38
39	1	BENCH SEAT (8'6"W X 18"D)	AAF	-	BLACK VINYL - NO BACK	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	39
40	1	2 DOOR REACH-IN REFRIGERATOR	TRUE	T-49-HC	-	X	-	5-15P	48"	5.8	1/3	120	1	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	40
41	1	BEVERAGE DISPENSER	BY VENDOR	-	VERIFY REQUIRMENTS W/ VENDOR	X	-	5-15P	24"	15.0	-	120	1	-	-	-	-	-	-	-	-	3"	-	VENDOR	VENDOR	VENDOR	41
42	1	BAG-N-BOX	BY VENDOR	-	VERIFY REQUIRMENTS W/ VENDOR	X	-	5-15P	96"	15.0	-	120	1	-	-	-	-	84"	0.75"	-	-	-	-	VENDOR	VENDOR	VENDOR	42
43	1	TEA URN DRAIN	CUSTOM	-	DRAIN FOR TEA URNS TO DROP INTO BEV STATION	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	3"	GC TO PROVIDE DRAIN & SUPPLY LINES	HRS	HRS	GC	43
44	2	TEA URN	BY VENDOR	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	VENDOR	VENDOR	VENDOR	44
45	1	BEVERAGE COUNTER (8'6"W X 3'D)	CUSTOM	-	FINISHES TO BE DETERMINED BY OWNER	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	45
46	1	BEVERAGE TOWER/ICE BIN	BY VENDOR	-	VERIFY REQUIRMENTS W/ VENDOR	X	-	5-15P	48"	15.0	-	120	1	-	-	-	-	-	-	-	-	3"	-	VENDOR	VENDOR	VENDOR	46
47	1	TEA BREWER	BY VENDOR	-	VERIFY REQUIRMENTS W/ VENDOR	X	-	5-15P	48"	15.0	-	120	1	-	-	-	-	48"	0.5"	-	-	-	-	VENDOR	VENDOR	VENDOR	47
48	2	LEMONADE BUBBLER	CRATHCO	D15-3	VERIFY REQUIREMENTS W/ VENDOR	X	-	5-15P	48"	3.0	-	120	1	-	-	-	-	-	-	-	-	-	-	VENDOR	VENDOR	VENDOR	48
49	1	CONDIMENT BIN (23"D X 15'W)	CUSTOM	-	COLOR OF CONDIMENT BIN SEE STATION	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	49
50	1	SMART WALL DRYING RACK (2'D X 6'W)	INTERMETRO	-	BACKER BOARD IN THE WALL REQUIRED	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	50
51	1	BACK COUNTER MILLWORK (24'W X 18"D)	CUSTOM	-	FINISHES TO BE DETERMINED BY OWNER	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	51
52	1	1 TIER WIRE SHELVING (24"D X 8'W)	INTERMETRO	-	BACKER BOARD IN THE WALL REQUIRED	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	52
53.1	1	PASS THRU WINDOW (8'W X 23"D)	M FAB	-	COORDINATE FIELD DIMENSIONS	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	53.1
53.2	1	PASS THRU WINDOW (3'W X 23"D)	M FAB	-	COORDINATE FIELD DIMENSIONS	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	53.2
54	1	OPEN AIR REFRIGERATED DISPLAY	STRUCTURAL CONCEPTS	CO45R	-	X	-	5-20P	18"	16.0	1/2	120	1	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	54
55	1	WATER FILTRATION SYSTEM	EVERPURE	EV9437-10	USE CLEAR BOWLS	-	-	-	-	-	-	-	-	-	-	-	0.75"	96"	-	-	-	-	-	HRS	GC	GC	55
56	1	27" UNDERCOUNTER REFRIGERATOR	TRUE	TUC-27-HC	-	X	-	5-15P	24"	2.0	-	115	1	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	56
57	1	2 TIER WIRE SHELVING (21"/24"D X 6'W)	INTERMETRO	-	BACKER BOARD IN THE WALL REQUIRED	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	57
58	1	1 TIER WIRE SHELVING (24"D X 5'W)	INTERMETRO	-	BACKER BOARD IN THE WALL REQUIRED	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	58
59	1	SINGLE BOOTH SEAT (16'7"W X 18"D)	AAF	-	BLACK VINYL - 42" HIGH	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	59
60	1	SINGLE BOOTH SEAT (30'10"W X 18"D)	AAF	-	BLACK VINYL - 42" HIGH	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	60
61	1 LOT	CHAIR	TS	HC-DM	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	61
62	3	3' WORK TABLE	BK RESOURSES	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	HRS	HRS	NA	62
GP	1	GENERAL PURPOSE OUTLET	-	-	VERIFY WITH OWNER	X	-	5-15P	48"	15.0	-	120	1	24" HIGH ON LOW WALL IN KITCHEN	-	-	-	-	-	-	-	-	-	-	-	-	GP
NA	1	WATER HEATER	BY MC	-	VERIFY REQUIREMENTS W/ MC	-	-	-	-	-	-	-	-	-	0.75"	-	0.75"	-	-	-	-	3"	-	GC	GC	GC	NA
NA	1	CO2 TANK	BY VENDOR	-	VERIFY REQUIREMENTS W/ VENDOR	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	-	VENDOR	VENDOR	VENDOR	NA

IG = ISOLATED GROUND
JB = JUNCTION BOX
MC = MECHANICAL CONTRACTOR
GC = GENERAL CONTRACTOR
HRS = HOTEL & RESTAURANT SUPPLY
FD = FLOOR DRAIN
FSD = FLOOR SINK DRAIN
AFF = ABOVE FINSHED FLOOR
DFA = DROP FROM ABOVE
SU = STUB UP
GP = GENERAL PURPOSE OUTLET

General Notes

1. It is the intent of the floor plan and related detail drawings to show approximate location and size of equipment and fixtures specified. The rough-in drawings are derived from the floor plan and indicate approximate outlet locations, connection position, and load requirements. While all of the drawings were prepared and drawn as accurately as possible, it is the responsibility of the kitchen equipment contractor working with general contractor to verify all of the above conditions prior to submittal of detailed floor plan, shop drawings, and dimensioned rough-in plans.
2. Prior to commencing work the mechanical contractors shall request dimensioned rough-in plans from the Kitchen Equipment Contractor.
3. All sizes given for food services equipment and fixtures on drawings and in written specifications are approximate. The Kitchen Equipment contractor working with general contractor shall verify all measurements at the job site prior to issuance of purchase orders for equipment.
4. Any changes or relocations of equipment, plumbing, electrical or mechanical services due to structural considerations shall be submitted to Chicken Salad Chick for review and approval before proceeding with work.

EXHAUST HOOD
A: EXHAUST & SUPPLY DUCT FROM HOOD TO FANS WELDED BY MECHANICAL CONTRACTOR.
B: ALL ROOF PENETRATION BY MECHANICAL CONTRACTOR.
C. GAS SHUT OFF VALVE FURNISHED BY HOTEL & RESTAURANT SUPPLY. - N/A
D: ELECTRIC SHUNT TO ACCOMODATE ELECTRIC EQUIPMENT - BY ELECTRICAL CONTRACTOR

WALK-IN COOLER/FREEZER
A: GENERAL CONTRACTOR TO APPROVE & VERIFY FIELD DIMENSIONS.
B: WALK-IN FREEZER - NA

REFUSE
TYPICALLY 26 YARDS OF DEBRIS & PACKING MATERIAL NEEDED AT JOB SITE - BY GEN CONTRACTOR

FOOD SERVICE EQUIPMENT DATA
REFERENCE ONLY -
NOT FOR CONSTRUCTION

Order Plans @ WWW.LDLine.com

jb A
jared bussey architect
1604 28th Ave South
Birmingham, AL 35209
205.533.3563

JARED BUSSEY ARCHITECT AGRICULTURE COMMERCE NO. 105577 STATE OF TENNESSEE

Chicken Salad Chick
Cleveland, Tennessee

Bradley Square Mall, Building H
200 Paul Huff Parkway NW
Cleveland, Tennessee 37312

No.	Revision	Date

Client:
J. Hudson Sandefur

Project Location:
200 Paul Huff Pkwy NW
Cleveland, Tennessee
37312

DATE: July 19, 2019
DRAWING TITLE: Equipment Data
PROJECT NUMBER: 31-19
FILE NUMBER: 31-19 CSC Cleveland.rvt
SHEET of
DRAWING NUMBER
A2.3