

FOOD SERVICE EQUIPMENT DATA

Item No.	QTY	Description	Supply						Drain			
			Hot Water		Cold Water		Filtered Water		Direct		Indirect	
			Size (in)	AFF (in)	Size (in)	AFF (in)	Size (in)	AFF (in)	Size (in)	AFF (in)	Size (in)	
01	1	4 Compartment Sink	0.5"	18"	0.5"	18"	-	-	-	-	-	3"
02	1	2 Compartment Sink	0.5"	18"	0.5"	18"	-	-	-	-	-	3"
05	2	Hand Sink	0.5"	18"	0.5"	18"	-	-	1.5"	15"	-	-
08	1	Ice Maker	-	-	-	-	0.5"	36"	-	-	-	3"
10	1	Mop Sink	0.5"	36"	0.5"	36"	-	-	4"	-	-	-
30A	1	Walk-In Cooler Evaporator	-	-	-	-	-	-	-	-	-	3"
34	1	Steamer	-	-	-	-	0.75"	18"	-	-	-	3"
38	1	Ice Machine @ Beverage Station	-	-	-	-	0.5"	78"	-	-	-	3"
41	1	Beverage Dispenser	-	-	-	-	0.5"	18"	-	-	-	3"
42	1	Bag-N-Box	-	-	-	-	0.75"	84"	-	-	-	-
43	1	Tea Urn Drain	-	-	-	-	-	-	-	-	-	3"
46	1	Beverage Tower / Ice Bin	-	-	-	-	0.5"	18"	-	-	-	3"
47	1	Tea Brewer	-	-	-	-	0.5"	48"	-	-	-	-
55	1	Water Filter	-	-	0.75"	96"	-	-	-	-	-	-

Refer To FS Drawings For Contractor Responsibility Matrix.

PLUMBING SCHEDULES

PLUMBING FIXTURE SCHEDULE										
ITEM	DESCRIPTION	MFG.	MODEL NO.	PIPE SIZES				REMARKS		
				WASTE	VENT	CW	HW			
P-1	WATER CLOSET	AMERICAN STANDARD	CADET 2467.016	4"	2"	1/2"	-	PRESSURE ASSISTED, 1.6 GAL. PER FLUSH, OPEN FRONT SEAT. CONFORM TO ADA MOUNT RIM HEIGHT AT 17" AFF.		
P-1R	WATER CLOSET	AMERICAN STANDARD	CADET 2467.016	4"	2"	1/2"	-	SAME AS P-1 EXCEPT RIGHT HAND FLUSH LEVER.		
P-2	LAVATORY	AMERICAN STANDARD	LUCERNE 0355.012	1-1/2"	1-1/2"	1/2"	1/2"	MOUNT RIM HEIGHT AT 34" AFF. PROVIDE FAUCET EQUAL TO AMERICAN STANDARD 1480.150 (0.5 GPM SEVA SINGLE CONTROL CENTERSET)		
WH	WATER HEATER (INTERIOR UNIT)	RINNAI	RUC98i	-	-	3/4"	3/4"	MAX INPUT = 199,000 Btu/H, 3/4" GAS CONNECTION. COUPLE WITH MCC-91-1US CONTROLLER SET AT 140 DEG. F. PROVIDE EZ CONNECT ACCESSORY TO ALLOW THE 2 HEATERS TO FUNCTION AS ONE. ELECTRICAL = 120V, 1 PHASE. PROVIDE / INSTALL WITH MANUFACTURER'S CONDENSATE NEUTRALIZER KIT.		
P-4	THERMOSTATIC MIXING VALVE	ACORN	ST70-12	-	-	1/2"	1/2"	SET OUTLET TEMPERATURE AT 105 DEG F.		
10	MOP SINK	SEE REMARKS	SEE REMARKS	-	-	-	-	SUPPLIED BY G.C. INSTALL PER MANUFACTURER'S INSTRUCTIONS.		

NOTES:
1. Provide Insulated PVC Wrap Kit On Hot And Cold Water Supplies And Traps At All Lavatories And Sinks.

DRAIN AND SPECIALTY SCHEDULE					
ITEM	DESCRIPTION	MANUFACTURER	MODEL	REMARKS	
FD	FLOOR DRAIN	J.R. SMITH	225-H04	PVC FLOOR DRAIN, 8" ROUND PVC GRATE.	
FS	FLOOR SINK	J.R. SMITH	305-14-13	PVC FLOOR SINK WITH 8" ROUND PVC GRATE AND 305-14 DOME BOTTOM STRAINER	
WCO	WALL CLEANOUT	J.R. SMITH	4020	DIPCO CAST IRON BODY WITH ROUND POLISHED NICKEL BRONZE TOP, TAPER THREAD AND BRONZE PLUG	
FCO	FLOOR CLEANOUT	J.R. SMITH	4436	DIPCO CAST IRON BODY WITH BRONZE TAPER PLUG AND ROUND, CHROME PLATED BRONZE FRAME AND COVER.	

Order Plans @ www.LDOnline.com



jb A
jared bussey
architect

1604 28th Ave South
Birmingham, AL 35209
205.533.3563



Daniel P. Bier
7/30/2019

dlb associates
CONSULTING ENGINEERS, P.C.
3290 Cumberland Club Drive, Suite 300
Atlanta, GA 30338
Questions For dlb Call: Andrew Bier
DLB Project ID: 26198 Phone: (732) 927-5023

Chicken Salad Chick
Cleveland, Tennessee
Bradley Square Mall, Building H
200 Paul Huff Parkway NW
Cleveland, Tennessee 37312

Client:
J. Hudson Sandefur
Project Location:
200 Paul Huff Pkwy NW
Cleveland, Tennessee
37312

DATE: July 30, 2019
DRAWING TITLE: Schedules
PROJECT NUMBER: 03-18
FILE NUMBER:
SHEET of
DRAWING NUMBER
P4.1