



NOTES

- COORDINATE ALL DEMOLITION WORK WITH NEW WORK AND WITH FINAL MERCHANDISE PLAN.
- THE GENERAL CONTRACTOR SHALL REVIEW THE ENTIRE DRAWING SET WITH THE CVS PROJECT MANAGER AND VERIFY ALL PROPOSED WORK AND MEASUREMENTS IN THE FIELD PRIOR TO THE START OF CONSTRUCTION.
- NOTIFY THE ARCHITECT OF ANY DISCREPANCIES IN PLAN.
- DEMOLISH ITEMS IN A WORKMAN-LIKE MANNER FROM TOP TO BOTTOM OR AS NEEDED TO PREVENT COLLAPSE. TAKE CARE TO PREVENT DAMAGE TO SURROUNDING CONSTRUCTION. DO NOT DEMOLISH ANY ITEM THAT MAY BE STRUCTURAL IN NATURE, IF SUCH ITEMS ARE ENCOUNTERED CONTACT THE ARCHITECT FOR DIRECTION PRIOR TO DEMOLISHING THE ITEM.

LEGEND

- EXISTING PARTITION TO REMAIN
- EXISTING PARTITION TO BE DEMOLISHED
- EXISTING FIXTURES, MILLWORK AND ETC. TO BE DEMOLISHED
- KEY NOTE DESIGNATION
- DOOR IDENTIFIER
- COLOR GRID
- RE/RELO: RELOCATE
D/DEMO: DEMOLISH
- NOTE: ALL WALLS, DOORS, AND WINDOWS WITHOUT A SYMBOL DESIGNATION ARE EXISTING TO REMAIN.

NOTES BY SYMBOL

- REMOVE EXISTING DOOR, FRAME, AND HARDWARE
- REMOVE EXISTING AISLE MARKERS AND INSERTS, CATEGORY SIGNS, HANGING GRAPHICS, AND GREETING CARD GRAPHICS.
- REMOVE AND/OR RELOCATE MERCHANDISE FIXTURES AND END PANELS SHOWN DASHED. COORDINATE LOCATION AS SHOWN ON MERCHANDISE PLAN.
- REMOVE ANY EXPOSED WALL COVERING THROUGH RETAIL, SKIM COAT WALLS AND PREPARE FOR NEW FINISH.
- REMOVE WALLS SHOWN HATCHED IN THEIR ENTIRETY
- REMOVE FURNISHINGS AND EQUIPMENT FROM EXISTING RHC.
- REMOVE ALL BLUE WAITING CHAIRS. RED WAITING CHAIRS TO BE RELOCATED.
- REMOVE CHECK-IN STATION AT MINUTE CLINICS.
- FRONT CHECKOUT TO BE REMOVED IN IT'S ENTIRETY. SEE FTP FOR EQUIPMENT TO BE REUSED.
- REMOVE PHOTOLAB MILLWORK IN IT'S ENTIRETY SAVE ALL EQUIPMENT FOR REUSE AS NEEDED PER FTP.
- CUT PORTION OF EXISTING WALL FOR NEW DOOR LOCATION
- RELOCATE ACCESSIBILITY SIGNAGE
- REMOVE WALLPAPER AND FRP FROM HALL WALLS.
- REMOVE ALL FLOOR FINISHES AND WALL BASES THROUGHOUT RETAIL, FRONT CHECKOUTS, PHOTOLAB, COOLERS, HALL, RHC, AND PHARMACY. PREP FLOORS FOR NEW FINISHES.
- REMOVE FRONT CHECKOUT GATE
- REMOVE ALL MILLWORK, PLUMBING AND FINISHES FROM EXISTING EMPLOYEE AREA.
- REMOVE EXISTING DOOR AND REPLACE WITH NEW

1 DEMOLITION FLOOR PLAN
AD1 1/8" = 1'-0"



STORE NUMBER: 4522
800 EAST WEST CONNECTOR
AUSTELL, GA
PROJECT TYPE: Health Hub and Reset
DEAL TYPE:
CS PROJECT NUMBER: 134320

ARCHITECT OF RECORD

www.littleonline.com

This drawing and the design ideas are the property of Little Architecture, Inc. No reproduction, copying or other use of this drawing without their written consent is prohibited and any infringement will be subject to legal action.

CONSULTANT:

DEVELOPER:

SEAL:

REVISIONS:

CVS PROJECT MANAGER: SB
DRAWING BY: JC
DATE: 07-22-2019
JOB NUMBER: 121-12600-08
TITLE:
DEMOLITION FLOOR PLAN

SHEET NUMBER: AD1

COMMENTS: