



- NOTES**
- INSTALL NEW/RELOCATE POWER POLES. REFERENCE ELECTRICAL DWGS.
 - EXISTING PERIMETER SIGNAGE TO BE CONSISTENT WITH CURRENT CVS STANDARDS. GC AND CVS CPM TO COORDINATE DEMO, RELOCATION, AND/OR RE-USE OF ALL EXISTING GRAPHICS.
 - RELOCATION OF EXISTING SECURITY CAMERAS, MOTION DETECTORS, AND SECURITY EQUIPMENT BY CVS VENDOR. GC SHALL COORDINATE INSTALLATION WITH VENDOR.
 - REPLACE ANY STAINED OR DAMAGED CEILING TILE THROUGHOUT ENTIRE STORE AS DETERMINED DURING PRE-BID WALKTHROUGH.
 - REPAIR OR REPLACE ANY DAMAGED OR INOPERABLE LIGHT FIXTURES AS REQUIRED.
 - RELO/INSTALL NEW AISLE MARKERS PER CVS SET-UP MANAGER.
 - CLEAN ALL EXISTING HVAC DIFFUSERS AND LIGHT FIXTURE LENSES THROUGHOUT THE ENTIRE STORE.
 - GENERAL CONTRACTOR SHALL COORDINATE REVISED CEILING GRID AND LIGHTING FIXTURE LOCATIONS WITH EXISTING CEILING DIFFUSERS AND REGISTERS. GC SHALL RELOCATE DIFFUSERS AND REGISTERS AS REQUIRED TO FACILITATE CEILING GRID MODIFICATIONS AND/OR RELOCATION OF LIGHT FIXTURES. PROVIDE ADDITIONAL SHEET METAL, FLEX DUCT, HANGERS AND ACCESSORIES AS REQUIRED TO RELOCATE AIR TERMINAL DEVICES. HVAC AIR TERMINAL DEVICES TO BE MODIFIED SHALL CONFORM TO SMACNA STANDARDS. UPON PROJECT COMPLETION, AIR TERMINAL DEVICES AND MINIMUM 5' OF ASSOCIATED BRANCH DUCTWORK SHALL BE CLEANED FREE OF DUST AND DEBRIS. MODIFICATION TO EXISTING VENTILATION AIR FLOW SHALL NOT BE PERMITTED.
 - GC SHALL RELOCATE SPRINKLER HEADS AS REQUIRED TO FACILITATE CEILING GRID MODIFICATIONS AND/OR RELOCATION OF LIGHT FIXTURES. PROVIDE ADDITIONAL PIPING, HANGERS AND ACCESSORIES AS REQUIRED TO FACILITATE SPRINKLER PIPING MODIFICATIONS. PROTECTED SPRINKLER SYSTEM MODIFICATIONS SHALL CONFORM TO NFPA 13 INSTALLATION AND OPERATION STANDARDS. FIRE SUPPRESSION SYSTEM DRAWINGS SHALL BE PREPARED BY A LICENSED FIRE PROTECTION CONTRACTOR AS REQUIRED BY THE AUTHORITIES HAVING JURISDICTION.

LEGEND

	EXISTING PARTITION TO REMAIN		GYPSUM WALLBOARD CEILING TO BE DEMOLISHED
	PARTITION TO BE DEMOLISHED		ACoustical CEILING TILE AND CEILING GRID TO BE DEMOLISHED
	KEY NOTE DESIGNATION		EXISTING ACoustical CEILING TILE TO REMAIN
	COLUMN GRID		FIXTURE DESIGNATIONS
			EXISTING TO REMAIN
			DEMOLISH
			RELOCATE

CEILING FIXTURE SCHEDULE

SYMBOL	DESCRIPTION
EX	EXISTING 2X4 RECESSED PARABOLIC
EX	EXISTING 1X4 RECESSED PARABOLIC
EX	EXISTING 4' RECESSED WALL WASHER
EX	EXISTING 8' STRIP
EX	EXISTING 4' STRIP
EX	EXISTING SURFACE MOUNT EMERGENCY
EX	EXISTING SURFACE MOUNT EXIT SIGN WITH EMERGENCY BATTERY BUG EYES LIGHT FIXTURE
	HVAC SUPPLY
	HVAC RETURN
	EXHAUST FAN/ COMBO FIXTURE

- NOTES BY SYMBOL**
- CLEAN HVAC SUPPLY/RETURN DIFFUSERS.
 - GC SHALL COORDINATE FIRE ALARM SYSTEM MODIFICATIONS WITH THE CVS VENDOR AND RELOCATE EXISTING STROBES AS REQUIRED.
 - REMOVE PERIMETER LIGHTING AND MODIFY ACoustical CEILING TILE AS NEEDED.
 - REMOVE ALL PIN LETTERS, EXCEPT PHARMACY.
 - EXISTING CLINICS TO BE MODIFIED. ALL EXISTING A.C.T. AND LIGHTS TO BE REMOVED. REUSE LIGHTS.
 - SPLIT SYSTEM UNIT IN EMPLOYEE ROOM TO BE RELOCATED.

1 DEMOLITION FLOOR PLAN
AD2 1/8" = 1'-0"



STORE NUMBER: 4522
800 EAST WEST CONNECTOR
AUSTELL, GA
PROJECT TYPE: Health Hub and Reset
DEAL TYPE:
CS PROJECT NUMBER: 134320

ARCHITECT OF RECORD

www.littleonline.com

This drawing and the design therein are the property of Little Architectural Consulting. The reproduction, copying or other use of this drawing without their written consent is prohibited and any infringement will be subject to legal action.

CONSULTANT:

DEVELOPER:

SEAL:

7/22/19

REVISIONS:

CVS PROJECT MANAGER: SB
DRAWING BY: JC
DATE: 07-22-2019
JOB NUMBER: 121-12600-08
TITLE: DEMOLITION REFLECTED CEILING PLAN
SHEET NUMBER: AD2
COMMENTS: