

Order Plans @

| INTERIOR FINISH SCHEDULE | | | | | |
|--|-----------------------------|---------------------------------|-----------------------------|--------------------------------------|--|
| TAG | MATERIAL / DESCRIPTION | MFR. | STYLE/ CAT. NO. | COLOR | NOTES |
| ACOUSTICAL | | | | | |
| CA1 | CEILING TILE | ARMSTRONG | 769 | WHITE | 2 x 4 PANELS |
| FLOORING | | | | | |
| FF5 | MODULAR CARPET | INTERFACE | 190F302500 CUSTOM | #180527 | QUARTER TURN. REFER TO CARPET TILE SPEC. |
| FF6 | MODULAR CARPET | INTERFACE | 190F302500 CUSTOM | #180668 | QUARTER TURN. REFER TO CARPET TILE SPEC. |
| FF7 | CUSHION-BACK CARPET TILES | INTERFACE | 242847 | #180668 BLACK | INSTALL WITH RANDOM PATTERN |
| FF8 | LUXURY VINYL TILE | INTERFACE | ARMSTRONG PARALLEL 20 | ARGENT CRV (#203) | REFER TO CARPET TILE SPEC. |
| FF12 | RIBBED ENTRANCE TILES | INTERFACE | DECO-RIB 62301 | #602371 ANTHRACITE | REFER TO CARPET TILE SPEC. |
| FF16 | RUBBER WALL BASE | BURKEMERCER | 4GL COVE | 701 BLACK | |
| FF18 | RUBBER WALL BASE | ROPPE | PINNACLE - STANDARD NO TOE | LIGHT BROWN 147 | |
| FF20 | LUXURY VINYL TILE | INTERFACE | NATURAL WOODGRAINS | A00211 WASHED MAPLE | |
| CERAMIC TILE | | | | | |
| CT6 | CERAMIC TILE | DALTILE CONTACT. (877) 556-5728 | VOL. 1 | DEGREES SILVER VL71 | COVE BASE 6x12. LATICRETE 24 NATURAL GREY NON SANDED GROUT 1/8" |
| CT7 | CERAMIC TILE | DALTILE CONTACT. (877) 556-5728 | SEVERINO | CENERE FOG SV98 | FLOOR TILE 12x12. LATICRETE 24 NATURAL GREY NON SANDED GROUT 1/8" |
| CT8 | CERAMIC TILE | DALTILE CONTACT. (877) 556-5728 | VOL. 1 | DEGREES SILVER VL71 | WALL TILE 12x12. LATICRETE 24 NATURAL GREY NON SANDED GROUT 1/8" |
| CT9 | CERAMIC TILE | DALTILE CONTACT. (877) 556-5728 | VOL. 1 | DEGREES SILVER VL71 | WALL TILE 6x6. LATICRETE 24 NATURAL GREY NON SANDED GROUT 1/8" |
| GLAZING | | | | | |
| GS7 | 1/4" LAMINATED GLASS | | | CLEAR | |
| GS8 | BULLET RESISTIVE GLASS | | | CLEAR | |
| GS9 | 1/4" GLASS DRIT | DRIT | | CLEAR | MOVABLE PARTITION WALL INSTALL BY DIRT |
| LAMINATE | | | | | |
| PL1 | LAMINATE | WILSONART | 7062 | CONGO SPRUCE | SUPPLIED BY MILLWORK VENDOR INSTALLED BY CONTRACTOR. HORIZONTAL SURFACES ONLY. GRAIN RUNS VERTICALLY (FOR EXISTING PHARMACY MODIFICATION) |
| PL2 | LAMINATE | WILSONART | 4669 | NATURAL TIGRIS | HIGH PRESSURE LAMINATE, SUPPLIED BY MILLWORK VENDOR INSTALLED BY CONTRACTOR. HORIZONTAL SURFACES ONLY (FOR EXISTING PHARMACY MODIFICATION) |
| PL7 | LAMINATE | WILSONART | 4940K-18 | ASTRO STRAINZ | SUPPLIED BY MILLWORK VENDOR INSTALLED BY CONTRACTOR. HORIZONTAL SURFACES ONLY. GRAIN RUNS VERTICALLY (M.C. AND FRONT CHECKOUT/PHOTOLAB) |
| PL8 | LAMINATE | WILSONART | 4942-60 | CRISP LINEN | HIGH PRESSURE LAMINATE, SUPPLIED BY MILLWORK VENDOR INSTALLED BY CONTRACTOR. HORIZONTAL SURFACES ONLY (M.C. AND FRONT CHECKOUT/PHOTOLAB) |
| PAINTS / SEALANTS | | | | | |
| PT1 | PAINT | BENJAMIN MOORE | PM-13 | TRIM WHITE/ AKA ALABASTER | EGOSPEC 374, 2 COATS, WALL/TRIM PAINT, EGGSHELL FINISH |
| PT4 | PAINT | BENJAMIN MOORE | INDIGO 744 | INDIGO | 2 COATS, WALL/TRIM PAINT, SATIN FINISH |
| PT8 | PRIMER | NU-BRITE/MURALC | #8400 | CLEAR | |
| PT20 | PAINT | BENJAMIN MOORE | 981 | WINDS BREATH | EGOSPEC 374, 2 COATS, WALL/TRIM PAINT, EGGSHELL FINISH |
| PT23 | PAINT | BENJAMIN MOORE | 779 | FAIRVIEW BLUE | EGOSPEC 374, 2 COATS, WALL/TRIM PAINT, EGGSHELL FINISH |
| PT24 | PAINT | BENJAMIN MOORE | 2001-10 | RUBY RED | EGOSPEC 374, 2 COATS, WALL/TRIM PAINT, FLAT FINISH |
| PT25 | PART - STAIN | MINIWAX | WOOD FINISH | PICKLED OAK 260 | 2 COATS ALL RETAIL WOOD DOORS |
| PT28 | PRIMER | BENJAMIN MOORE | V342 | MATCH ATRILUM WHITE A.K.A. ALABASTER | COROTECH HIGH PERFORMANCE PRE-CATALYZED WATERBORNE EPOXY, EGGSHELL FINISH |
| PT33 | PRIMER | NU-BRITE/MURALC | #8400 | CLEAR | LEVEL 5 PRIMER FINISH |
| WALL COVERING | | | | | |
| WV1 | VINYL WALL COVERING | WOLF GORDON | WG-10686434 | | GRAIN TO RUN HORIZONTALLY AND RUN FROM [W11] TRIM TO CEILING EDGE. INSTALL AT THE BOTTOM EDGE OF TRIM. |
| WV2 | VINYL WALL COVERING | PRATT | GRAPHIC | | PHARMACY WAITING ICON GRAPHIC |
| WV3 | VINYL WALL COVERING | PRATT | GRAPHIC | | MINUTE CLINIC WAITING ICON GRAPHIC |
| WV5 | CORNER GUARD | TRIMACO | 01188G | CLEAR | AVAILABLE AT HOME DEPOT 1 1/2" X 1 1/2" X 8FT |
| WV6 | PHARMACY ACROVYN ICON PANEL | IMPACT SPECIALTIES | ACROVYN WALL PANEL | | PHARMACY WAITING ICON GRAPHIC |
| WV7 | ACROVYN WALL PANEL | IMPACT SPECIALTIES | MC | ICON PATTERN | INSTALL IN GONDOLA WAITING AREA |
| WV8 | ACROVYN CHAIR RAIL | IMPACT SPECIALTIES | FR-125N SHADOWGRAIN TEXTURE | 1035 CLAMSHELL | PROVIDE ALL MOUNTING HWR., END CAPS & OUTSIDE CORNERS |
| WV22 | VINYL WALL COVERING | WOLF GORDON | WG-10099735 | OFF WHITE | INSTALL W/ PATTERN RUNNING VERTICALLY |
| GENERAL FINISHES NOTES: | | | | | |
| 1. ALL FINISHES SHALL BE PROVIDED AND INSTALLED AS PART OF THIS CONTRACT UNLESS OTHERWISE NOTED. | | | | | |
| 2. THE CONTRACTOR SHALL INSTALL ALL REQUIRED NON-COMBUSTIBLE BLOCKING AS REQUIRED FOR THE INSTALLATION OF ALL MILLWORK AND TOILET ROOM ACCESSORIES. COORDINATE WITH EQUIPMENT SUPPLIERS. | | | | | |
| 3. ALL INTERIOR FINISHES SHALL CONFORM TO A MAXIMUM CLASS A FLAME SPREAD RATING AND A MAX DEVELOPING RATING OF 450. | | | | | |
| 4. ACOUSTICAL CEILINGS AND INSULATION SHALL HAVE A MAX SPREAD OF 25 AND A MAX SMOKE DEVELOPMENT RATING OF 50. | | | | | |
| 5. WHERE APPLICABLE, TOOTH IN NEW FLOOR TILES WITH EXISTING FLOORING TO MATCH EXISTING PATTERN. | | | | | |

| ROOM FINISH SCHEDULE | | | | | | | | | | |
|----------------------|--------------------|------|------|------|------|------|------|-----------|-----------------------------------|--|
| ROOM NAME | WALLS - RE: NOTE 1 | | | | FLR | BASE | CEIL | CEIL HGT. | REMARKS | |
| | 1 | 2 | 3 | 4 | | | | | | |
| 101 ENTRY | PT20 | PT20 | PT20 | PT20 | FF12 | FF16 | | EXISTING | EXISTING | |
| 101 RETAIL | PT20 | PT20 | PT20 | PT20 | FF5 | FF16 | | EXISTING | PATCH AND PAINT WALLS | |
| 102 CHECKOUT | PT20 | | | | FF7 | FF16 | | EXISTING | EXISTING | |
| 103 PHOTOLAB | PT20 | | | | FF5 | FF16 | | EXISTING | EXISTING | |
| 105 EMPLOYEE | PT11 | PT11 | PT11 | PT11 | FF5 | FF16 | CA1 | 8'-0" | | |
| 106 RECEIVING | | | | | | | | | PAINT NEW WALLS TO MATCH EXISTING | |
| 109 HALL | PT20 | PT20 | PT20 | PT20 | FF5 | FF16 | GW6 | 7'-6" | PATCH AND PAINT WALLS | |
| 110 PHARMACY | PT20 | PT23 | PT23 | PT23 | FF7 | FF16 | | EXISTING | PAINT PHARMACY INTERIOR DOOR PT23 | |
| 111 RX WAITING | PT20 | | | | FF6 | FF16 | | EXISTING | EXISTING | |
| 112 RHC-MAIN | PT20 | PT20 | PT20 | PT20 | FF8 | FF16 | CA1 | 8'-0" | | |
| 113 RHC-SECONDARY | PT20 | PT20 | PT20 | PT20 | FF8 | FF16 | CA1 | 8'-0" | | |
| 114 RHC-LAB | PT20 | PT20 | PT20 | PT20 | FF8 | FF16 | CA1 | 8'-0" | | |
| 115 RHC WAITING | PT20 | PT20 | PT20 | PT20 | FF6 | FF16 | | EXISTING | EXISTING | |
| 116 CONSULTING | PT20 | PT20 | PT20 | PT20 | FF8 | FF16 | | EXISTING | EXISTING | |
| 117 SALES ROOM | PT20 | PT20 | PT20 | PT20 | FF8 | FF16 | | EXISTING | EXISTING | |

* REFER TO INTERIOR ELEVATIONS SHEETS.


FINISH NOTES:
 1. WALLS ARE NUMBERED STARTING WITH THE FRONT WALL AS #1, AND THEN ROTATE COUNTER CLOCKWISE.
 2. ALL COLUMNS TO BE PAINTED FROM FLOOR TO CEILING.
 3. PAINT [PT8] PRIOR TO ALL VINYL INSTALLATION.
 4. CLEAN RESTROOMS. PATCH GYM BOARD WALLS AS NEEDED AND PAINT TO MATCH EXISTING.



STORE NUMBER: 4522
 800 EAST WEST CONNECTOR
 AUSTELL, GA
 PROJECT TYPE: Health Hub and Reset
 DEAL TYPE:
 CS PROJECT NUMBER: 134320



CONSULTANT:



REVISIONS:

CVS PROJECT MANAGER: SB

DRAWING BY: JC

DATE: 07-22-2019

JOB NUMBER: 121-12600-08

TITLE: FINISH SCHEDULES AND DETAILS

SHEET NUMBER:

A6

COMMENTS: