

Order Plans @

PLUMBING NOTES

- GENERAL NOTES ARE APPLICABLE TO ALL PLUMBING WORKING DRAWINGS.
- THE WORK SHALL BE EXECUTED IN STRICT CONFORMITY WITH BASE BUILDING SPECIFICATION AND WITH THE LATEST EDITION OF THE PREVAILING LOCAL PLUMBING AND BUILDING CODES AND ALL LOCAL REGULATIONS THAT MAY APPLY. IN CASE OF CONFLICT BETWEEN THE CONTRACT DOCUMENTS AND A GOVERNING CODE OR ORDINANCE THE MORE STRINGENT STANDARD SHALL APPLY.
- ALL PLUMBING WORK SHALL BE COORDINATED WITH ALL OTHER TRADES BEFORE PROCEEDING WITH INSTALLATION.
- NO CHANGES ARE TO BE MADE IN PLUMBING LAYOUT WITHOUT WRITTEN PERMISSION BY THE ENGINEER OF RECORD.
- NO PIPING SHALL RUN EXPOSED IN SALES OR FINISHED AREAS.
- PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR OBTAINING ALL NECESSARY PERMITS AND FOR PAYING RELATED FEES.
- ROUGH-IN DIMENSIONS OF TOILET FIXTURES MUST BE COORDINATED WITH GENERAL CONTRACTOR AND FIELD SUPERVISOR.
- INSTALL BALL VALVES ON ALL BRANCH SUPPLY LINES.
- PROVIDE ACCESS PANELS ON ALL INACCESSIBLE VALVES AND CLEANOUTS. ACCESS PANELS SHALL BE PROVIDED BY GENERAL CONTRACTOR. PLUMBING CONTRACTOR SHALL BE RESPONSIBLE FOR THEIR LOCATION. MOUNT SHUT-OFF VALVES NO HIGHER THAN 12'-8" AFF.
- ALL WORK SHALL BE PROPERLY TESTED, BALANCED AND CLEANED. PROVIDE A ONE YEAR WARRANTY FROM DATE OF FINAL INSPECTION ON ALL PARTS AND LABOR.
- FOLLOW PDI STANDARDS FOR WATER HAMMER ARRESTORS.
- ALL FIXTURES TO BE SUPPLIED & INSTALLED BY PLUMBING CONTRACTOR, EXCEPT THE PHARMACY SINK: CVS SUPPLIES & PLUMBING CONTRACTOR INSTALLS.
- GENERAL CONTRACTOR SHALL COORDINATE WATER METER LOCATION AND INSTALLATION WITH LOCAL AUTHORITIES AND CIVIL DRAWINGS.
- PROVIDE BUILDING SERVICE LINE 5'-0" FROM BUILDING LINE, OR INSIDE BUILDING FROM OUTLET SIDE OF METER AS SHOWN ON CIVIL SITE PLAN. COORDINATE EXACT LOCATION WITH CIVIL DRAWINGS AND AT JOB SITE. PROVIDE BACKFLOW PREVENTER AS REQUIRED BY AUTHORITIES.
- SANITARY SEWER PIPING SHOWN IS BASED ON 0.125'/FT FOR 3"-6" & 0.25'/FT FOR 2 1/2" OR LESS FOR ALL PIPING. COORDINATE BUILDING SEWER LOCATION AND INVERT ELEVATION WITH CIVIL DRAWINGS.
- TRAP SEAL PRIMERS ARE TO BE PROVIDED AT NO ADDITIONAL COST TO OWNER IF REQUIRED BY LOCAL BUILDING CODE OFFICIALS.
- VIR'S SHALL BE LOCATED A MINIMUM OF 5' FROM ANY PARAPET WALL AND 10' FROM ANY RTH/INTAKE.
- COOLER AND FREEZER DRAIN PAN CONNECTION SHALL BE LOCATED WITHIN MAXIMUM 10' FROM NEAREST FLOOR SINK.

PLUMBING FIXTURE SCHEDULE

| ITEM | MANUFACTURER | REMARKS AND SPECIFICATIONS |
|------|---|--|
| EW-1 | BRADLEY | EYEWASH: #S19-270C, SWING-ACTIVATED, (COORDINATE WITH ARCHITECTURE DRAWINGS FOR WASH SINKS SHALL RECEIVE EMERGENCY EYEWASH, REFER TO EYEWASH MOUNTING DETAIL (100-53). WATER TEMPERATURE SHALL BE SET TO NOT EXCEED 95°. |
| S-1 | DAYTON: #D11515 ALT: MOEN: ALT: BLANCO: ALT: HOUZER: #1515-6BS | BREAKROOM SINK: STAINLESS STEEL SINK 15"X15"X1/8" DEEP, 14-3/8" DIA. CUTOUT WITH 1-1/2" RAD. CORNERS, 1-1/4" DIA. FAUCET HOLES. FAUCET: DELTA 711F-1000ND GOLF NECK BAR FAUCET WITH HANDLES AND AERATOR, OVERALL HEIGHT 4". FINISH AND INSTALL BROCKHOLM CSOR-B TRAP WRAP FOR PFB. BROCAR TEL: (800) 827-1207. |
| S-5 | SINK & FAUCET FURNISHED BY MILLWORK SUPPLIER, INSTALLED BY PLUMBER | MODEL #SL-AD-19-A-GR STAINLESS STEEL SINK 17-1/2"x19"x4-1/2", (2) HOLES ON 4" CENTERS, CENTER REAR DRAIN W/ FAUCET |
| WCO | J. R. SMITH | W.C. CLEANOUT: #442 PAPER THREAD PLUG WITH ROUND COVER. |
| WH-1 | CHRONOMITE LABORATORIES | INSTANTANEOUS WATER HEATER: MODEL SR-20L, TANKLESS ELECTRIC WATER HEATER, FLOW ACTIVATED, STAINLESS STEEL HEATING COILS, ONE 1/2" WATT, 208 VOLT, SINGLE PHASE, 20 AMP, 1/2" WATER CONNECTION, 6" HX WX2-1/2", 80-121 DEGREE F. TEMP. RANGE. |
| DP-1 | | DRAIN PUMP: MODEL 105 COMPLETE WITH BASIN, PUMP, AND CHECK VALVE |

PLUMBING FIXTURE PIPING SCHEDULE

| TAG | FIXTURE TYPE | LINE SIZES | | | | |
|-----|-------------------|------------|-------|-------|------|-----|
| | | WASTE | TRAP | VENT | COLD | HOT |
| S-1 | BREAK ROOM SINK | 1 1/2 | 1 1/4 | 1 1/2 | 1/2 | 1/2 |
| S-5 | CONSULTATION SINK | 2 | 1 1/2 | 1 1/2 | 1/2 | 1/2 |

LEGEND

| | | | | | |
|-------------|---------------------|-----------|---------------------|----|----------------|
| —SS— | SANITARY SEWER | — — — — — | PLUMBING VENT | | |
| — — — — — | DOMESTIC COLD WATER | ⌒ | ELBOW - TURNED DOWN | | |
| — · · · · · | DOMESTIC HOT WATER | ⌒ | GATE VALVE | | |
| HW | HOT WATER | PF | PLUMBING FIXTURE | SS | SANITARY SEWER |
| CW | COLD WATER | PD | PUMP DISCHARGE | V | PLUMBING VENT |
| DN | DOWN | | | | |



STORE NUMBER: 4522
 800 EAST WEST CONNECTOR
 AUSTELL, GA
 PROJECT TYPE: Health Hub and Reset
 DEAL TYPE:
 CS PROJECT NUMBER: 134320

ARCHITECT OF RECORD



110 South College St., Suite 400, Durham, NC 27601
 P: 704.828.4242 F: 704.828.1170
 www.littleonline.com

CONSULTANT:



GEORGE W AUSTIN JR, PE
 217 N. McDowell St. Suite 204
 Charlotte, NC 28204
 (P) 704.334.7363 (F) 704.347.0093
 www.challeng.com
 SEG - 19-097

DEVELOPER:



SEAL:



REVISIONS:

CVS PROJECT MANAGER: SB
 DRAWING BY: ZTM
 DATE: 07-22-2019
 JOB NUMBER: 121-12600-08
 TITLE:

PLUMBING LEGEND,
 NOTES, AND SCHEDULES
 SHEET NUMBER:

P1

COMMENTS: