

NOTED TO BE DOUBLE CHECKED AND CORRECTED AND INSTALLED IN A NEAT AND ORDERLY FASHION.

seiberdesign
ARCHITECTS & ENGINEERS

875 Drewry St. NE
 Suite 200
 Atlanta GA 30306
 404.875.6755
 www.seiberdesign.com

© Copyright (2017) SE
 This drawing and all reproductions thereof are the property of Seiber Design, Inc. (SDI). It is intended for the sole use of the project named herein. Reproduction without the written consent of SDI is prohibited. All rights reserved. No part of this drawing is to be returned to SDI upon project completion.



Consultant
WESTSIDE
 5525 Interstate North Pkwy
 Suite 200
 Atlanta, GA 30328
 404-965-1287 tel
 404-601-9859 fax
 westside@westside-engineering.com

KEY NOTES


- ① PROVIDE ELECTRICAL RECEPTACLE AND DATA OUTLET FOR CONNECTION TO POS SYSTEM. COORDINATE EXACT MOUNTING HEIGHT AND LOCATION WITH OWNER/ARCHITECT PRIOR TO ROUGH-IN.
- ② OUTLET FOR WALL MOUNTED MISTING FAN. COORDINATE EXACT MOUNTING HEIGHT WITH ARCHITECT PRIOR TO ROUGH-IN.

ELECTRICAL ROUGH-IN NOTES

- 1. VERIFY ALL EQUIPMENT LOCATIONS AND MOUNTING HEIGHTS SHOWN WITH EQUIPMENT SUPPLIER AND OWNER PRIOR TO ROUGH-IN.
- 2. ALL 20A 1P RECEPTACLES IN SCHEDULE SHALL BE GFI PROTECTED.
- 3. VERIFY ALL LOADS AND CONNECTION FOR ACTUAL EQUIPMENT SUPPLIED PRIOR TO ROUGH-IN. VERIFY EXACT REQUIREMENTS WITH MANUFACTURER PRIOR TO ROUGH-IN.
- 4. COORDINATE EXACT LOCATION WITH EQUIPMENT SUPPLIER PRIOR TO ROUGH-IN.

ABBREVIATIONS

AF	ABOVE FINISHED FLOOR
BT	BRANCH TO CONNECT
CLG	CEILING
DFA	DOWN FROM ABOVE
FD	FLOOR DRAIN
FFD	FUNNEL FLOOR DRAIN
FLR	FLUSH WITH FLOOR
FS	FLOOR SINK
VRF	VERIFY W/EQUIPMENT SUPPLIER



1 PARTIAL 3RD LEVEL - ELECTRICAL
 E1.2 SCALE: 3/16" = 1'-0"

ELECTRICAL CONNECTION SCHEDULE

EQPT. NO.	EQUIPMENT	CIRCUIT	CONDUCTIONS	ELECTRICAL DATA			REMARKS	
				VOLTS/PH	KW	AMP		
A1	ROTTLE COOLER	RK3-29	2#12, 1#12G, 5/4"PC	120	-	5.2	180	VERIFY CONNECTION TYPE
A2	BACK BAR COOLER	RK3-31	2#12, 1#12G, 5/4"PC	120	-	5.2	180	VERIFY CONNECTION TYPE
A3	COMMENCE RECEPTACLES	RK3-33	2#12, 1#12G, 5/4"PC	120	-	15.0	120	VERIFY CONNECTION TYPE
AGA	BLENDEK STATION	RK3-35	2#12, 1#12G, 5/4"PC	120	-	15.0	120	VERIFY CONNECTION TYPE
AGB	BLENDEK STATION	RK3-37	2#12, 1#12G, 5/4"PC	120	-	15.0	120	VERIFY CONNECTION TYPE
AS	POS STATION	RK3-39	2#12, 1#12G, 5/4"PC	120	-	15.0	80	VERIFY CONNECTION TYPE

Order Plans @ WWW.LDILine.com

**EDGAR'S ABOVE BROAD
 699 BROAD ST.
 AUGUSTA, GEORGIA 30901**

Project Number	1817	
Revisions		
Revision History		
Number	Date	Description
	08/20/19	ISSUED FOR CONSTRUCTION
Drawing Title	PARTIAL 3RD LEVEL - ELECTRICAL	
Drawing Status	ISSUED FOR CONSTRUCTION	
Drawing Number		

E1.2