



PLAN TRUE
 1 MECHANICAL FLOOR PLAN
 M-2 SCALE: 1/4" = 1'-0"

MECHANICAL SHEET NOTES

- Prior to estimating costs/ordering equipment: Verify final location of rooftop equipment with Landlord and Structural Engineer.
- RTU'S BY LANDLORD: Verify make and model, cooling capacity, supply air CFM, electrical. Verify each unit is provided with thermostat controller and duct smoke detector.
- Route exhaust duct to terminate min 10ft from OSA intakes.
- Electronically interlock MUA-1, RTU-4, and RTU-6B fans "ON" with KEF-1, KEF-2. Contact Accurex/refer to Accurex design sheets regarding fan interlock location on hood control panel.
- Min 10ft clear radius between OSA intakes and exhaust duct terminations, fans of adjacent units, plumbing vent.
- Provide rated cleanout for grease exhaust duct. Verify clearance requirements to combustibles with Mfr.
- Provide Ductmate or equal exposed rectangular duct with flanged connections where duct is exposed. Where duct run permits - space flanged joints 5'-6" apart on center. Prior to ordering materials: Verify 13ft min from bottom of duct to finished floor with Architect. Do not route duct directly below lights. Line duct internally with R6 insulation. Increase sheet metal accordingly; duct sizes noted on plan are inside, clear dimensions.
- Route SA duct within soffit space, verify height AFF prior to ordering materials.
- Verify existing or provide ionized smoke detector in RA duct. Fan shall shut off upon detection of smoke per code.
- Provide smooth transition up to rooftop equipment. Verify ductwork will not conflict with roof trusses prior to ordering materials.
- Connect new ductwork to risers from existing RTU; provide smooth transition. Verify ductwork will not conflict with roof trusses prior to ordering materials.
- Provide transfer opening above door with return grilles on each side of wall.
- Route duct above cloud ceiling. Verify clearances to roof structure prior to ordering materials.
- Provide elbow in RA. Cover open end with 1/2" galv. mesh. Line duct with 1" acoustical insulation.
- Ductwork above lay-in ceiling in-between joists or below bottom of joist. Prior to fabrication, verify clearances, and space for duct crossings. Insulate supply duct to R-5 below roof insulation where above ceiling (none required for exposed ductwork, unless where noted otherwise).
- WALL REGISTER: Provide 8 inch duct extension off of SA trunk for wall register fitting. Duct extension dimensions are same as WR size noted on plan. See Detail 3, M-1.
- Owner shall provide remote thermostat sensor and necessary wiring. Locate remote sensor 72" AFF as shown on plan. Verify no extraneous heat sources are located near the sensor. Route wiring within conduit. Do not locate sensor near or above sources of heat, in direct sunlight, or in immediate path of supply air from ceiling diffuser.
- Locate Owner-provided thermostat controller per Architectural Elevations.

Consultant:
 ARWIN PRIEST P.E., P.Eng.
 MECHANICAL * ENGINEER * ELECTRICAL
 242 MOUNTAIN CLOUD CIRCLE
 HIGHLANDS RANCH, CO 80126

(303) 898-2664 pc5744@gmail.com

5280 Engineering
 www.DesignMEP.com
 720-320-7744 reg@5280engineering.com

SEAL

DATE :



GOOD TIMES RESTAURANTS, INC.
 141 Union Blvd, Suite 400
 Lakewood, CO 80228
 tel: (303) 384-1430

BAD DADDY'S BURGER BAR
 "SANDY PLAINS"
 3460 SANDY PLAINS RD
 SUITE 110
 MARIETTA, GA 30062

Issue Record:
 06.07.2019 FOR PLAN REVIEW

Revisions:
 08.01.2019 BAR FIXT. TO GREASE WST
 08.28.2019 QCR

Drawn:
 DRAWN BY: F Long

Checked:
 CHECKED BY: R Blank

Project No.
 PROJECT#: 2019-041

Consultant:
 MECHANICAL:
 FLOOR PLAN, SHEET NOTES

M-2
 of 3