

GENERAL NOTES
A. SEQUENCING OF PERMITS AND REQUIRED PRECONSTRUCTION MEETINGS ARE AS FOLLOWS:
1. A PRE-CONSTRUCTION MEETING WILL NEED TO BE SCHEDULED BY THE CONTRACTOR THROUGH THE PERMIT DEVELOPMENT OFFICE WITH THE CHIEF BUILDING INSPECTOR SPECIFICALLY RELATED TO THE RETAINING WALL CONSTRUCTION.
2. AFTER THE WALL CONSTRUCTION PERMIT HAS BEEN OBTAINED BY THE CONTRACTOR, A SECOND PRE-CONSTRUCTION MEETING WILL NEED TO BE SCHEDULED BY THE CONTRACTOR THROUGH PLANNING AND DEVELOPMENT TO OBTAIN THE DEVELOPMENT PERMIT. THE PERMIT CARD WILL BE DELIVERED TO THE CONTRACTOR AT THE SECOND PRE-CONSTRUCTION MEETING. NO MOBILIZATION CAN OCCUR ON SITE PRIOR TO THE DELIVERY OF THE DEVELOPMENT PERMIT.

DESIGN DATA PROVIDED IN ELECTRONIC FORMAT IS FOR INFORMATION PURPOSES ONLY AND SHOULD BE USED AT YOUR OWN RISK, AND IS PROVIDED WITHOUT REPRESENTATIONS AND WARRANTIES. ANY CONFLICT BETWEEN THE INFORMATION REFLECTED ON THE LATEST REVISION OF THE SEALED PLAN SHEETS AND THAT PROVIDED VIA ELECTRONIC FORMAT SHALL BE RESOLVED IN FAVOR OF THE SEALED PLAN SHEETS.

EXISTING UTILITIES ARE SHOWN IN AN APPROXIMATE MANNER ONLY AND THE ENGINEER ASSUMES NO RESPONSIBILITY FOR LOCATIONS SHOWN. FIELD VERIFY THE LOCATION OF ALL EXISTING UTILITIES WITHIN THE LIMITS OF CONSTRUCTION. NOTIFY THE OWNER AND ENGINEER IF DISCREPANCIES ARE FOUND THAT WILL AFFECT THE CONSTRUCTION PROJECT. PROTECT ALL EXISTING UTILITIES.

TEMPORARY PROVISIONS: SEQUENCE THE WORK AND PROVIDE TEMPORARY MEASURES AS NEEDED TO MAINTAIN ACCESS TO THE SITE THROUGH ALL ENTRANCES AT ALL TIMES DURING CONSTRUCTION. TEMPORARY PROVISIONS MAY INCLUDE, BUT ARE NOT LIMITED TO, BARRICADES, FLASHING LIGHTS, FLAGMAN, TEMPORARY PAVEMENT, AND DIRECTIONAL SIGNAGE.

EXISTING STORAGE: DO NOT PARK EQUIPMENT OR STORE MATERIALS IN STATE, COUNTY, OR CITY RIGHT-OF-WAY.

NOTIFY THE ENGINEER IN WRITING OF ANY DISCREPANCIES BETWEEN THE EXISTING CONDITIONS IN THE FIELD AND THE SURVEY SHOWN ON THE PLANS BEFORE PROCEEDING WITH ANY NEW CONSTRUCTION.

OBTAIN ALL REQUIRED CONSTRUCTION RELATED PERMITS, INCLUDING DEMOLITION PERMIT, BEFORE STARTING WORK. RETAIN COPIES OF ALL PERMITS AT THE PROJECT SITE AT ALL TIMES.

APPROVAL OF THESE PLANS DOES NOT CONSTITUTE APPROVAL OF ANY LAND DISTURBING ACTIVITIES WITHIN OR NEAR THE PROJECT AREA. CONTACT THE APPROPRIATE REGULATORY AGENCY FOR APPROVAL OF ANY WETLAND AREA DISTURBANCE.

SIGNS (LOCATION, NUMBER, AND SIZE) ARE NOT APPROVED UNDER THE GENERAL DEVELOPMENT PERMIT. A SEPARATE PERMIT IS REQUIRED FOR ON-SITE SIGNAGE.

NO CERTIFICATE OF OCCUPANCY WILL BE ISSUED UNTIL ALL SITE IMPROVEMENTS HAVE BEEN COMPLETED ON THE SITE.

COMPLY WITH ALL APPLICABLE STATE, FEDERAL, AND LOCAL BUILDING AND UTILITY INSTALLATION CODES. ALL MATERIALS AND CONSTRUCTION METHODS SHALL BE IN ACCORDANCE WITH THESE PLANS AND SPECIFICATIONS UNLESS DEPARTMENT OF TRANSPORTATION STANDARDS OR LOCAL MUNICIPAL STANDARDS ARE MORE STRINGENT.

DO NOT DEVIATE FROM THE STANDARDS AND SPECIFICATIONS WITHOUT PRIOR WRITTEN APPROVAL FROM THE ENGINEER OF RECORD.

WORK WITHIN D.O.T. RIGHT-OF-WAY:
1. ALL PAVEMENT MARKINGS WITHIN D.O.T. RIGHT-OF-WAY SHALL BE THERMOPLASTIC AND IN ACCORDANCE WITH D.O.T. SPECIFICATIONS.
2. RE-ESTABLISH ALL RIGHT-OF-WAY AREA, WHICH IS DAMAGED OR DISTURBED, TO ORIGINAL CONDITION OR BETTER.
3. ALL WORK WITHIN D.O.T. RIGHT-OF-WAY SHALL COMPLY WITH D.O.T. SPECIFICATIONS.

ARRANGE HIGH INTENSITY LIGHTING TO CONCEAL THE SOURCE OF LIGHT FROM PUBLIC VIEW AND PREVENT INTERFERENCE WITH TRAFFIC.

ENSURE CORRECT HORIZONTAL AND VERTICAL ALIGNMENT OF ALL TIES BETWEEN PROPOSED AND EXISTING PAVEMENTS, CURB AND GUTTER, SIDEWALKS, WALLS, AND UTILITIES BEFORE BEGINNING WORK. NOTIFY ENGINEER IF DISCREPANCIES EXIST.

TRAFFIC CONTROL
A. IF DRAWINGS DO NOT INDICATE SITE SPECIFIC TRAFFIC CONTROL MEASURES, CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING A TEMPORARY TRAFFIC CONTROL PLAN IN ACCORDANCE WITH THE MANUAL ON UNIFORM TRAFFIC CONTROL DEVICES (MUTCD), LATEST EDITION.
B. ALL TEMPORARY TRAFFIC CONTROL SIGNAGE AND MARKINGS SHALL BE INSTALLED PRIOR TO CONSTRUCTION AND MAINTAINED DURING CONSTRUCTION IN ACCORDANCE WITH THE MUTCD, LATEST EDITION.
C. CONTACT PROPERTY OWNERS TO BE AFFECTED BY CONSTRUCTION AND COORDINATE TEMPORARY DRIVEWAY CLOSURES AND SEQUENCING. MAINTAIN ACCESS FOR ALL PROPERTY OWNERS DURING CONSTRUCTION.
D. CONTROL DUST AS NECESSARY TO PREVENT INTERFERENCE WITH TRAFFIC.
E. INSPECT TRAFFIC CONTROL DEVICES ON A DAILY BASIS TO ENSURE PLACEMENT OF BARRICADES AND FUNCTION OF LIGHTS IS MAINTAINED THROUGHOUT CONSTRUCTION.
F. COORDINATE ALL LANE CLOSURES WITH THE LOCAL JURISDICTION HAVING AUTHORITY.

STRUCTURE & SITE DEMOLITION
A. VERIFY THAT UTILITIES HAVE BEEN DISCONNECTED AND CAPPED BEFORE STARTING DEMOLITION OPERATIONS.
B. VERIFY THAT HAZARDOUS MATERIALS HAVE BEEN REMEDIATED BEFORE PROCEEDING WITH BUILDING DEMOLITION OPERATIONS.
C. ENVIRONMENTAL & GEOTECHNICAL REVIEW ALL PROJECT ENVIRONMENTAL AND GEOTECHNICAL REPORTS AN BECOME FAMILIAR WITH ALL ISSUES BEFORE DEMOLITION.
D. EXISTING UTILITIES: LOCATE, IDENTIFY, DISCONNECT, AND SEAL OR CAP OFF INDICATED UTILITIES SERVING BUILDINGS AND STRUCTURES TO BE DEMOLISHED.
1. ARRANGE TO SHUT OFF INDICATED UTILITIES WITH UTILITY COMPANIES.
2. IF REMOVAL, RELOCATION OR ABANDONMENT OF UTILITY SERVICES WILL AFFECT ADJACENT OCCUPIED BUILDINGS, THEN PROVIDE TEMPORARY UTILITIES THAT BYPASS BUILDINGS AND STRUCTURES TO BE DEMOLISHED AND THAT MAINTAIN CONTINUITY OF SERVICE TO OTHER BUILDINGS AND STRUCTURES.
3. DO NOT COMMENCE DEMOLITION OPERATIONS UNTIL TEMPORARY EROSION AND SEDIMENT CONTROL AND PLANT-PROTECTION MEASURES ARE IN PLACE.
4. OBTAIN THE DEMOLITION PERMIT FROM THE LOCAL AUTHORITY PRIOR TO STARTING DEMOLITION ACTIVITIES.
5. EXISTING FACILITIES: PROTECT ADJACENT WALKWAYS, LOADING DOCKS, BUILDING ENTRIES, AND OTHER BUILDING FACILITIES DURING DEMOLITION OPERATIONS. MAINTAIN EXITS FROM EXISTING BUILDINGS PROMPTLY REPAIR ANY FACILITIES DAMAGED BY CONSTRUCTION OPERATIONS TO OWNERS SATISFACTION AT NO ADDITIONAL COST TO THE OWNER.
6. EXISTING UTILITIES: MAINTAIN UTILITY SERVICES TO REMAIN AND PROTECT FROM DAMAGE DURING DEMOLITION OPERATIONS.
7. TEMPORARY PROTECTION: ERECT TEMPORARY PROTECTION, SUCH AS WALKS, FENCES, RAILINGS, CANOPIES, AND COVERED PASSAGEWAYS, WHERE REQUIRED BY AUTHORITIES HAVING JURISDICTION AND AS INDICATED.
8. REMOVE TEMPORARY BARRIERS AND PROTECTIONS WHERE HAZARDS NO LONGER EXIST.

WHERE OPEN EXCAVATIONS OR OTHER HAZARDOUS CONDITIONS REMAIN, LEAVE TEMPORARY BARRIERS AND PROTECTIONS IN PLACE.
9. REMOVE DEMOLITION WASTE MATERIALS FROM PROJECT SITE AND LEGALLY DISPOSE OF THEM IN AN EPA-APPROVED LANDFILL ACCEPTABLE TO AUTHORITIES HAVING JURISDICTION.
10. DO NOT BURN DEMOLITION MATERIALS UNLESS SPECIAL WRITTEN PERMISSION IS OBTAINED FROM OWNER AND ENGINEER.
11. CLEAN ADJACENT STRUCTURES AND IMPROVEMENTS OF DUST, DIRT, AND DEBRIS CAUSED BY BUILDING DEMOLITION OPERATIONS. RETURN ADJACENT AREAS TO CONDITION EXISTING BEFORE BUILDING DEMOLITION OPERATIONS BEGAN.

SITE CLEARING
1.) PROJECT CONDITIONS
A. TRAFFIC: MINIMIZE INTERFERENCE WITH ADJOINING ROADS, STREETS, WALKS, AND OTHER ADJACENT OCCUPIED OR USED FACILITIES DURING SITE-CLEARING OPERATIONS TO SHUT OFF INDICATED UTILITIES.
B. ENVIRONMENTAL & GEOTECHNICAL REVIEW ALL PROJECT ENVIRONMENTAL AND GEOTECHNICAL REPORTS AND BECOME FAMILIAR WITH ALL ISSUES BEFORE SITE CLEARING.
C. UTILITY LOCATOR SERVICE: NOTIFY UTILITY LOCATOR SERVICE FOR AREA WHERE PROJECT IS LOCATED BEFORE SITE CLEARING.
D. DO NOT COMMENCE SITE CLEARING OPERATIONS UNTIL TEMPORARY EROSION- AND SEDIMENTATION-CONTROL AND PLANT-PROTECTION MEASURES ARE IN PLACE.
2.) TEMPORARY EROSION AND SEDIMENTATION CONTROL
A. PROVIDE TEMPORARY EROSION- AND SEDIMENTATION-CONTROL MEASURES TO PREVENT SOIL EROSION AND DISCHARGE OF SOIL-BEARING WATER RUNOFF OR AIRBORNE DUST TO ADJACENT PROPERTIES AND WALKWAYS, ACCORDING TO EROSION- AND SEDIMENTATION-CONTROL DRAWINGS AND REQUIREMENTS OF AUTHORITIES HAVING JURISDICTION.
B. VERIFY THAT FLOWS OF WATER REDIRECTED FROM CONSTRUCTION AREAS OR GENERATED BY CONSTRUCTION ACTIVITY DO NOT ENTER OR CROSS PROTECTION ZONES.
C. AND REPAIR OR REPLACE BRUSH, SHRUBS, AND OTHER VEGETATION INDICATED TO REMAIN OR BE RELOCATED THAT ARE DAMAGED BY CONSTRUCTION OPERATIONS, IN A MANNER APPROVED BY ENGINEER.
3.) TREE AND PLANT PROTECTION
A. REPAIR OR REPLACE TREES, SHRUBS, AND OTHER VEGETATION INDICATED TO REMAIN OR BE RELOCATED THAT ARE DAMAGED BY CONSTRUCTION OPERATIONS, IN A MANNER APPROVED BY ENGINEER.
4.) EXISTING UTILITIES
A. LOCATE, IDENTIFY, DISCONNECT, AND SEAL OR CAP UTILITIES INDICATED TO BE REMOVED OR ABANDONED IN PLACE. ARRANGE WITH UTILITY COMPANIES TO SHUT OFF INDICATED UTILITIES.
B. INTERRUPTING EXISTING UTILITIES: DO NOT INTERRUPT UTILITIES SERVING FACILITIES OCCUPIED BY OWNER OR OTHERS UNLESS PERMITTED UNDER THE FOLLOWING CONDITIONS AND THEN ONLY AFTER ARRANGING TO PROVIDE TEMPORARY UTILITY SERVICES ACCORDING TO REQUIREMENTS INDICATED.
1. NOTIFY UTILITY OWNER NOT LESS THAN TWO DAYS IN ADVANCE OF PROPOSED UTILITY INTERRUPTIONS.
2. DO NOT PROCEED WITH UTILITY INTERRUPTIONS WITHOUT UTILITY OWNER'S WRITTEN PERMISSION.
C. POT HOLE EXISTING WATER LINES, UNDERGROUND ELECTRICAL LINES, GAS LINES, UNDERGROUND TELEPHONE LINES, FIBER OPTIC, AND ANY OTHER EXISTING UTILITY LINES WITHIN THE PROJECT LIMITS DURING SITE CLEARING AND DEMOLITION ACTIVITIES. SURVEY THE EXISTING UTILITY ELEVATIONS AND PROVIDE THE SURVEYED FIELD LOCATIONS AND DEPTHS TO THE ENGINEER FOR REVIEW. THESE EXISTING UTILITIES MAY REQUIRE RELOCATION.
5.) CLEARING AND GRUBBING
A. REMOVE OBSTRUCTIONS, CONCRETE, ASPHALT, TREES, SHRUBS, AND OTHER VEGETATION TO PERMIT INSTALLATION OF NEW CONSTRUCTION.
1. DO NOT REMOVE TREES, SHRUBS, AND OTHER VEGETATION INDICATED TO REMAIN OR TO BE RELOCATED.
2. MINIMUM PRESSURE RATING: 250 PSIG.
3. END CONNECTIONS: MECHANICAL JOINT.
4. INTERIOR COATING: COMPLY WITH AWWA C550.
B. GATE VALVE ACCESSORIES AND SPECIALTIES
A. TAPPING-SLEEVE ASSEMBLIES: SLEEVE AND VALVE COMPATIBLE WITH DRILLING MACHINE.
1. STANDARD: MSS SP-80.
2. VALVE: AWWA CAST-IRON OR DUCTILE-IRON OR STAINLESS-STEEL, TWO-PIECE BOLTED SLEEVE WITH FLANGED OUTLET FOR NEW BRANCH CONNECTION. INCLUDE SLEEVE MATCHING SIZE AND TYPE OF PIPE MATERIAL BEING TAPPED AND WITH RECESSED FLANGE FOR BRANCH VALVE.
3. VALVE: AWWA CAST-IRON, NONRRISING-STEM, RESILIENT-SEAATED GATE VALVE WITH ONE RAISED FACE FLANGE MATING TAPPING-SLEEVE FLANGE.
B. VALVE BOXES: COMPLY WITH AWWA M44 FOR CAST-IRON VALVE BOXES. INCLUDE TOP SECTION, ADJUSTABLE EXTENSION OF LENGTH REQUIRED FOR DEPTH OF BURIAL OF VALVE, PLUS WITH LETTERING "WATER" AND BOTTOM SECTION WITH BASE THAT FITS OVER VALVE AND WITH BARREL APPROXIMATELY 5 INCHES IN DIAMETER.
7.) BACKFLOW PREVENTERS
A. DOUBLE-CHECK DETECTOR ASSEMBLY BACKFLOW PREVENTERS:
1. STANDARDS: ASSE 1048 AND UL LISTED OR FMG APPROVED.
2. OPERATION: CONTINUOUS-PRESSURE APPLICATIONS.
3. PRESSURE LOSS: 4 PSIG MAXIMUM THROUGH MIDDLE 1/3 OF FLOW RANGE.
4. BODY: CAST IRON WITH INTERIOR LINING COMPLYING WITH AWWA C550 THAT IS FDA APPROVED.
5. END CONNECTIONS: FLANGED.
6. CONFIGURATION: DESIGNED FOR HORIZONTAL STRAIGHT THROUGH.
8.) WATER METER BOXES
A. DESCRIPTION: CAST-IRON BODY AND COVER FOR DISC-TYPE WATER METER WITH LETTERING "WATER METER" IN COVER, AND WITH SLOTTED BOTTOM BASE SECTION WITH TOP TO FIT OVER SERVICE PIPING.
9.) CONCRETE VAULTS
A. DESCRIPTION: PRECAST, REINFORCED CONCRETE VAULTS DESIGNED FOR A-16 LOAD DESIGNATION ACCORDING TO ASTM C 850. MAKE SECTION TO ASTM C 868.
1. LAIDERS: ASTM A 36A 3/8" STEEL OR P220 TYPICAL ENCL. 1.1 STEEL STEPS.
2. MANHOLE: ASTM A 36A 1/8" CLASS 150 MINIMUM TENSILE STRENGTH, GRAY-IRON TRAFFIC FRAME AND COVER.
a. DIMENSION: 24-INCH MINIMUM DIAMETER, UNLESS OTHERWISE INDICATED.
3. DRAIN: ASME A112.6.3. CAST-IRON FLOOR DRAIN WITH OUTLET OF SIZE INDICATED. INCLUDE BODY ANCHOR FLANGE, LIGHT-DUTY CAST-IRON GRATE, BOTTOM OUTLET, AND INTEGRAL OR FIELD-INSTALLED CONCRETE BALL OR CLAPPER-TYPE BACKWATER VALVE.
10.) FIRE HYDRANT
A. DRIVE-BARREL TYPE HYDRANTS: FREESTANDING, WITH ONE NPS 1-1/2 AND TWO NPS 2-1/2 OUTLETS, 5-1/4" ICH MAIN VALVE, MAIN VALVE, AND NPS 6 MECHANICAL-JOINT INLET. INCLUDE INTERIOR COATING ACCORDING TO AWWA C550. HYDRANT SHALL HAVE CAST-IRON BODY, COMPRESSION PEX VALVE PENN AGAINST PRESSURE AND CLOSING WITH PRESSURE.
1. STANDARD: AWWA C502.
2. PRESSURE RATING: 250 PSIG.
11.) FIRE DEPARTMENT CONNECTIONS
A. FIRE DEPARTMENT CONNECTIONS: FREESTANDING, WITH CAST-BRONZE BODY, THREAD INLETS ACCORDING TO TRADES AND MATCHING LOCAL FIRE DEPARTMENT HOSE THREADS, AND THREADED BOTTOM OUTLET. INCLUDE LUGGED CAPS, GASKETS, AND CHAINS, LUGGED SWIVEL CONNECTION AND DROP CLAPPER FOR EACH HOSE-CONNECTION INLET, 18-INCH, HIGH BRASS SLEEVE, AND ROUND ESCUTCHION PLATE.
12.) VALVE APPLICATIONS
A. DRAWINGS INDICATE VALVE TYPES TO BE USED, WHERE SPECIFIC VALVE TYPES ARE NOT INDICATED, THE FOLLOWING REQUIREMENTS APPLY:
1. UNDERGROUND VALVES, NPS 3 AND LARGER: AWWA CAST-IRON, NONRRISING-STEM, RESILIENT-SEAATED GATE VALVES WITH VALVE BOX.
2. USE THE FOLLOWING FOR VALVES IN VAULTS AND ABOVEGROUND:
a. GATE VALVES, NPS 2 AND SMALLER: BRONZE, NONRRISING STEM.
b. GATE VALVES, NPS 3 AND LARGER: AWWA, CAST IRON, OS&Y RISING STEM, RESILIENT SEAATED.
c. CHECK VALVES: AWWA C508, SWING TYPE.
13.) FIELD QUALITY CONTROL
A. PIPING TESTS: CONDUCT PIPING TESTS BEFORE JOINTS ARE COVERED AND AFTER CONCRETE THRUST BLOCKS HAVE HARDENED SUFFICIENTLY. FILL PIPELINE 24 HOURS BEFORE TESTING AND APPLY TEST PRESSURE TO STABILIZE SYSTEM. USE ONLY POTABLE WATER.
B. HYDROSTATIC TESTS: TEST AT NOT LESS THAN ONE-AND-ONE-HALF TIMES WORKING PRESSURE FOR TWO HOURS, INCREASE PRESSURE IN 50-PSIG INCREMENTS AND INSPECT EACH JOINT BETWEEN INCREMENTS. HOLD AT TEST PRESSURE FOR 1 HOUR, DECREASE TO 0 PSIG, SLOWLY INCREASE AGAIN TO TEST PRESSURE AND HOLD FOR 1 MORE HOUR. MAXIMUM ALLOWABLE LEAKAGE IS 2 QUARTS PER HOUR PER 100 JOINTS. REMAKE LEAKING JOINTS WITH NEW

TOPSOIL STRIPPING
1. REMOVE SOIL AND GRASS BEFORE STRIPPING TOPSOIL.
2. STRIP TOPSOIL IN A MANNER TO PREVENT INTERMINGLING WITH UNDERLYING SUBSOIL OR OTHER WASTE MATERIALS.
3. DISSEMINATED AND AWAY FROM EDGE OF EXCAVATIONS WITHOUT INTERMINGLING WITH SUBSOIL, GRADE AND SHAPE STOCKPILES TO DRAIN SURFACE WATER. COVER TO PREVENT WINDBLOWN DUST AND EROSION BY WATER.
4. DISPOSE OF SURPLUS TOPSOIL. SURPLUS TOPSOIL IS THAT WHICH EXCEEDS QUANTITY INDICATED TO BE STOCKPILED OR REUSED.

SITE WATER DISTRIBUTION
1.) GENERAL
A. REGULATORY REQUIREMENTS
1. COMPLIANCE WITH REQUIREMENTS OF UTILITY COMPANY SUPPLYING WATER. INCLUDE TAPPING OF WATER MAINS AND BACKFLOW PREVENTION.
2. COMPLY WITH STANDARDS OF AUTHORITIES HAVING JURISDICTION FOR POTABLE-WATER-SERVICE PIPING, INCLUDING MATERIALS, INSTALLATION, TESTING, AND DISINFECTION.
B. PIPING MATERIALS SHALL BEAR LABEL, STAMP, OR OTHER MARKINGS OF SPECIFIED TESTING AGENCY.
C. INTERRUPTION OF EXISTING WATER-DISTRIBUTION SERVICE: NOTIFY OWNER AT LEAST 2 DAYS PRIOR TO INTERRUPTION OF EXISTING WATER SERVICES.
D. COORDINATE WITH UTILITY COMPANY FOR REQUIRED INSPECTIONS AND FOR CONNECTION OF WATER MAIN AND SERVICES BEFORE STARTING CONSTRUCTION.
2.) COPPER TUBE AND FITTINGS
A. SOFT COPPER TUBE: ASTM B88, TYPE K, WATER TUBE, ANNEALED TEMPER.
B. COPPER, PRESSURE-SEAL, FITTINGS
1. USE ONLY SMALLER WEIGHT COPPER FITTING WITH EPDM O-RING SEAL IN EACH END.
2. NPS 2-1/2 TO NPS 4: BRONZE FITTING WITH STAINLESS-STEEL GRIP RING AND EPDM O-RING SEAL IN EACH END.
3. BROZE FITTING: ASME B16.24, CLASS 150, WITH SOLDER-JOINT. FURNISH CLASS 300 FLANGES IF REQUIRED TO MATCH PIPING.
C. COPPER UNIONS: MSS SP-123. CAST-COPPER-ALLOY, HEXAGONAL STOCK BODY WITH BALL-AND-SOCKET, METAL-TO-METAL SEATING SURFACES, AND SOLDER-JOINT OR THREADED END.
3.) DUCTILE-IRON PIPE AND FITTINGS
A. MECHANICAL-JOINT, DUCTILE-IRON PIPE: AWWA C151, WITH MECHANICAL-JOINT BELL AND FLAN PLAIN ENDS.
1. MECHANICAL-JOINT, DUCTILE-IRON FITTINGS: AWWA C110, DUCTILE- OR GRAY-IRON STANDARD PATTERN OR AWWA C153, DUCTILE-IRON COMPACT PATTERN.
2. GLANDS, GASKETS, AND BOLTS: AWWA C111, DUCTILE- OR GRAY-IRON GLANDS, RUBBER GASKETS, AND STEEL BOLTS.
B. PUSH-ON-JOINT, DUCTILE-IRON PIPE: AWWA C151, WITH PUSH-ON-JOINT BELL AND FLAN SPIGOT END UNLESS GROOVED OR FLANGED ENDS ARE INDICATED.
C. CAST-IRON FLANGES: ASME B16.24, CLASS 150, WITH SOLDER-JOINT.
4.) PVC PIPE AND FITTINGS
PVC SCHEDULE 40 PIPE: ASTM D 1788. PVC, SCHEDULE 40 SOCKET FITTINGS: ASTM D 2466.
PVC BALLAST: ASME B16.24, CLASS 200, WITH BELL END WITH GASKET, AND WITH SPIGOT END.
5.) MECHANICAL-JOINT, DUCTILE-IRON FITTINGS: AWWA C110, DUCTILE- OR GRAY-IRON STANDARD PATTERN OR AWWA C153, DUCTILE-IRON COMPACT PATTERN.
6.) GATE VALVES
A. VALVE CAST-IRON GATE VALVES: NONRRISING-STEM, RESILIENT-SEAATED GATE VALVES: GRAY- OR DUCTILE-IRON BODY AND BONNET; WITH BRONZE OR GRAY- OR DUCTILE-IRON GATE, RESILIENT SEATS, BRONZE-STEM, AND STEM NUT.
1. STANDARD: AWWA C508.
2. MINIMUM PRESSURE RATING: 250 PSIG.
3. END CONNECTIONS: MECHANICAL JOINT.
4. INTERIOR COATING: COMPLY WITH AWWA C550.
B. GATE VALVE ACCESSORIES AND SPECIALTIES
A. TAPPING-SLEEVE ASSEMBLIES: SLEEVE AND VALVE COMPATIBLE WITH DRILLING MACHINE.
1. STANDARD: MSS SP-80.
2. VALVE: AWWA CAST-IRON OR DUCTILE-IRON OR STAINLESS-STEEL, TWO-PIECE BOLTED SLEEVE WITH FLANGED OUTLET FOR NEW BRANCH CONNECTION. INCLUDE SLEEVE MATCHING SIZE AND TYPE OF PIPE MATERIAL BEING TAPPED AND WITH RECESSED FLANGE FOR BRANCH VALVE.
3. VALVE: AWWA CAST-IRON, NONRRISING-STEM, RESILIENT-SEAATED GATE VALVE WITH ONE RAISED FACE FLANGE MATING TAPPING-SLEEVE FLANGE.
B. VALVE BOXES: COMPLY WITH AWWA M44 FOR CAST-IRON VALVE BOXES. INCLUDE TOP SECTION, ADJUSTABLE EXTENSION OF LENGTH REQUIRED FOR DEPTH OF BURIAL OF VALVE, PLUS WITH LETTERING "WATER" AND BOTTOM SECTION WITH BASE THAT FITS OVER VALVE AND WITH BARREL APPROXIMATELY 5 INCHES IN DIAMETER.
7.) BACKFLOW PREVENTERS
A. DOUBLE-CHECK DETECTOR ASSEMBLY BACKFLOW PREVENTERS:
1. STANDARDS: ASSE 1048 AND UL LISTED OR FMG APPROVED.
2. OPERATION: CONTINUOUS-PRESSURE APPLICATIONS.
3. PRESSURE LOSS: 4 PSIG MAXIMUM THROUGH MIDDLE 1/3 OF FLOW RANGE.
4. BODY: CAST IRON WITH INTERIOR LINING COMPLYING WITH AWWA C550 THAT IS FDA APPROVED.
5. END CONNECTIONS: FLANGED.
6. CONFIGURATION: DESIGNED FOR HORIZONTAL STRAIGHT THROUGH.
8.) WATER METER BOXES
A. DESCRIPTION: CAST-IRON BODY AND COVER FOR DISC-TYPE WATER METER WITH LETTERING "WATER METER" IN COVER, AND WITH SLOTTED BOTTOM BASE SECTION WITH TOP TO FIT OVER SERVICE PIPING.
9.) CONCRETE VAULTS
A. DESCRIPTION: PRECAST, REINFORCED CONCRETE VAULTS DESIGNED FOR A-16 LOAD DESIGNATION ACCORDING TO ASTM C 850. MAKE SECTION TO ASTM C 868.
1. LAIDERS: ASTM A 36A 3/8" STEEL OR P220 TYPICAL ENCL. 1.1 STEEL STEPS.
2. MANHOLE: ASTM A 36A 1/8" CLASS 150 MINIMUM TENSILE STRENGTH, GRAY-IRON TRAFFIC FRAME AND COVER.
a. DIMENSION: 24-INCH MINIMUM DIAMETER, UNLESS OTHERWISE INDICATED.
3. DRAIN: ASME A112.6.3. CAST-IRON FLOOR DRAIN WITH OUTLET OF SIZE INDICATED. INCLUDE BODY ANCHOR FLANGE, LIGHT-DUTY CAST-IRON GRATE, BOTTOM OUTLET, AND INTEGRAL OR FIELD-INSTALLED CONCRETE BALL OR CLAPPER-TYPE BACKWATER VALVE.
10.) FIRE HYDRANT
A. DRIVE-BARREL TYPE HYDRANTS: FREESTANDING, WITH ONE NPS 1-1/2 AND TWO NPS 2-1/2 OUTLETS, 5-1/4" ICH MAIN VALVE, MAIN VALVE, AND NPS 6 MECHANICAL-JOINT INLET. INCLUDE INTERIOR COATING ACCORDING TO AWWA C550. HYDRANT SHALL HAVE CAST-IRON BODY, COMPRESSION PEX VALVE PENN AGAINST PRESSURE AND CLOSING WITH PRESSURE.
1. STANDARD: AWWA C502.
2. PRESSURE RATING: 250 PSIG.
11.) FIRE DEPARTMENT CONNECTIONS
A. FIRE DEPARTMENT CONNECTIONS: FREESTANDING, WITH CAST-BRONZE BODY, THREAD INLETS ACCORDING TO TRADES AND MATCHING LOCAL FIRE DEPARTMENT HOSE THREADS, AND THREADED BOTTOM OUTLET. INCLUDE LUGGED CAPS, GASKETS, AND CHAINS, LUGGED SWIVEL CONNECTION AND DROP CLAPPER FOR EACH HOSE-CONNECTION INLET, 18-INCH, HIGH BRASS SLEEVE, AND ROUND ESCUTCHION PLATE.
12.) VALVE APPLICATIONS
A. DRAWINGS INDICATE VALVE TYPES TO BE USED, WHERE SPECIFIC VALVE TYPES ARE NOT INDICATED, THE FOLLOWING REQUIREMENTS APPLY:
1. UNDERGROUND VALVES, NPS 3 AND LARGER: AWWA CAST-IRON, NONRRISING-STEM, RESILIENT-SEAATED GATE VALVES WITH VALVE BOX.
2. USE THE FOLLOWING FOR VALVES IN VAULTS AND ABOVEGROUND:
a. GATE VALVES, NPS 2 AND SMALLER: BRONZE, NONRRISING STEM.
b. GATE VALVES, NPS 3 AND LARGER: AWWA, CAST IRON, OS&Y RISING STEM, RESILIENT SEAATED.
c. CHECK VALVES: AWWA C508, SWING TYPE.
13.) FIELD QUALITY CONTROL
A. PIPING TESTS: CONDUCT PIPING TESTS BEFORE JOINTS ARE COVERED AND AFTER CONCRETE THRUST BLOCKS HAVE HARDENED SUFFICIENTLY. FILL PIPELINE 24 HOURS BEFORE TESTING AND APPLY TEST PRESSURE TO STABILIZE SYSTEM. USE ONLY POTABLE WATER.
B. HYDROSTATIC TESTS: TEST AT NOT LESS THAN ONE-AND-ONE-HALF TIMES WORKING PRESSURE FOR TWO HOURS, INCREASE PRESSURE IN 50-PSIG INCREMENTS AND INSPECT EACH JOINT BETWEEN INCREMENTS. HOLD AT TEST PRESSURE FOR 1 HOUR, DECREASE TO 0 PSIG, SLOWLY INCREASE AGAIN TO TEST PRESSURE AND HOLD FOR 1 MORE HOUR. MAXIMUM ALLOWABLE LEAKAGE IS 2 QUARTS PER HOUR PER 100 JOINTS. REMAKE LEAKING JOINTS WITH NEW

MATERIALS AND REPEAT TEST UNTIL LEAKAGE IS WITHIN ALLOWED LIMITS.
DISINFECTION: CLEAN AND DISINFECT POTABLE WATER MAINS AS DIRECTED BY THE LOCAL AUTHORITY, OR, IF METHOD IS NOT PRESCRIBED BY THE LOCAL AUTHORITY, USE PROCEDURE DESCRIBED IN AWWA C651.
D. PLAN AND CONDUCT TESTING ACTIVITIES AND SUBMIT TO THE ENGINEER FOR APPROVAL.
14.) IDENTIFICATION
A. INSTALL CONTINUOUS UNDERGROUND DETECTABLE WARNING TAPE DURING BACKFILLING OF TRENCH FOR UNDERGROUND WATER-DISTRIBUTION PIPING. LOCATE BELOW FINISHED GRADE, DIRECTLY OVER PIPING.
SITE SANITARY SEWERS
1.) PROJECT CONDITIONS
A. INTERRUPTION OF EXISTING SANITARY SEWAGE SERVICE: COORDINATE AS REQUIRED WITH THE LOCAL SANITARY SEWER AUTHORITY BEFORE STARTING CONSTRUCTION.
B. UTILITY LOCATOR SERVICE: NOTIFY UTILITY LOCATOR SERVICE FOR AREA WHERE PROJECT IS LOCATED BEFORE BEGINNING SANITARY SEWER INSTALLATION OPERATIONS. FIELD VERIFY ALL EXISTING UTILITIES SHOWN ON THE DRAWINGS BY POT-HOLING THE LINES, SURVEY EXISTING UTILITIES AND PROVIDE HORIZONTAL AND VERTICAL LOCATION INFORMATION TO THE ENGINEER TO DETERMINE OF ANY UTILITIES WILL CONFLICT WITH THE PROPOSED DESIGN.
2.) DUCTILE-IRON, GRAVITY SEWER PIPE AND FITTINGS
A. PIPE: ASTM A 746 FOR PUSH-ON JOINTS.
B. COMPACT FITTINGS: AWWA C153, DUCTILE IRON, FOR PUSH-ON JOINTS.
C. GASKETS: AWWA C111, RUBBER.
3.) PVC PIPE AND FITTINGS
PVC SANITARY SEWER ENDS SHALL BE ASTM D 3034, RATED SDR 35 WITH INTEGRALLY MOLDED BELL ENDS, ASTM D 3034, TABLE 2, WITH FACTORY SUPPLIED ELASTOMERIC GASKETS AND LUBRICANT, DIP SANITARY SEWER LINE BE ASTM A746, CLASS 50 WITH AWWA C111, RUBBER GASKET JOINT DEVICES.
4.) CLEANOUTS
A. CAST-IRON CLEANOUTS:
1. DESCRIPTION: ASME B12.24, ROUND, GRAY-IRON HOUSING WITH CLAMPING DEVICE AND UNDER, SECURED, SCOURIATED, GRAY-IRON COVER, INCLUDE GRAY-IRON FERRULE WITH INSIDE CALK OR SPIGOT CONNECTION AND COUNTERSUNK, TAPERED-THREAD, BRASS CLOSURE PLUG.
2. INSTALLATION CLASSIFICATION: TRAFFIC RATED, HEAVY DUTY, IN ALL PAVED AREAS AND AREAS SUBJECT TO VEHICULAR TRAFFIC.
3. SEWER PIPE FITTING AND RISER TO CLEANOUT: ASTM A 74, SERVICE CLASS, CAST-IRON SOIL PIPE AND FITTING.
B. PVC CLEANOUTS: PVC BODY WITH PVC THREADED PLUG. INCLUDE PVC SEWER PIPE FITTING AND RISER TO CLEANOUT OF SAME MATERIAL AS SEWER PIPING. USE IN LIGHT DUTY APPLICATIONS WHERE THERE IS PEDESTRIAN TRAFFIC ONLY OR IN LANDSCAPED AREAS.
5.) MANHOLES
A. STANDARD PRECAST CONCRETE MANHOLES:
1. DESCRIPTION: ASTM C 478, PRECAST, REINFORCED CONCRETE, OF DEPTH INDICATED, WITH DIAMETER: 48 INCHES MINIMUM UNLESS OTHERWISE INDICATED.
2. DIAMETER: 48 INCHES MINIMUM UNLESS OTHERWISE INDICATED.
3. BALLAST: INCREASE THICKNESS OF PRECAST CONCRETE SECTIONS OR ADD CONCRETE TO BASE SECTION, AS REQUIRED TO PREVENT FLOTATION.
4. BASE SECTION: 6-INCH MINIMUM THICKNESS FOR FLOOR SLAB AND 4-INCH MINIMUM THICKNESS FOR WALLS AND BASE RISER SECTION, WITH SEPARATE BASE SLAB OR BASE SECTION WITH INTEGRAL FLOOR.
5. RISER SECTIONS: 4-INCH MINIMUM THICKNESS, OF LENGTH TO PROVIDE DEPTH INDICATED.
6. TOP SECTION: ECCENTRIC-CONE TYPE UNLESS CONCENTRIC-CONE OR FLAT-SLAB-TOP TYPE IS INDICATED, AND TOP OF CONE OF SIZE THAT MATCHES GRADE RINGS.
7. JOINT SEALANT: ASTM C 590, BITUMEN OR BUTYL RUBBER.
8. STEPS: INDIVIDUAL FRP STEPS OR FRP LADDER, WIDE ENOUGH TO ALLOW WORKER TO PLACE BOTH FEET ON ONE STEP AND DESIGNED TO PREVENT LATERAL SLIPPAGE OFF STEP. CAST OR ANCHOR STEPS INTO SIDEWALLS AT 12- TO 16-INCH INTERVALS. OMIT STEPS IF TOTAL DEPTH FROM FLOOR OF CATCH BASIN TO FINISHED GRADE IS LESS THAN 48 INCHES.
9. MANHOLE FRAMES AND COVERS:
1. DESCRIPTION: FERROUS; 24-INCH ID BY 7- TO 9-INCH RISER WITH 4-INCH, MINIMUM WIDTH RISING RINGS; MATCHING TO CONCRETE TOP DESIGN WITH LETTERING WITH LETTERING CAST INTO COVER, USING WORDING EQUIVALENT TO "STORM SEWER."
2. MATERIAL: ASTM A 536, GRADE 60-40-18 DUCTILE IRON UNLESS OTHERWISE INDICATED.
7.) INLET & JUNCTION BOXES
A. STANDARD PRECAST CONCRETE:
1. DESCRIPTION: ASTM C 478, PRECAST, REINFORCED CONCRETE, OF DEPTH INDICATED, WITH PROVISION FOR SEALANT JOINTS.
2. BASE SECTION: 6-INCH MINIMUM THICKNESS FOR FLOOR SLAB AND 4-INCH MINIMUM THICKNESS FOR WALLS AND BASE RISER SECTION, AND SEPARATE BASE SLAB OR BASE SECTION WITH INTEGRAL FLOOR.
3. RISER SECTIONS: 4-INCH MINIMUM THICKNESS, 48-INCH DIAMETER, AND LENGTHS TO PROVIDE DEPTH INDICATED.
4. TOP SECTION: ECCENTRIC-CONE TYPE UNLESS CONCENTRIC-CONE OR FLAT-SLAB-TOP TYPE IS INDICATED, AND TOP OF CONE OF SIZE THAT MATCHES GRADE RINGS.
5. JOINT SEALANT: ASTM C 590, BITUMEN OR BUTYL RUBBER.
6. STEPS: INDIVIDUAL FRP STEPS OR FRP LADDER, WIDE ENOUGH TO ALLOW WORKER TO PLACE BOTH FEET ON ONE STEP AND DESIGNED TO PREVENT LATERAL SLIPPAGE OFF STEP. CAST OR ANCHOR STEPS INTO SIDEWALLS AT 12- TO 16-INCH INTERVALS. OMIT STEPS IF TOTAL DEPTH FROM FLOOR OF CATCH BASIN TO FINISHED GRADE IS LESS THAN 48 INCHES.
7. PIPE CONNECTORS: ASTM C 923, RESILIENT, OF SIZE REQUIRED, FOR EACH PIPE CONNECTING TO BASE SECTION.
8.) STORMWATER DETENTION STRUCTURES
A. CAST-IN-PLACE CONCRETE STORMWATER DETENTION STRUCTURES, CONSTRUCTED OF REINFORCED-CONCRETE BOTTOM, WALLS, AND TOP; DESIGNED ACCORDING TO ASTM C 890 FOR A-16 (ASSTO H20-44), HEAVY TRAFFIC, STRUCTURAL LOADING, OF DEPTH, SHAPE, DIMENSIONS, AND APPURTENANCES INDICATED.
1. BALLAST: INCREASE THICKNESS OF CONCRETE AS REQUIRED TO PREVENT FLOTATION.
2. GRADE RINGS: INCLUDE TWO OR THREE REINFORCED-CONCRETE RINGS, OF 6- TO 9-INCH TOTAL THICKNESS, THAT MATCH 24-INCH DIAMETER FRAME AND COVER.
3. STEPS: INDIVIDUAL FRP STEPS OR FRP LADDER, WIDE ENOUGH TO ALLOW WORKER TO PLACE BOTH FEET ON ONE STEP AND DESIGNED TO PREVENT LATERAL SLIPPAGE OFF STEP. CAST OR ANCHOR STEPS INTO SIDEWALLS AT 12- TO 16-INCH INTERVALS. OMIT STEPS IF TOTAL DEPTH FROM FLOOR OF STRUCTURE TO FINISHED GRADE IS LESS THAN 48 INCHES.
4. FORM AND CAST WIERS AND PIPE OPENINGS AS INDICATED ON DRAWINGS.
B. SLOPE PAVED HEAD WALLS: CAST-IN-PLACE REINFORCED CONCRETE AS SHOWN ON DRAWINGS, DESIGNED FOR HEAVY-DUTY SERVICE.
9.) PIPE OUTLETS
A. PRE-CAST HEAD WALLS: PRE-CAST REINFORCED CONCRETE, WITH APRON AND TAPERED SIDES.
B. SLOPE PAVED HEAD WALLS: CAST-IN-PLACE REINFORCED CONCRETE AS SHOWN ON DRAWINGS.
C. RIPRAP BASINS: BROKEN, IRREGULARLY SIZED AND SHAPED, GRADED STONE ACCORDING TO NSSGA'S "QUARRIED STONE FOR EROSION AND SEDIMENT CONTROL," MINIMUM STONE SIZE AND DIMENSIONS AS SHOWN ON DRAWINGS.
10.) PIPING INSTALLATION
A. INSTALL LOCATOR WIRE OR TAPE 6-INCHES ABOVE ALL NON-METALLIC PIPING.
B. INSTALL BEDDING AND BACKFILL IN ACCORDANCE WITH PIPE MANUFACTURERS INSTRUCTIONS.
C. BEGIN INSTALLATION AT DOWNSTREAM PIPING CONNECTION TO OUTFALL POINT.
D. CONSTRUCT ALL HEADWALLS FLUSH WITH EXISTING AND PROPOSED EMBANKMENT SLOPES.
11.) CLEANING
A. CLEAN INTERIOR OF PIPING OF DIRT AND SUPERFLUOUS MATERIALS.)

24 HOURS ADVANCE NOTICE.
4. SUBMIT A SEPARATE REPORT FOR EACH TEST TO THE ENGINEER FOR APPROVAL.
5. AIR TESTS: TEST SANITARY SEWERAGE ACCORDING TO REQUIREMENTS OF AUTHORITIES HAVING JURISDICTION, UNH-B, AND THE FOLLOWING:
6. MANHOLES: PERFORM HYDRAULIC TEST ACCORDING TO ASTM C 969.
C. LEAKS AND LOSS IN TEST PRESSURE CONSTITUTE DEFECTS THAT MUST BE REPAIRED.
D. REPLACE LEAKING PIPING USING NEW MATERIALS, AND REPEAT TESTING UNTIL LEAKAGE IS WITHIN ALLOWED SPECIFIED.


PIPE AND FITTINGS-GENERAL
1. ALL STORMWATER PIPE, INLETS, HEADWALLS, AND RELATED APPURTENANCES SHALL MEET LOCAL D.O.T. STANDARDS.
B. ALL STORMWATER PIPE SHALL BE INSTALLED IN ACCORDANCE WITH PIPE MANUFACTURERS INSTRUCTIONS.
2.) STEEL PIPE AND FITTINGS
A. CORRUGATED-STEEL PIPE AND FITTINGS: ASTM A 760/A 760M, TYPE I WITH FITTINGS OF SIMILAR FORM AND CONSTRUCTION AS PIPE.
1. STANDARD-JOINT BANDS: CORRUGATED STEEL.
2. COATING: ALUMINUM OR BITUMINOUS.
3.) PE PIPE AND FITTINGS
A. CORRUGATED PE DRAINAGE PIPE AND FITTINGS NPS 3 TO NPS 10: AASHTO M 2540M, NPS 3 TO NPS 48: AASHTO M 2540 TYPE 5, WITH SMOOTH WATERWAY FOR COUPLINGS.
B. SLIGHT COUPLINGS: PE SLEEVE WITH ASTM D 1556, TYPE 2, OF A. G. MATERIAL. CLASS III. WALL MATERIAL THAT MATES WITH TUBE AND FITTINGS.
4.) PVC CORRUGATED PIPE AND FITTINGS
A. CORRUGATED-STEEL PIPE AND FITTINGS NPS 4 TO NPS 10: AASHTO M 2540, TYPE I FM 49, 49 PSI STIFFNESS WHEN TESTED IN ACCORDANCE WITH ASTM D 2412. PVC ROUND HAVING A MINIMUM CELL CLASSIFICATION OF 1264 AS DEFINED IN ASTM D 784. FITTINGS: SMOOTH INTERIOR. ASTM F4153 SECTION 2.2.3 OR 2.4. JOINTS SHALL BE MADE WITH INTEGRALLY-FORMED BELL AND SPIGOT GASKET CONNECTION. MANUFACTURER SHALL PROVIDE DOCUMENTATION SHOWING NO LEAKAGE WHEN TESTED. PIPE JOINTS ARE TESTED IN ACCORDANCE WITH ASTM D3212 ELASTOMERIC SEALS (GASKETS) SHALL MEET ASTM F477.
5.) REINFORCED-CONCRETE SEWER PIPE AND FITTINGS: ASTM C 76 - BELL-AND-SPIGOT OR TONGUE-AND-GROOVE WITH GASKETS AND FITTINGS WITH ASTM C 443, RUBBER GASKETS OR SEALANT JOINTS WITH ASBESTOS, BITUMEN OR BUTYL RUBBER SEALANT. CLASS III WALL B. CAST-IRON AREA DRAINING: ASME A12.8, GRAY-IRON ROUND BODY WITH ANCHOR FLANGE AND ROUND GRIP. INCLUDE BOTTOM BUTTLE WITH INSIDE CALK OR SPIGOT CONNECTION, OF SIZES INDICATED.
6.) MANHOLES
A. STANDARD PRECAST CONCRETE MANHOLES:
1. DESCRIPTION: ASTM C 478, PRECAST, REINFORCED CONCRETE, OF DEPTH INDICATED, WITH DIAMETER: 48 INCHES MINIMUM UNLESS OTHERWISE INDICATED.
2. DIAMETER: 48 INCHES MINIMUM UNLESS OTHERWISE INDICATED.
3. BALLAST: INCREASE THICKNESS OF PRECAST CONCRETE SECTIONS OR ADD CONCRETE TO BASE SECTION, AS REQUIRED TO PREVENT FLOTATION.
4. BASE SECTION: 6-INCH MINIMUM THICKNESS FOR FLOOR SLAB AND 4-INCH MINIMUM THICKNESS FOR WALLS AND BASE RISER SECTION, WITH SEPARATE BASE SLAB OR BASE SECTION WITH INTEGRAL FLOOR.
5. RISER SECTIONS: 4-INCH MINIMUM THICKNESS, OF LENGTHS TO PROVIDE DEPTH INDICATED.
6. TOP SECTION: ECCENTRIC-CONE TYPE UNLESS CONCENTRIC-CONE OR FLAT-SLAB-TOP TYPE IS INDICATED, AND TOP OF CONE OF SIZE THAT MATCHES GRADE RINGS.
7. JOINT SEALANT: ASTM C 590, BITUMEN OR BUTYL RUBBER.
8. STEPS: INDIVIDUAL FRP STEPS OR FRP LADDER, WIDE ENOUGH TO ALLOW WORKER TO PLACE BOTH FEET ON ONE STEP AND DESIGNED TO PREVENT LATERAL SLIPPAGE OFF STEP. CAST OR ANCHOR STEPS INTO SIDEWALLS AT 12- TO 16-INCH INTERVALS. OMIT STEPS IF TOTAL DEPTH FROM FLOOR OF CATCH BASIN TO FINISHED GRADE IS LESS THAN 48 INCHES.
9. MANHOLE FRAMES AND COVERS:
1. DESCRIPTION: FERROUS; 24-INCH ID BY 7- TO 9-INCH RISER WITH 4-INCH, MINIMUM WIDTH RISING RINGS; MATCHING TO CONCRETE TOP DESIGN WITH LETTERING WITH LETTERING CAST INTO COVER, USING WORDING EQUIVALENT TO "STORM SEWER."
2. MATERIAL: ASTM A 536, GRADE 60-40-18 DUCTILE IRON UNLESS OTHERWISE INDICATED.
7.) INLET & JUNCTION BOXES
A. STANDARD PRECAST CONCRETE:
1. DESCRIPTION: ASTM C 478, PRECAST, REINFORCED CONCRETE, OF DEPTH INDICATED, WITH PROVISION FOR SEALANT JOINTS.
2. BASE SECTION: 6-INCH MINIMUM THICKNESS FOR FLOOR SLAB AND 4-INCH MINIMUM THICKNESS FOR WALLS AND BASE RISER SECTION, AND SEPARATE BASE SLAB OR BASE SECTION WITH INTEGRAL FLOOR.
3. RISER SECTIONS: 4-INCH MINIMUM THICKNESS, 48-INCH DIAMETER, AND LENGTHS TO PROVIDE DEPTH INDICATED.
4. TOP SECTION: ECCENTRIC-CONE TYPE UNLESS CONCENTRIC-CONE OR FLAT-SLAB-TOP TYPE IS INDICATED, AND TOP OF CONE OF SIZE THAT MATCHES GRADE RINGS.
5. JOINT SEALANT: ASTM C 590, BITUMEN OR BUTYL RUBBER.
6. STEPS: INDIVIDUAL FRP STEPS OR FRP LADDER, WIDE ENOUGH TO ALLOW WORKER TO PLACE BOTH FEET ON ONE STEP AND DESIGNED TO PREVENT LATERAL SLIPPAGE OFF STEP. CAST OR ANCHOR STEPS INTO SIDEWALLS AT 12- TO 16-INCH INTERVALS. OMIT STEPS IF TOTAL DEPTH FROM FLOOR OF CATCH BASIN TO FINISHED GRADE IS LESS THAN 48 INCHES.
7. PIPE CONNECTORS: ASTM C 923, RESILIENT, OF SIZE REQUIRED, FOR EACH PIPE CONNECTING TO BASE SECTION.
8.) STORMWATER DETENTION STRUCTURES
A. CAST-IN-PLACE CONCRETE STORMWATER DETENTION STRUCTURES, CONSTRUCTED OF REINFORCED-CONCRETE BOTTOM, WALLS, AND TOP; DESIGNED ACCORDING TO ASTM C 890 FOR A-16 (ASSTO H20-44), HEAVY TRAFFIC, STRUCTURAL LOADING, OF DEPTH, SHAPE, DIMENSIONS, AND APPURTENANCES INDICATED.
1. BALLAST: INCREASE THICKNESS OF CONCRETE AS REQUIRED TO PREVENT FLOTATION.
2. GRADE RINGS: INCLUDE TWO OR THREE REINFORCED-CONCRETE RINGS, OF 6- TO 9-INCH TOTAL THICKNESS, THAT MATCH 24-INCH DIAMETER FRAME AND COVER.
3. STEPS: INDIVIDUAL FRP STEPS OR FRP LADDER, WIDE ENOUGH TO ALLOW WORKER TO PLACE BOTH FEET ON ONE STEP AND DESIGNED TO PREVENT LATERAL SLIPPAGE OFF STEP. CAST OR ANCHOR STEPS INTO SIDEWALLS AT 12- TO 16-INCH INTERVALS. OMIT STEPS IF TOTAL DEPTH FROM FLOOR OF STRUCTURE TO FINISHED GRADE IS LESS THAN 48 INCHES.
4. FORM AND CAST WIERS AND PIPE OPENINGS AS INDICATED ON DRAWINGS.
B. SLOPE PAVED HEAD WALLS: CAST-IN-PLACE REINFORCED CONCRETE AS SHOWN ON DRAWINGS, DESIGNED FOR HEAVY-DUTY SERVICE.
9.) PIPE OUTLETS
A. PRE-CAST HEAD WALLS: PRE-CAST REINFORCED CONCRETE, WITH APRON AND TAPERED SIDES.
B. SLOPE PAVED HEAD WALLS: CAST-IN-PLACE REINFORCED CONCRETE AS SHOWN ON DRAWINGS.
C. RIPRAP BASINS: BROKEN, IRREGULARLY SIZED AND SHAPED, GRADED STONE ACCORDING TO NSSGA'S "QUARRIED STONE FOR EROSION AND SEDIMENT CONTROL," MINIMUM STONE SIZE AND DIMENSIONS AS SHOWN ON DRAWINGS.
10.) PIPING INSTALLATION
A. INSTALL LOCATOR WIRE OR TAPE 6-INCHES ABOVE ALL NON-METALLIC PIPING.
B. INSTALL BEDDING AND BACKFILL IN ACCORDANCE WITH PIPE MANUFACTURERS INSTRUCTIONS.
C. BEGIN INSTALLATION AT DOWNSTREAM PIPING CONNECTION TO OUTFALL POINT.
D. CONSTRUCT ALL HEADWALLS FLUSH WITH EXISTING AND PROPOSED EMBANKMENT SLOPES.
11.) CLEANING
A. CLEAN INTERIOR OF PIPING OF DIRT AND SUPERFLUOUS MATERIALS.)

ENGINEER



Foresite Group, Inc. w | www.fg-inc.net
3740 Davinci Ct. o | 770.368.1399
Suite 100 f | 770.368.1944
Peachtree Corners, GA 30092

DEVELOPER



75 LANGLEY DR
LAWRENCEVILLE, GEORGIA 30046
770-922-9864

CONTACT: MR. REX SCHUDER

ELISHA WINN HOUSE
SITE IMPROVEMENTS

908 DACULA RD
DACULA, GA 30019
LL # 1, DISTRICT 2, ZONE R-100
PARCEL #P2001 158

PROJECT

SEAL



4/08/19
GEORGIA LEVEL II CERTIFIED PROFESSIONAL # 0000058923
EXPIRATION DATED: 08/21/2021

REVISIONS DATE

REVISIONS	DATE
GWINNETT CO. RESUBMITTAL	03/20/2019
GWINNETT CO. RESUBMITTAL	03/25/2019

PROJECT MANAGER: AWP
DRAWING BY: SSH
JURISDICTION: GWINNETT COUNTY
DATE