

WIRING SCHEDULE

- ① 6#6 + 1#6G IN 1 1/4" C
 - ② 4#10 + 1#10G IN 3/4" C
 - ③ 2#10 + 1#10G IN 3/4" C
 - ④ 8#6 + 1#6G IN 1 1/2" C
 - ⑤ 12#8 + 1#8G IN 1 1/2" C
 - ⑥ 12#6 + 1#6G IN 2" C
 - ⑦ 6#8 + 1#8G IN 1 1/4" C
 - ⑧ 8#8 + 1#8G IN 1 1/4" C
 - ⑨ 2#8 + 1#8G IN 3/4" C
 - ⑩ 3#10 + 1#10G IN 3/4" C
 - ⑪ 2#10 + 1#10G IN 1 1/2" C
 - ⑫ 3#8 + 1#8G IN 1" C
 - ⑬ 10#8 + 1#8G IN 1 1/4" C
- ALL CONDUCTORS ARE TO BE COPPER

NOTE


1. ALL SITE OUTLETS ARE TO BE FIELD LOCATED BY THE OWNER AND/OR THE LANDSCAPE ARCHITECT PRIOR TO INSTALLATION.

ENGINEER:

FORESITE
group

Foresite Group, Inc. w | www.fg-inc.net
3740 Davinci Ct. o | 770.368.1399
Suite 100 f | 770.368.1944
Peachtree Corners, GA 30092

DEVELOPER:



75 LANGLEY DR.
LAWRENCEVILLE, GEORGIA 30048
770-822-8884

CONTACT: MR. REX SCHUDER

PROJECT:

SEAL:



REVISIONS DATE

REVISIONS	DATE

PROJECT MANAGER: ###

DRAWING BY: CPP

JURISDICTION: GWINNETT COUNTY

DATE: 02/12/2019

SCALE: AS SHOWN

TITLE:

PARTIAL SITE PLAN - LIGHTING

SHEET NUMBER:


E-2

COMMENTS: ###

JOBFILE NUMBER: 223.082



1 PARTIAL SITE PLAN - LIGHTING
E-2 SCALE: 1" = 20'-0"



W&A PROJECT NUMBER - 18040

2300 Lake Park Dr. Suite 250
Smyrna, Georgia 30080
Voice: 770-459-3000 Fax: 770-459-4388
WOMACK & ASSOCIATES
COA #PEF006530 EXP - 06/30/2020
PLOT SCALE: 1"=1'