2 ELEVATION: REAR - G-1

SCALE: 1/8"=1'-0"

ELEVATION NOTES:
1. SEE A7.1 FOR WINDOW SCHEDULE
2. SEE FINISH NOTES FOR EXTERIOR COLOR SCHEDULE
3. FIELD VERIFY FINAL SIDEWALK GRADE AT EXT STAIR
4. PROVIDE ONE WINDOW PER SLEEPING UNIT W 5.7 SF EGRESS AREA
5. PAINT ALL WALL & ROOF PENETRATIONS TO MATCH ADJACENT SURFACE
6. RE: LANDSCAPE DWGS FOR MECH UNIT SCREENING

1 ELEVATION: FRONT - G-1

SCALE: 1/8"=1'-0"

EXTERIOR MATERIALS SCHEDULE	
BRICK	PT - 65HR 75 POLAR BEAR
SIDING	PT - 65HR 75 POLAR BEAR
COLUMNS	PT- 65HR 77OP-3 DARK ASH
TRIM	PT - 65HR 75 POLAR BEAR
FACIA	PT - 65HR 75 POLAR BEAR
SHINGLES	GAF TIMBERLINE CHARCOAL
METAL RAILINGS	BLACK
DOWNSPOUT	PRE FINISHED BLACK

Order Plans @ WWW.LDLine.com

Pate Design Group, Inc.
Architecture / Interiors
4168 Abbotts Bridge Road
Duluth, Georgia 30097
(p) 770.814.0885
(f) 770.814.0888
Kirby@patedesigngroup.com

G-1 AND G-2
WISTERIA RIDGE
Will-O-War LLC
75 North Main Street
Watkinsville, GA 30677

Issue & Revisions:

No.	Date	Description
1	040119	CLARFICATION

BUILDING ELEVATIONS G-1 BLDG

Drawn: MWB
Checked: KEP
Contract No.: 07-03
Scale: AS NOTED

STATE OF GEORGIA — REGISTERED ARCHITECT

A3.1
040119 of sheets

RELEASED FOR CONSTRUCTION

THIS DRAWING IS THE PROPERTY OF PATE DESIGN GROUP AND IS NOT TO BE COPIED IN WHOLE OR IN PART. IT IS TO BE USED FOR THE PROJECT AND SITE SPECIFICALLY IDENTIFIED HEREIN AND IS NOT TO BE USED IN ANY OTHER PROJECT. IT IS TO BE RETURNED UPON REQUEST.