

GENERAL NOTES

- VOLUME DAMPERS LOCATED ABOVE HARD CEILING SHALL BE EQUIPPED WITH CABLE OPERATORS AT FACE OF DIFFUSER OR REGISTER.
- PROVIDE ACCESS PANEL FOR EQUIPMENT ABOVE HARD CEILING.

(X) KEYNOTES

- PROVIDE AND INSTALL NEW WALL THERMOSTAT WHERE INDICATED. SEE HVAC SEQUENCING OF CONTROLS, SHEET M002.
- COMBINE TEMPERATURE AND HUMIDITY SENSORS MOUNTED ON WALL AT 60" AFF. HUMIDITY FUNCTION IS TO BE TIED BACK TO RTU. THE TEMPERATURE FUNCTION TIES BACK TO THE THERMOSTAT IN THE OFFICE.
WOODER WALL VENT WITH SPRING LOADED DAMPER, MET AND BUG SCREEN. COLOR TO BE WHITE. COORDINATE MOUNTING HEIGHT AND LOCATION WITH FINISH ELEVATIONS.
PROVIDE AND INSTALL HEAT TEMPERATURE SENSOR AT CEILING.

HFA
HARRISON FRENCH & ASSOCIATES, LTD.
1705 S. Walton Blvd., Suite 3
Bentonville, Arkansas 72712
www.hfa-ae.com
1-479-273-7780

STIPULATION FOR REUSE
THIS DRAWING WAS PREPARED FOR MICCO, INC. AND IS NOT TO BE REPRODUCED OR USED FOR ANY OTHER PROJECT WITHOUT THE WRITTEN CONSENT OF HARRISON FRENCH & ASSOCIATES, LTD. THE USE OF THIS DRAWING FOR ANY OTHER PROJECT WITHOUT THE WRITTEN CONSENT OF HARRISON FRENCH & ASSOCIATES, LTD. IS PROHIBITED. THE ENGINEER'S RESPONSIBILITY IS LIMITED TO THE PROJECT AND SHALL NOT BE EXTENDED TO ANY OTHER PROJECTS.

Cumberland
Store Number: 9747
8090 US1
Micco, FL 32976
JOB NUMBER: 411-17-00190

ISSUE BLOCK

CLIENT REVIEW	08/30/19
100%	09/27/19

CHECKED BY: BRT
DRAWN BY: BRT

HVAC FLOOR PLAN

SHEET: M100

1 HVAC FLOOR PLAN
SCALE: 1/4"=1'-0"

Order Plans @ www.lidline.com

WWW.LIDLINE.COM

