

## PLANT LIST

PLANT NAME		PROJECT: HEARD CO. BOE OFFICE			
		QTY	SIZE	SPACING	DESCRIPTION
OCTOBER GLORY MAPLE <i>Acer rubrum</i> 'October Glory'		4	2" CAL	25'	FULL, WELL BRANCHED, UNIFORM, STAKED
YOSHINO CHERRY (light pink flower) <i>Prunus x yedoensis</i>		3	2" CAL	25'	FULL, WELL BRANCHED, UNIFORM, STAKED
LIMELIGHT HYDRANGEA <i>Hydrangea paniculata</i> 'Limelight'		2	5 GAL	6'	FULL, WELL BRANCHED, NOT POT BOUND
BURFORD HOLLY <i>Ilex cornuta</i> 'Burfordi'		4	7 GAL	36"	FULL, WELL BRANCHED, NOT POT BOUND
DWARF BURFORD HOLLY <i>Ilex cornuta</i> 'Dwarf Burford'		26	3 GAL	30"	FULL, WELL BRANCHED, NOT POT BOUND
NELLIE R. STEVENS HOLLY <i>Ilex</i> 'Nelle R. Stevens'		7	5-6'	8'	FULL, WELL BRANCHED, NOT POT BOUND
MISCANTHUS <i>Miscanthus sinensis</i> 'Adagio'		2	3 GAL	4'	FULL, WELL BRANCHED, NOT POT BOUND
DISTYLUM COPPERTONE <i>Distylium PLIDIST-II'</i> PP25,304		16	3 GAL	30"	FULL, WELL BRANCHED, NOT POT BOUND
BIG BLUE LIRIOPE <i>Liriope muscari</i> 'Royal purple'		68	4" pot	16"	FULL, WELL BRANCHED, NOT POT BOUND
ANNUALS amended & mulched with hardwood mulch		72	4" pot	sum 9-12" oc wint. 6-8" oc	SELECTED BY OWNER FOR APPROPRIATENESS FOR THE TIME OF YEAR
PINE STRAW Long leaf pine straw		*	BALE		CLEAN, FREE OF DEBRIS, SPREAD 3-4" THICK
HARDWOOD MULCH Color: Black		*	BAG/ BULK		CLEAN, SPREAD 4 - 6" THICK
TENNESSEE FIELDSTONE BOULDER		2	600lb		CLEAN, IRREGULAR, 14-18" THICK, 24-36" L&W

\* QUANTITY AS REQUIRED TO COVER BEDS AS DESCRIBED

## PLANTING NOTES:

1. ALL PLANTING BEDS SHALL BE MULCHED WITH 3" THICK CLEAN LONG LEAF (NEEDLE) PINE STRAW.
2. ALL TREES SHALL BE CIRCLED WITH A 6 FOOT DIAMETER CIRCLE OF PINE STRAW.
3. ALL PLANTING BEDS SHALL HAVE WEED BARRIER INSTALLED.
4. ROOT BALL SHALL BE SET 1/2 TO 1" HIGHER THAN THE EXISTING GRADE FOR ALL SHRUBS AND TREES.
5. PRUNE OUT ALL BROKEN LIMBS OR PROBLEM BRANCHES.
6. BACKFILL MIXTURE FOR TREES AND SHRUBS SHALL BE THREE (3) PARTS NATIVE SOIL AND ONE (1) PART NATURE'S HELPER (OR EQUAL).
7. ALL PLANT MATERIAL SHALL BE WATERED IMMEDIATELY AFTER PLANTING.
8. ALL PLANTING BEDS AND TREE RINGS SHALL BE NEATLY DETAILED WITH A FLAT SHOVEL EDGE TO FORM A CRISP EDGE BETWEEN THE GRASS AND THE PLANTING BED.
9. ALL SOD SHALL BE INSTALLED AS SOON AS IT IS DELIVERED TO THE SITE. INSTALL SOD PERPENDICULAR TO THE SLOPE, AND STAKE OR STAPLE IF NECESSARY. ROLL SOD AND WATER DAILY.
10. LANDSCAPE CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING POSITIVE DRAINAGE AWAY FROM BUILDINGS, PLANTED AND SODDED AREAS. ADD SOIL IF NECESSARY.
11. FINE GRADE AREAS AND PLANTING AREAS TO PROVIDE POSITIVE DRAINAGE TO STORM SEWER.
12. SPRAYING TREES AND WEEDS WITH GRASS & WEED KILLER PRIOR TO PLANTING. TREES AND GRASS SHALL BE ALLOWED TO DIE PRIOR TO PLANTING. NEW PLANT MATERIALS, REMOVE ROOTS, ROCKS AND DEBRIS PRIOR TO GRADING AND PLANT INSTALLATIONS.
13. PLANTING BEDS SHALL BE MULCHED WITH BLACK HARDWOOD MULCH.

0 30 60  
SCALE: 1" = 20'

SA&E PROJECT NUMBER	01-615-057		
BID PACKAGE/PHASING	BP-1		
ISSUED FOR CONSTRUCTION	10/15/2019		
REVISIONS			
R #	Doc #	Date	
1	AD1	11.4.2019	

**Southern A&E**  
7951 Troon Circle  
Austell, Ga 30168  
(770) 419-7777  
architects & engineers

© COPYRIGHT 2019 BY SOUTHERN A&E LLC. ALL RIGHTS RESERVED.  
THIS DOCUMENT IS THE PROPERTY OF SOUTHERN A&E LLC AND SHALL NOT BE COPIED OR  
REPRODUCED IN WHOLE OR IN PART WITHOUT EXPRESS WRITTEN CONSENT FROM SOUTHERN A&E  
LLC.

ADD ALTERNATE #1  
BOARD OF EDUCATION OFFICE FOR:  
**HEARD COUNTY SCHOOL**  
4647 PEA RIDGE ROAD, FRANKLIN, GA 30127  
**HEARD COUNTY SCHOOL SYSTEM**  
FRANKLIN, GEORGIA

LANDSCAPE PLAN



DRAWING NUMBER

L101

## CAUTION:

THE UTILITIES SHOWN ARE SHOWN FOR THE CONTRACTORS CONVENIENCE ONLY. OTHER UTILITIES MAY BE PRESENT BUT NOT SHOWN ON THESE DRAWINGS. THE ARCHITECT & ENGINEER ASSUME NO RESPONSIBILITY FOR THE UTILITY LOCATIONS SHOWN, AND IT SHALL BE THE CONTRACTOR'S RESPONSIBILITY TO DETERMINE THE EXACT LOCATIONS OF ALL UTILITIES WITHIN THE LIMITS OF THE WORK. ALL DAMAGE MADE TO THE EXISTING UTILITIES BY THE CONTRACTOR SHALL BE REPAIRED TO A "LIKE NEW" CONDITION. THE CONTRACTOR SHALL BEAR THE SOLE RESPONSIBILITY FOR ANY LOSSES THAT OCCUR FROM DAMAGES TO THE EXISTING UTILITIES.

