


#	KEYNOTE DESCRIPTION
C1	PROVIDE CONNECTION FROM FIRE ALARM SYSTEM TO OCCUPANCY SENSOR POWER PACK AND/OR RELAY PANEL FOR OVERRIDE OF OCCUPANCY SENSOR(S) IN THIS SPACE UPON ACTIVATION OF FIRE ALARM. PER NFPA-101.
C6	AT THIS OPENING, PROVIDE CONDUIT AND BOXES FOR ACCESS CONTROL DOOR ROUGH-IN. PER DETAIL.
C14	PROVIDE CONNECTION FROM FIRE ALARM CONTROL MODULE (IF SMOKE RATED) OR FIRE ALARM MONITOR MODULE (IF FIRE RATED ONLY) TO MOTOR OPERATED COILING DOOR CLOSER AND DOOR ALARM SIREN AND BEACON. REFER TO SHOP DRAWINGS FOR COILING DOOR ASSEMBLY. PROVIDE RELAY AS REQUIRED.
C15	PROVIDE AND INSTALL FIRE ALARM CONTROL MODULE TO MUTE SOUND SYSTEM UPON ACTIVATION OF THE FIRE ALARM SYSTEM.
C16	DATA DROP TO BE INSTALLED IN RECESSED DISPLAY WALL BOX.
C17	AUDITORIUM PROJECTOR W/ WALL MOUNT BRACKET. REFER VIDEO SYSTEM ONE-LINE DIAGRAM AND SECTION 27 41 16 FOR ADDITIONAL REQUIREMENTS.
C18	INSTALL THIS DATA OUTLET IN SOUND SYSTEM FLOOR BOX AT THIS LOCATION. COORDINATE INSTALLATION REQUIREMENTS WITH SOUND SYSTEM AND ELECTRICAL CONTRACTOR PRIOR TO ROUGH-IN. FURNISH AND INSTALL 1" CONDUIT FROM EACH SOUND SYSTEM FLOOR BOX BELOW GRADE TO J-B in AUDIO 157. RACEWAY FOR UTP INSTALLATION TO PATCH PANEL/ NETWORK SWITCH LOCATED IN AUDIO RACK. LEAVE EACH RACEWAY WITH PULL STRING INSTALLED AND TERMINATED WITH BUSHED OPENINGS.
C19	DIGITAL VIDEO OUTPUT PLATE IN COMMON AV DISPLAY WALL BOX AT THIS LOCATION. PROVIDE (1) CAT 6 UTP CABLE FROM DIGITAL VIDEO INPUT DEVICE TO VIDEO SWITCHER/SPLITTER LOCATED IN AUDITORIUM VIDEO SYSTEM RACK (AVSR) IN CONTROL ROOM 144. REFER TO SECTION 27 41 16 FOR ADDITIONAL REQUIREMENTS.
C20	ALL LOW VOLTAGE CABLING ROUTED THROUGH THIS SPACE SHALL BE INSTALLED IN RACEWAY. RACEWAY SHALL BE PAINTED TO MATCH ROOF AND/OR WALL COLOR.
C21	DIGITAL VIDEO INPUT PLATE IN SOUND SYSTEM FLOOR BOX AT THIS LOCATION. PROVIDE (1) CAT 6 UTP CABLE FROM DIGITAL VIDEO INPUT DEVICE TO VIDEO SWITCHER/SPLITTER LOCATED IN AUDITORIUM VIDEO SYSTEM RACK (AVSR) IN CONTROL ROOM 144. REFER TO SECTION 27 41 16 FOR ADDITIONAL REQUIREMENTS.
C22	UTP CONDUIT ROUTED FROM OUTLET BOX AT CAMERA BELOW GRADE BACK TO IDF RACK LOCATED IN DATA 156.
C23	DATA DROP(S) INSTALLED ABOVE SUSPENDED CLOUD.
C25	DATA DROP INSTALLED IN ACCESS CONTROL HEADEND PANEL.
C33	AUDITORIUM DESKTOP TOUCHSCREEN PANEL FOR CONTROL OF AUDIO, VIDEO AND LIGHTING. PROVIDE UTP CABLING TO PATCH PANEL IN AVSR. REFER TO VIDEO SYSTEM ONE-LINE ON DRAWING E508 AND SECTION 27 41 16 FOR ADDITIONAL REQUIREMENTS.
C34	ROUTE DATA NETWORK CABLING TO PATCH PANEL AND NETWORK SWITCH LOCATED IN AUDITORIUM OR RACK IN CONTROL 144. ROUTE 1" TO ACR J-BOX.
C35	FURNISH AND INSTALL WALL DISPLAY UNIT AND ARTICULATING WALL MOUNT AT THIS LOCATION. REFER TO SECTION 27 41 16 FOR REQUIREMENTS.

3 LEVEL 02 - AUDITORIUM - MEZZANINE SPECIAL SYSTEMS PLAN  
1/8" = 1'-0"

1 LEVEL 01 - AUDITORIUM - SPECIAL SYSTEMS PLAN  
1/8" = 1'-0"



SA&E PROJECT NUMBER	01-615-056
BID PACKAGE	BP-1
ISSUED FOR CONSTRUCTION	10/15/2019
<b>Southern AE</b>	
7951 Tricon Circle Austell, Ga 30168 (770) 519-7777 architects & engineers	REVISIONS R # Doc # Date 1 AD1 11.4.2019

FACILITY CODE NUMBER: 674-0110  
GYMNASIUM/AUDITORIUM FOR:  
**HEARD COUNTY SCHOOLS**  
545 MAIN STREET, FRANKLIN, GA 30217  
**HEARD COUNTY SCHOOL SYSTEM**  
FRANKLIN, GEORGIA

AUDITORIUM - LEVEL 01 - SPECIAL SYSTEMS PLAN

DRAWING NUMBER  
**E112**

Order Plans @ www.LDHL.com