


Order Plans @

1 LEVEL 01 - AUDITORIUM - THEATRICAL SOUND & INTERCOM PLAN
1/8" = 1'-0"

2 LEVEL 02 - AUDITORIUM - MEZZANINE THEATRICAL SOUND & INTERCOM PLAN
1/8" = 1'-0"

#	KEYNOTE DESCRIPTION
12	SOUND SYSTEM SURFACE MOUNTED TECHNICAL WALL PANEL PER SECTION 27 51 16. TECHNICAL PANEL SHALL BE FURNISHED BY SOUND SYSTEM CONTRACTOR AND INSTALLED BY ELECTRICAL CONTRACTOR. COORDINATE INSTALLATION WITH SOUND SYSTEM SHOP DRAWINGS PRIOR TO ROUGH-IN. MOUNT SMP AND TP-2 36" AFF TO BOTTOM OF PANEL AND TP-1 18" AFF TO BOTTOM OF PANEL.
13	WIRELESS MICROPHONE REMOTE ANTENNAS. PROVIDE A SINGLE GANG OUTLET BOX 6" ABOVE PROSCENIUM OPENING WITH CONDUIT AS INDICATED BACK TO STAGE RACK. COORDINATE EXACT LOCATION WITH SOUND SYSTEM VENDOR SHOP DRAWINGS PRIOR TO ROUGH-IN.
14	THEATRICAL SOUND SYSTEM STAGE RACK. REFER TO SECTION 27 51 16 FOR REQUIREMENTS.
15	SOUND SYSTEM SURFACE MOUNT JUNCTION BOXES. FURNISHED AND INSTALLED BY ELECTRICAL CONTRACTOR. REFER TO AUDITORIUM SOUND SYSTEM CONDUIT RISER FOR JUNCTION BOX SIZE AND COORDINATE INSTALLATION WITH SECTION 27 51 16 CONTRACTOR PRIOR TO ROUGH-IN.
16	CHOIR MICROPHONES PENDANT HUNG FROM OUTLET BOXES ATTACHED TO STAGE ELECTRIC #1. UTILIZE PANTOGRAPH FOR CABLE SUPPORT TO GRID IRON JUNCTION BOX AT ROOF DECK. COORDINATE PANTOGRAPH LOCATION AND CABLE LENGTH REQUIREMENT WITH RIGGING CONTRACTOR INSTALLER PRIOR TO ROUGH-IN.
17	CONTROL BOOTH SELF-POWERED MONITOR SPEAKERS & ASSOCIATED DESKSTANDS. REFER TO SECTION 27 51 16 FOR CABLING AND SPEAKER REQUIREMENTS.
18	SOUND SYSTEM FLUSH MOUNT JUNCTION BOX (JB-3). FURNISHED AND INSTALLED BY ELECTRICAL CONTRACTOR. LOCATE BOX BEHIND SOURCE RACK. REFER TO AUDITORIUM SOUND SYSTEM CONDUIT RISER FOR JUNCTION BOX SIZE AND COORDINATE INSTALLATION REQUIREMENTS WITH SECTION 27 51 16 CONTRACTOR PRIOR TO ROUGH-IN.
19	SOUND SYSTEM MAIN LOUDESPEAKERS MOUNTED TO WALL WITH ADJUSTABLE BRACKET. MOUNT SPEAKER 11'-6" ABOVE STAGE FLOOR, MEASURED TO BOTTOM OF SPEAKER. COORDINATE SPEAKER COMMUNICATION AND POWER OUTLET BOX LOCATIONS W/ RESPECTIVE INSTALLERS PRIOR TO ROUGH-IN OF SPEAKER.
110	SOUND SYSTEM DATA NETWORK OUTLET INSTALLED 14'-6" AFF OF STAGE W/ 1" CONDUIT BACK TO JB-1 LOCATED BEHIND SOUND STAGE RACK IN AUDIO 157.
111	SOUND SYSTEM DATA NETWORK OUTLET FLUSH MOUNTED IN CEILING WITH UTP CABLING BACK TO PATCH PANEL IN SOUND SYSTEM RACK. PROVIDE PATCH CABLES AS REQUIRED FOR CONNECTION TO AUDIO NETWORK.
112	ROUTE UTP CABLING IN A 1" BACK TO JB-1 AT SOUND SYSTEM RACK IN AUDIO 157. TERMINATE CABLING ON PATCH PANEL IN RACK.



SA&E PROJECT NUMBER	01-615-056
BID PACKAGE	BP-1
ISSUED FOR CONSTRUCTION	10/15/2019
Southern AE	
7951 Tricon Circle Austell, Ga 30168 (770) 519-7777 architects & engineers	REVISIONS R# Doc# Date 1 AD1 11.4.2019

FACILITY CODE NUMBER: 674-0110
GYMNASIUM/AUDITORIUM FOR:
HEARD COUNTY SCHOOLS
545 MAIN STREET, FRANKLIN, GA 30217
HEARD COUNTY SCHOOL SYSTEM
FRANKLIN, GEORGIA

AUDITORIUM - LEVEL 01 - THEATRICAL
SOUND & INTERCOM PLAN

		DRAWING NUMBER
		E114