



CLEAN ROOM SCOPE OF WORK (ROOMS 102, 103, 105, 106, 107, 108, 110, 111, 112 AND THOSE PERIMETER WALLS SURROUNDING THESE ROOMS.)

THE FOLLOWING NUMBERED ITEMS TO BE PERFORMED BY GC'S NORMAL SUBCONTRACTORS

1. ALL WALLS FRAMED WITH COLUMNS IMBEDDED AND ROUGH OPENINGS CREATED FOR DOORS & WINDOWS. **PRECISE PLACEMENT OF WALLS IS CRITICAL FOR LAYOUT & STRUCTURAL COLUMN PLACEMENT & REQUIRED GRID SPACING**
2. INSTALL 6 MILL PLY VAPOR BARRIER ON INTERIOR STUD FACE BEFORE APPLYING DRYWALL ON ALL PERIMETER WALLS OF ROOMS 102, 103, 105, 106, 107, 108, 110, 112, & 112.
3. PROVIDE & INSTALL ALL DRYWALL, TAPED & FLOATED
4. PROVIDE & INSTALL ALL CLEAN ROOM WINDOWS, LOGS (DOORS 118, 119, 121, 122, 123, 124, 125, 126, 127) (REFER TO A-4.1)
5. ALL MECHANICAL DUCT WORK AND CONTROLS WIRING INSTALLED WITHIN SPACE TO MAINTAIN MIN. 18" CLEARANCE
6. ALL ELECTRICAL OUTLETS & SWITCHES SHALL BE TO BE ROUGHED-IN, WIRED, COVER PLATES INSTALLED
7. ALL LIGHT FIXTURES TO BE BLANDED & WIRED AT DESIGNATED LOCATION
8. PROVIDE & INSTALL ALL PLUMBING FIXTURES AND ASSOCIATED PIPING
9. INSTALL FIRE SPRINKLER SYSTEM AND HEADS ADJUSTED TO 8' RAY-IN CEILING HEIGHT.
10. ELECTRICAL TO INSTALL & WIRE ALL LOW VOLTAGE WIRING FOR CONTROLS AND SENSORS, WORKED TO BE COORDINATED WITH CLEAN ROOM INSTALLER & IT INSTALLER

THE FOLLOWING TO BE PERFORMED BY SPECIALTY CLEAN ROOM CONTRACTOR TO ACHIEVE USP 795, 797, & 800 REGULATIONS

- A. PROVIDE & INSTALL CLEAN ROOM CEILING GRID & CEILING PANELS, INCLUDING CAULKING PANELS IN PLACE, PER REGULATORY REQUIREMENTS (REFER TO DWG. A-2.1 AND SEPARATE BOUND SPECIFICATIONS)
- C. PROVIDE & INSTALL ALL FAN FILTER UNITS AND INSTALL GRILLS COORDINATE ACTIVATION AND ADJUSTMENT OF SENSORS, & CONTROLS.
- E. CONNECT B5C HOOD(S) TO EXHAUST DUCTS (ROOMS 108)
- F. COORDINATE ALL CLEAN ROOM AIR BALANCING TO REGULATORY REQUIREMENT WITH MAIN HVAC INSTALLING CONTRACTOR & THIRD PARTY AIR BALANCING COMPANY FOR ROOMS 103, 105, 106, 107, 108, 110, 111, 112
- G. PROVIDE & INSTALL WALL PAINT FINISHES, REFER TO FINISH PLAN FOR LOCATION AND SEPARATE SPEC. SHEET FOR PRODUCT TYPE IN ROOMS 103, 105, 106, 107, 108, 110, 111, 112
- H. PROVIDE & INSTALL ALL FINISH FLOORING & WALL BASE (SEE FINISH PLAN & SPEC) TO REGULATORY REQUIREMENTS AND IN A MANNER EASY TO CLEAN AND MAINTAIN FOR ROOMS 101, 102, 103, 104, 105, 106, 107, 110, 111, 112.
- I. COORDINATE FINAL REGULATORY INSPECTIONS & CERTIFICATION WITH INDEPENDANT 3RD PARTY INSPECTOR / TESTING SERVICE

Order Plans @

WWW.DLINE.COM

PHARMACY ENLARGED PLAN W/
HOODS
A-1.1A
3/8" = 1'-0"

CROSSFIELDS
CHIROPRACTIC OFFICE DESIGN

3206 Strapping Palmetto Trail
Mableton, GA 30126
Phone: 770.434.8000
Fax: 770.434.8000
Web: www.ChiropracticOfficeDesign.com



THIS DRAWING IS THE PROPERTY OF CROSSFIELDS, INC. AND ANY REPRODUCTION OR COPYING OF THIS DRAWING, IN WHOLE OR PART IS PROHIBITED WITHOUT WRITTEN PERMISSION.

**INNOVATION
COMPOUNDING
DR. SHAWN HODGES**
6095 PINE MOUNTAIN RD., SUITE 104
KENNESAW, GA 30152

REVISIONS:

NO.	DATE	DESCRIPTION
1	01/09/19	CLEAN RM. SCOPE REVISION

DRAWN BY: CMB
CHECKED BY: CMB/SBE
DATE: 09.24.19
PROJECT NUMBER: 17125-IC
SHEET NO:

A-1.1A

FOR PERMIT