



- KEY NOTES - WALL FINISH PLANS:**
- SEE MILLWORK DRAWING FOR DETAILS AND WALL FINISHES AT FRONT DESK AND RETAIL.
  - WETWALLS TO BE CLAD AS SPECIFIED FLOOR TO CEILING.
  - WALLS OF SHOWER TO BE CLAD WITH TILE AS SPECIFIED FLOOR TO CEILING.
  - REPAINT EXISTING METAL EXTERIOR DOOR AND TRIM TO MATCH EXISTING STOREFRONT AS NEEDED.

- SHEET NOTES - WALL FINISH PLANS:**
- ALL WALLS NOT MARKED TO BE PT-1
  - ALL DOORS & DOOR FRAMES TO BE PT-T
  - PREP ALL WALLS AS REQUIRED TO RECEIVE NEW FINISH
  - ALL NEWLY PAINTED SURFACES TO BE PRIMED FIRST. PAINT ALL NEW WALLS (3 COATS): 1 PRIMER COAT, 1 BASE COAT, AND 1 TOP COLOR COAT. DRYWALL SUBCONTRACTOR SHALL DELIVER WORK SURFACE IN A BLEMISH-FREE MANNER PRIOR TO PRIMER COAT. ANY BLEMISHES IDENTIFIED AFTER 1ST PRIMER COAT SHALL BE RECTIFIED IMMEDIATELY BY DRYWALL SUBCONTRACTOR. WHEN CHANGE OF COLOR TRANSITION IS IN QUESTION, CONSULT DESIGNER FOR SOLUTION AND APPROVAL PRIOR TO PAINTING. CHANGE TO CAMOUFLAGE EXISTING IMPERFECT WALL EDGE.
  - INTERIOR WALLS AND CEILING COORDINATOR CAB BY ELEVATOR MANUFACTURER

SEE SPECIFICATIONS, SECTIONS AND INSTRUCTIONS ON A SEPARATE DOCUMENT

**FINISH LEGEND**

- WALL FINISH
- SCHEDULE FLOORING OR TRANSITION
- SCHEDULE BASE

DRAWINGS ARE REPRESENTATIVE OF DESIGN INTENT. THEY MAY NOT REPRESENT FULL EXECUTION REQUIREMENTS DUE TO UNFORESEEN AND/OR UNKNOWN AS-BUILT CONDITIONS.

1 WALL FINISH PLAN - 2ND FLR.  
ID-4.2  
1/4" = 1'-0"  
PLAN NORTH

**CROSSFIELDS**  
CHIROPRACTIC OFFICE DESIGN

2265 Shavano Parkway Suite 3015  
Kennesaw, GA 30144  
Phone: 770.424.9200  
Web: www.ChiropracticOfficeDesign.com

THIS DRAWING IS THE PROPERTY OF CROSSFIELDS, INC. AND ANY REPRODUCTION OR COPYING OF THIS DRAWING, IN WHOLE OR PART IS PROHIBITED WITHOUT WRITTEN PERMISSION.

**INNOVATION  
COMPOUNDING  
DR. SHAWN HODGES**  
6095 PINE MOUNTAIN RD. SUITE 104  
KENNESAW, GA 30152

REVISIONS:

NO.	DATE	DESCRIPTION

DRAWN BY: CMB/LEB  
CHECKED BY: CMB  
DATE: 09.24.19  
PROJECT NUMBER: 17125-IC  
SHEET NO:

ID-4.2

FOR PERMIT