VULCAN LANDS INC
PARCEL ID: 119-6043-001

NOTE: FORCE MAIN PIPE SHALL BE HDPE UNLESS OTHERWISE CALLED OUT IN THE PROFILE.

MULCHING, GRASSING AND PLANTING Ds1 Ds2 Ds3

SILT FENCE NON-SENSITIVE Sdl-NS

STA. 32+83
END REMOVE AND DISPOSE
738 L.F. OF ASPHALT PAVT.
BY SAW CUT METHOD

PROP. 8" DR 11 HDPE C906
SEWER FORCE MAIN. 3.5' MIN.
COVER REQUIRED

PROP. 60'
TEMP. CONST.
EASEMENT

PROP. 30'
PERM. UTILITY
EASEMENT

15'

STA. 37+06
1 - AIR AND VACUUM RELEASE
VALVE ASSEMBLY. CONTRACTOR
TO LOCATE AT HIGH POINT IN
FORCE MAIN

MATCH LINE STA. 27+50
SEE SHT. NO C.09

MATCH LINE STA. 42+00
SEE SHT. NO C.11

SLOPE STABILIZATION (HECP) 1,477 S.Y. Ss

FORD GROSSING Ford

I-85 SOUTH

MPM 52

GRAPHIC SCALE
50 0 25 50 100 200
(IN FEET)
1 inch = 50 ft.

LEVEL II CERTIFICATION #21533 TIM G. BLAYDES EXPIRES 10/28/2020

ABANDONED ACCESS ROAD

EXIST. GRADE

PROP. 8" FORCE MAIN
3.5' MIN. COVER REQ'D.

AIR AND VACUUM
RELEASE VALVE. CONTRACTOR
TO LOCATE AT HIGH POINT IN LINE

PROFILE
SCALE: 1" = 50' HORIZ.
1" = 10' VERT.

948.38 952.85 954.39 957.77 964.01 966.87 967.56 969.66 972.20 972.73 971.27 963.56 948.11 938.45 933.76

28+00 29+00 30+00 31+00 32+00 33+00 34+00 35+00 36+00 37+00 38+00 39+00 40+00 41+00 42+00

Order Plans @ WWW.LDILine.com

DRAWING FILE: G:\Projects\Coweta\CATL190025 - Northgate High School Sanitary Sewer\0 DWG\CATL-190025-BASE.dwg
PLOTTED: Oct 18, 2019 - 7:29am

GMC
6120 Powers Ferry Road NW, Suite 350
Atlanta, GA 30339
T 770.952.2481
GMCNETWORK.COM

ISSUE	DATE
PRELIMINARY	08.15.2019
75% SUBMITTAL	10.01.2019
BID READY	10.18.2019

DRAWN BY: DS
CHECKED BY: CB

NORTHGATE HIGH SCHOOL
SANITARY SEWER
COWETA COUNTY WATER AND SEWERAGE AUTHORITY

CATL190025

GEORGIA REGISTERED No. 24141 PROFESSIONAL 10-18-19 ENGINEER TIMOTHY G. BLAYDES

FORCE MAIN
PLAN & PROFILE

C.10
sheet of