

1 **FIRST LEVEL - REFERENCE PLAN - AREA 1-1**
SCALE: 1/8" = 1'-0"



2 **FIRST LEVEL - REFERENCE PLAN - AREA 1-2**
SCALE: 1/8" = 1'-0"

GENERAL NOTES

A SEE SPECIFICATIONS FOR METAL PAN STAIR. METAL PAN STAIR IS A DELIGATED DESIGN SUBMITTAL. METAL PAN STAIR PROVIDER IS TO PROVIDE SHOP DRAWINGS DETAILING STEEL, MEMBER SIZES, SUPPORT REQUIREMENTS, DETAILS, AND OTHER CONDITIONS RELATED TO THE DESIGN OF THE STAIR. SEE SPECIFICATIONS.

B PLAM-3 BASIS-OF-DESIGN IS FORMICA HARDSTOP. SEE SPECIFICATIONS. PLAM-3 IS INSTALLED OF GYPSUM WALLBOARD. ALL JOINTS, END CONDITIONS (END OF WALL, TOP OF PANEL, BOTTOM OF PANEL), AND CORNERS UTILIZE MANUFACTURER'S STANDARD TRIM PIECES. PROVIDE BRUSHED ALUMINUM FINISH.

C GLASS GUARDRAIL SYSTEM BASIS-OF-DESIGN IS C.R. LAURENCE TAPER-LOC DRY GLAZED RAILING SYSTEM W/ CONTINUOUS BASE RAIL, ANCHORED TO STEEL PLATE, WELDED TO STEEL TUBE STRINGER. FOR HANDRAIL TO BE CONTINUOUS, GLASS PLANE MUST ALIGN WITH THE PLANE OF THE PLAM-3 WALL, IN PLAN. THIS ALIGNMENT REQUIRES A CONTINUOUS STEEL PLATE WELDED TO THE STRINGER TO BRING THE RAILING SYSTEM INTO ALIGNMENT.

D STAIR HANDRAIL IS A BRUSHED STAINLESS STEEL CUSTOM HANDRAIL, CONTINUOUS FROM THE PLAM-3 WALL TO THE GLASS RAILING SYSTEM. WHERE DISTANCE FROM WALL VARIES, PROVIDE EXPOSED BLOCKING FOR MOUNTING. EXPOSED BLOCKING SHALL BE 3-INCH DIA. PAINT GRADE POPLAR, PAINTED TO MATCH WALL, W/ CONCEALED FASTENERS.

E PROVIDE VINYL TREADS AND RISERS, TYPICAL. PROVIDE MATCHING VINYL MOLDING.

FLOOR PLAN LEGEND

- NEW DOOR
- EXISTING DOOR
- EXISTING WALL
- OUTLINE OF OBJECT ABOVE
- FEC — FIRE EXTINGUISHER CABINET
- FE — BRACKET MOUNTED FIRE EXTINGUISHER
- 1HR FIRE BARRIER / FIRE PARTITION
- EXISTING RATED CONSTRUCTION
- 3 HR FIRE WALL
- EXISTING RATED CONSTRUCTION

FLOOR PLAN KEYNOTE LEGEND

Key Value	Keynote Text
A2	SALVAGED WHITE BOARD / TACKBOARD MOUNTED TO NEW WALL. CONFIRM MOUTNING HEIGHT W/ ARCHITECT PRIOR TO INSTALLATION.
A3	REINSTALL EXISTING SNACK MACHINE.
A4	PROVIDE NEW VET FLOOR IN HATCHED AREA, SEE FINISH SCHEDULE.
A5	PROVIDE TRANSITION STRIP BETWEEN EXISTING CARPET AND NEW VET FLOOR.
A7	PROVIDE NEW PAINT AND BASE ON NEW WALL, SEE FINISH SCHEDULE. TYPICAL.
A8	CAULK EXISTING CABINETS TO NEW WALL.
A10	PATCH AND REPAIR BLOCK WALL WHERE EXISTING CONSTRUCTION WAS REMOVED, TYPICAL.
A11	REPLACE CORNER CMU AS REQUIRED TO INTEGRATE NEW WALL. REMOVE AND REPLACE WALL ROUNDED CMU.
A12	SALVAGED DOOR AND NEW FRAME.
A13	NEW DOOR AND FRAME, TYPICAL.
A15	EXISTING MILLWORK TO REMAIN, PROTECT DURING CONSTRUCTION.
A16	WHERE ROOM WAS ENLARGED (DEFINED BY MATCHED AREA), PROVDE NEW PAINT AND BASE TO MATCH EXISTING, TYPICAL.
A17	REINSTALL SALVAGED LIQUID SOAP DISPENSER.
A18	REINSTALL EXISTING REFRIGERATOR.
A19	PROVIDE CMU INFILL TO MATCH EXISTING CONSTRUCTION WHERE EXISTING WINDOW WAS REMOVED.
A20	INFILL EXISTING WALL WHERE EXISTING DOORS WERE REMOVED. MATCH EXISTING CONSTRUCTION.
A21	INFILL EXISTING WALL WHERE EXISTING LOUVERS (3) WERE REMOVED. MATCH EXISTING CONSTRUCTION.
A22	REINSTALL EXISTING SHELVING IN CONFIGURATIONS SHOW. GENERAL CONTRACTOR IS RESPONSIBLE FOR REPAIRING / MODIFYING EXISTING SHELVING AS REQUIRED. INFILL PANELS AND REVISED / REPLACEMENT END PANELS WILL BE REQUIRED TO SUPPORT NEW CONFIGURATION. ANY PANELS DAMAGED DURING SALVAGE / STORAGE MUST BE REPAIRED / REPLACED.
A23	GENERAL CONTRACTOR TO PROVIDE (1) NEW CUSTOM BOOKSHELD TO MATCH EXISTING BOOKSHELVES; 42" HIGH, DOUBLE SIDED, 3 SHELVES.
A24	PROVIDE SQUARE CORNER CMU AT THIS LOCATION.
A25	PROVIDE SQUARE CORNER CMU AT ALL CORNERS ON THIS WALL.
A26	REMOVE EXISTING ROUDNED CORNER CMU AND REPLACE WITH SQUARE CORNER.
A27	NEW CUSTOM CIRCULATION DESK - SEE MILLWORK DRAWINGS.
A32	(5) SHELF HIGH WOOD SHELVING, 18" DEEP. SEE SPECIFICATIONS.

EQUIPMENT KEY NOTE LEGEND

Key Value	Keynote Text
E1	OWNER PROVIDED, OWNER INSTALLED RELOCATED SMARTBOARD
E2	4X4 MARKBOARD - SEE SPECIFICATIONS
E3	4X4 TACKBOARD - SEE SPECIFICATIONS

KEY PLAN



Order Plans @ WWW.EDILine.com

GMC
1219 Wayne Street
Columbia, SC 29201
T: 803.786.1235
GMCNETWORK.COM

STATE OF SOUTH CAROLINA — GOODWYN, MILLS & CAWOOD, INC. — GREENVILLE, SC — REGISTERED ARCHITECT

STATE OF SOUTH CAROLINA — MARC W. WARREN — COLUMBIA, SC — REGISTERED ARCHITECT

10.24.19

ISSUE	DATE
BID DOCUMENTS	10.24.19

DRAWN BY: MJW
CHECKED BY: MWW

MILLBROOK ELEMENTARY SCHOOL - ADDITION AND RENOVATIONS
255 E PINE LOG RD, AIKEN, SC 29803

GMC # ACOL180004

FIRST LEVEL - REFERENCE PLAN - AREA 1

A1.11

10/29/2019 4:42:43 AM