


1 FOUNDATION PLAN

1/8" = 1'-0"

- PLAN NOTES:
- SEE CIVIL FOR FINISH FLOOR ELEVATION.
 - TOP OF EXTERIOR FOOTINGS = -2'-0" BELOW FINISH FLOOR AND TOPS OF INTERIOR FOOTINGS = -1'-4" BELOW FINISH FLOOR UNLESS INDICATED OTHERWISE ON THE PLAN.
 - FLOOR CONSTRUCTION IS 4" SLAB ON GRADE REINFORCED WITH WWF 6X6 - W1.4 X W1.4 OVER VAPOR BARRIER AND 4" GRANULAR BASE.
 - SEE DWG. S201 FOR SAW JOINT (S.J.) AND STEP FOOTING DETAILS AND FOOTING SCHEDULE.
 - WHERE SHARED AREAS ARE INDICATED "NOTE 5" - GROUT 24" WIDTH OF CMU WALL SOLID AND PROVIDE #5 BARS @ 8" OC (3 BARS AT EACH LOCATION), FROM FOOTING UP TO BOTTOM OF BEARING PLATE OF BEAMS ABOVE. SEE S1.02 FOR BEAMS.
 - DO NOT CONNECT PERPENDICULAR WALLS TO FIRE WALL. PROVIDE JOINT BETWEEN PERPENDICULAR WALLS AND FIRE WALLS AS SHOWN ON THE ARCHITECTURAL DRAWINGS.
 - PROVIDE THICKENED SLAB AREAS 24" X 24" X 12" THICK WHEREVER STAR STRINGERS OR SUPPORT POSTS FOR STAR SIT ON FLOOR SLAB. COORDINATE THICKENED SLAB LOCATIONS WITH STAR SHOP DRAWINGS.

GMC

1219 Wayne Street
Columbia, SC 29201
T 803.766.1235
GMCNETWORK.COM



ISSUE	DATE
BID DOCUMENTS	10.24.19
DRAWN BY: TGD	
CHECKED BY: RMB	

MILLBROOK ELEMENTARY
SCHOOL - ADDITIONS AND
RENOVATIONS
255 E PINE LOG RD, AIKEN, SC 29803
GMC # ACOL 180004

FOUNDATION PLAN

S1.01

