

6. Gaskets shall be of neoprene and shall have plain lips unless otherwise specified.

7. Cast iron pipe fittings for PVC pipe shall be mechanical joint or single gasket, push-on type with a maximum pressure rating of 100 psi and shall conform to the requirements of ANSI Standard A21.4. Extender of fitting shall have a burr-free coating.

8. Polyvinyl Chloride Pipe and Fittings
1. Polyvinyl chloride (PVC) pipe four inches (4") and larger in diameter shall conform to the requirements of AWWA C-900.

2. Fittings:
PVC fittings four inches (4") and larger shall be furnished by the manufacturer of the pipe with which they are used or approved equal by the City.

PVC fittings smaller than four inches (4") shall be Scheduled 80 PVC.

3. Joints
PVC pipe four inches (4") and larger shall have provision for expansion and contraction provided in the joints. All joints, except solvent weld and threaded joints, shall be designed for push-on make up connection. A push-on joint may be a coupling manufactured as an integral part of the pipe barrel consisting of a bevelled section with an expanded bell with a groove to retain a rubber sealing ring of uniform cross section similar and equal to Johns-Manville Ring-Tite and Davis Meter Dow-Tite, or may be made with a separate ten gasketed coupling similar and equal to Centristeel Fluid Tite.

Joints in PVC smaller than four inches (4") shall be solvent welded in accordance with the recommendations of the pipe manufacturer using the solvent welding compound furnished with the pipe, or shall be threaded. Threaded joints shall be used only with Schedule 80 pipe or better.

C. Gate Valves

1. Gate valves three inches (3") in diameter and larger shall be iron body, non-rising stem, bronze mounted gate valves, mechanical joint and/or single gasket push-on type, conforming to requirements of the AWWA Standard C500 and shall be provided with a two-inch (2") square operating nut. Valves shall be of the single-wedge gate and shall turn to the left (counterclockwise) to open. The seat and gate shall have smooth, perfectly machined surfaces and shall be watertight when in contact. All valves shall be provided with o-ring seals. The design and machining of valves shall be such as to permit replacing the o-ring seals while in service without undue leakage.

2. Gate valves 16 inches in diameter and larger, installed horizontally, shall be provided with bevel gearing, a gear case that can be packed from the

outside, rollers, tracks, and scrapers constructed so that the weight of the gate is carried on the rollers throughout the entire length of travel. The design shall conform to the requirements of AWWA Standard C500.

3. Gate valves for pipe less than three inches (3") in diameter shall conform to the requirements of Federal Specifications WW-V-54 for Class A, Type I, and shall be bronze, single wedge, non-rising stem, screwed bonnet, 125-pound S.P., 300-pound W.C.G., with stuffing box replaceable under pressure and all parts renewable. Ends shall be as shown on the Drawings.

Body ends shall be:
1. Flanged with dimensions, facing and drilling in full conformance with ANSI B 16.1, Class 125.
2. Mechanical joint to meet the requirements of AWWA C111/ANSI A21.11.

The valve plug shall be constructed of cast iron ASTM A 128, Class B. The plugs shall have a conical seating surface, which is eccentrically offset from the center of the plug shafts. The plug shafts shall be integral. The entire plug face shall be totally encapsulated with Buna N (Nitrile) rubber in all valve sizes. The rubber compound shall be approximately 60 (Shore A) durometer hardness. The rubber to metal bond must withstand 75 lbs. pull under test procedure ASTM D-429-73 Method B. Plug geometry and valve rotational characteristics must allow drop tight shutoff in both standard and "reverse-flow" direction with minimal "break-aways" torque.

When plug is in full open position, plug geometry and body waterway contours must provide the following:

- a) A "round" passageway that allows flow capacity equal to 100% of the adjacent pipe area.
- b) Allowance of maximum passage of "solids".
- c) No cavities where debris can collect.
- d) Minimal head loss (no turbulence).

Valve steel mating surface shall be constructed of solid, one-piece 304 stainless steel ring or cast iron with welded nickel seating surface. The ring shall be threaded in place in the valve body to allow easy seat adjustment and/or replacement in the field. Seat ring contour must be precision machined to effect drop-tight shutoff in either direction with minimum rubber interference and "break-aways" torque. Seat mating surfaces coated with non-metallic materials shall not be acceptable.

Shaft bearings shall be sleeve type, fitted in both the upper and lower trunnions. Bearings shall be corrosion resistant, have a low coefficient of friction and possess inert properties so that the possibility of galvanic corrosion as well as galling between shaft and bearing material is eliminated.

A heavy-duty, two-way thrust collar shall be provided to ensure proper plug centering to accommodate drop-tight shutoff with minimum "break-aways" torque as previously specified. The thrust collar shall be accurately set at the factory and then "locked" in place to prevent tampering in the field.

A mechanical "brake" shall be supplied on 3"-6" valves, ordered without auxiliary actuators. The valve "brake" shall be capable of "locking" the valve in any intermediate position between full-open and full-closed.

No. 973-12.3, Code 1-2, as specified in the FDOT Standard Specifications or other approved material. Backfill shall not be placed for 30 minutes following paint application. In lieu of the painted stripe on PVC pipe the PVC pipe shall be furnished with a bronze primer, "Force Main" legend and 6" by 6" by Davis Industries, Inc. 14 gauge copper wire shall be placed along and attached to the entire length of the force main to serve as locate wire.

G. Backfilling
1. After pipe has been laid, inspected, and found satisfactory, sufficient backfill shall be placed along the pipe barrel to hold the pipe adequately in place during the conduct of the preliminary hydrostatic test. No backfill shall be placed over joints until the preliminary test is satisfactorily completed, leakage is exposed to view for the detection of any leaks.

2. Upon satisfactory completion of the preliminary hydrostatic test, the filling of the trench shall be completed.

H. Concrete Protection: All concrete encasement, manholes, manas, ditches or other cuts are crossed by the force main shall be installed across and to 10 feet each side of the bottom. All crossing signs shall be placed vertically above the center line of the pipe, at each crossing, in the casual, waterway, etc.

A. Flushing: All force mains shall be flushed to remove all sand and other foreign matter. The velocity of the flushing water shall be at least 4 feet per second. Flushing shall be terminated at the discretion of the Engineer. The contractor shall dispose of the flushing water without causing nuisance or property damage. B.

B. Cleaning: Prior to pressure and leakage testing, the interior of each main shall be cleaned of accumulation of sand and other foreign matter by pressure or hand methods. Hand cleaning methods may consist of shoveling the materials and pressure cleaning with a water hose. Care shall be exercised in cleaning to prevent damage to the pipe lining.

C. Hydrostatic Tests
1. All components of the force main system, including fittings, connections and valves shall remain uncovered until tested and accepted; provided, however, that pipe trenches under traveled streets or roads or in unstable soil conditions may be backfilled with the permission of the City. No testing shall be done until all concrete throat blocking is in place. In testing, the part of the system under test shall be filled with water and subjected to a sustained pressure of 100 pounds per square inch. The piping shall be tested in sections, thereby testing each valve for secure closure. While the system is being filled, air shall be carefully and completely exhausted. If permanent air vents are not located at all high points, the contractor shall install copper air stops or fittings and valves at such points so the air can be expelled as the pipe system is slowly filled with water.

2. Test pressure shall be maintained by pumping for at least 3 hours and until all sections under test have been checked for evidence of leakage. Rate of loss shall not exceed that specified hereafter. Visible leaks shall be corrected regardless of total leakage shown by test.

Manual gear, electric motor and cylinder valve actuators shall be supplied as specified. Each type shall be designed to open or close their respective valve without the application of excessive force. Manual gear and electric motor actuators shall hold the valve in any intermediate position between full-open and full-closed. Manual gear actuators shall be of the worm gear type and shall be totally enclosed and sealed. Trochoid actuators shall be furnished with hand-wheel or chain-wheel and position indicators.

Plug valves shall have Buna-N or neoprene rubber faced plugs and shall be of eccentric construction. Valves shall be made of cast iron, or semi-steel at least equal to ASTM A126, Class B. Body seats of valves three inches (3") and larger shall have a welded overlay of not less than 90 percent pure nickel or fusion bonded A1-Clad Nylon II on all surfaces contacting the plug face. Stem bearings shall be of corrosion resistant material. All exposed bolts, nuts, cotter pins, washers, etc., shall be stainless steel. Port areas for valves 24 inches through 60 inches shall be 70 percent of full pipe area. Valves four inches (4") and larger shall have adjustable packing glands or permanent non-adjusting packing and shall be capable of being packed without the bonnet or plug being removed from the valve. Valves shall be designed for not less than 150 psi cold water, oil, or gas working pressure. Valves shall have drop tight shutoff at a bi-directional test pressure of 100 psi with pressure in either direction. Valves shall be permanently lubricated and shall be provided with an angle underground actuator, two inches (2") square operating nut and extended nut for wrench operation. The extended nut shall be within six inches (6") of the top of the valve box, shall have a port position indicator and shall indicate direction to open the valve. Operations shall be sized for a minimum of 90 psi differential pressure. All valves shall be as manufactured by DeL'Oric, Dresser, Homestead or approved equal.

E. Check Valves

1. Swing check valves four inches (4") and larger shall have a cast iron or cast steel body with a bronze or stainless steel seat ring, a non-corrosive shaft for attachment of weight and lever and a 300 psi hydrostatic test pressure rating. Check valves shall absolutely prevent the return of water back through the valve when the inlet pressure decreases below the delivery pressure. The valve must be full opening, tight seating and its seat ring shall be renewable and must be securely held in place by a threaded joint; the valve disc shall be of cast iron or cast steel and shall be suspended from a non-corrosive shaft which will pass through a stuffing box. A tapered boss with plug shall be provided on the check valve bonnet for future use with a pressure gauge.

2. Check valves smaller than four inches (4") shall be bronze, bronze disc, swing check valves conforming to Federal Specification WW-V-51E, Type 4 Class A-125 pound. Ends shall be as shown or indicated on Drawings.

F. Tapping sleeves and tapping valves used to make "tee" taps into existing mains shall be provided and installed at locations as shown on the Drawings. Tapping sleeves shall be soft cast iron units and rated for 100 psi working pressure. Steel units will not be acceptable. The contractor shall determine the diameter of the existing main before ordering the sleeve. Valves shall be of the non-rising stem type with o-ring seals and shall conform to the applicable requirements as specified above for the valves.

G. Cast iron valve boxes shall be provided for all valves installed underground which do not have extended operators such as those required by the plug valves. The valve boxes shall be adjustable to the integrated depth of earth cover over the valve and shall be designed to prevent the transmission of surface loads directly to the valve or stem. Valve boxes shall be three-piece type and have an interior diameter of not less than five inches (5"). All valve boxes shall be provided with covers which will fit the diameter of the existing main before ordering the sleeve. Valves shall be of the non-rising stem type with o-ring seals and shall conform to the applicable requirements as specified above for the valves.

H. Air Release Valves and Control Valves

3. The system as a whole, or any part, shall be released after completion of backfilling. Such release will be required for final acceptance.

4. All pumps, gauges and measuring devices shall be furnished, installed and operated by the contractor and all such equipment and devices and their installation shall be approved by the City. All pressure and leakage testing shall be done in the presence of a representative of the City Utilities.

5. Water for testing and flushing shall be potable water provided by the Contractor from a source approved by the City.

6. When the section of force main is ready for testing, the line shall be filled with water, pumped to a pressure of 100 psi and maintained at the pressure for a period of three hours. No leakage allowed.

1. Automatic air release valves shall be Empire Diaphragm Type II, Fig. #642 or approved equal manufactured for sewage service. The valves shall be so designed that they will not suck shut or leak water under continued long operating conditions and to insure opening under high internal pressure. The design shall incorporate a siphon setting chamber or trap and a flushing system by which the trap and the entire valve can be back flushed and cleaned.

2. All air release valves shall be installed in a pre-cast vault 3,000 gal. capacity, with four-inch (4") walls. Vaults shall have a 30" x 36" opening with a lockable, aluminum hatch with stainless steel hardware. The air release valves shall be to the right or left of the main. The vault is situated four to six inches (4" - 6") from the main.

PREPARATION

A. Pipe

1. Gradient: Lines shall be laid to a depth of cover shall be maintained uniform in respect to friction. If either grading is completed or proposed, the pipe installation shall be in a grade or slope as shown on the Drawings. Safety boards with string line paralleling design grade, or other suitably approved method, shall be used by the contractor to assure conformance to design grade.

Pipe Installation: Maximum 20%

3. Defects: Any pipe found defective shall be immediately removed and replaced with sound pipe at the contractor's expense.

4. Anchors: Concrete thrust blocks shall be placed at all bends, tees, plugs and other fittings to provide lateral support, except where restrained joints are specified. Thrust blocks shall conform to the details shown on the Drawings and not poured in place. (See Restrainted Joints).

5. PVC: Polyvinyl chloride pipe may be damaged by prolonged exposure to direct sunlight and the contractor shall take necessary precautions during storage and installation to avoid this damage. Pipe shall be stored under cover and sufficient backfill to shield it from the sun shall be placed as the pipe is installed.

B. Ductile Iron Pipe Joints

1. Type: The joints of all pipelines shall be made absolutely tight. The particular joint used shall be approved by the Owner prior to installation. Where shown on the Drawings or notes, in the opinion of the Owner, settlement or vibration is likely to occur, all pipe joints shall be bolted.

2. Mechanical Joints: All types of mechanical joint pipes shall be laid and joined in full conformance with manufacturer's recommendations, which shall be submitted to the Engineer for review and approval before work is begun. Only especially skilled workmen shall be permitted to make up mechanical joints. Torque wrenches set as specified in AWWA Standard C111 shall be used, to spanner type wrenches not longer than specified therein may be used without the permission of the Engineer.

Order Plans @ WWW.ADDIline.com

FIELD QUALITY CONTROL

A. Flushing: All force mains shall be flushed to remove all sand and other foreign matter. The velocity of the flushing water shall be at least 4 feet per second. Flushing shall be terminated at the discretion of the Engineer. The contractor shall dispose of the flushing water without causing nuisance or property damage. B.

B. Cleaning: Prior to pressure and leakage testing, the interior of each main shall be cleaned of accumulation of sand and other foreign matter by pressure or hand methods. Hand cleaning methods may consist of shoveling the materials and pressure cleaning with a water hose. Care shall be exercised in cleaning to prevent damage to the pipe lining.


C. Hydrostatic Tests
1. All components of the force main system, including fittings, connections and valves shall remain uncovered until tested and accepted; provided, however, that pipe trenches under traveled streets or roads or in unstable soil conditions may be backfilled with the permission of the City. No testing shall be done until all concrete throat blocking is in place. In testing, the part of the system under test shall be filled with water and subjected to a sustained pressure of 100 pounds per square inch. The piping shall be tested in sections, thereby testing each valve for secure closure. While the system is being filled, air shall be carefully and completely exhausted. If permanent air vents are not located at all high points, the contractor shall install copper air stops or fittings and valves at such points so the air can be expelled as the pipe system is slowly filled with water.

2. Test pressure shall be maintained by pumping for at least 3 hours and until all sections under test have been checked for evidence of leakage. Rate of loss shall not exceed that specified hereafter. Visible leaks shall be corrected regardless of total leakage shown by test.

BERRY ENGINEERS LLC
355 KEITHST NW, SUITE 109
CLEVELAND, TN 37312
TEL: (623) 796-5880
CERTIFICATE OF AUTHORIZATION #0818

HUTTON ROCKLEDGE MF LLC
736 CHERRY STREET
CHATTANOOGA, TN 37402

ROCKLEDGE FLATS
190 BARTON BLVD
ROCKLEDGE, FL



REVISIONS table with 10 rows and 2 columns.

SHEET NAME: CITY DETAILS

DATE: 11/01/2019
DRAWN BY: JDS
CHECKED BY: BMB
PROJECT NO: 19018
SHEET NUMBER: C-13