


**FINISH LEGEND**

CERAMIC TILE	
CT-14	MANUFACTURER: SHAW CONTRACT PRODUCT: PALACE CT38 18"X18" COLOR: 500 ALPINE FINISH: MATTE
CORNER GUARD	
CG-1	MANUFACTURER: NPRO PRODUCT: SURFACE MOUNT'S STAINLESS STEEL CORNER GUARD SIZE: 3-1/2" WING, 9" TALL FINISH: STAINLESS STEEL
PAINT	
PT-5	MANUFACTURER: SHERWIN WILLIAMS PRODUCT: PROMAR 200 SERIES COLOR: T80 FINISH: EGGSHELL
PT-2	MANUFACTURER: SHERWIN WILLIAMS PRODUCT: PROMAR 200 SERIES COLOR: T80 FINISH: FLAT
PT-4	MANUFACTURER: SHERWIN WILLIAMS PRODUCT: PROMAR 200 SERIES COLOR: T80 FINISH: EGGSHELL
SEALED CONCRETE	
SC-1	MANUFACTURER: N/A PRODUCT: SEALED CONCRETE

**GENERAL FINISH PLAN NOTES**

- ALL PARTIES RESPONSIBLE FOR DELIVERING FINISHES TO THE SITE SHOULD CHECK QUANTITIES AND DELIVERY DATES AS SOON AS SO'S AWARDED. IT IS THE DIRECT RESPONSIBILITY OF THE CONTRACTOR TO SECURE FINISH ORDERS TO ELIMINATE THE NEED FOR RESELECTION OR ADDITIONAL SHIPPING EXPENSES.
- ITEMS REQUIRING FINISH SELECTION THAT DO NOT APPEAR ON THE FINISH DOCUMENTS SHALL BE SELECTED FROM SHOP DRAWINGS, SUBMITTALS AND/OR SAMPLES AS REQUIRED BY ARCHITECTURAL SPECIFICATIONS.
- CHANGES OF LEVELS BETWEEN FLOORING MATERIALS TO BE NO GREATER THAN 1/4" U.N.O.
- SAVE ALL CARPET, TILE, BASE AND WALLCOVERING USABLE SCRAPS. STORE IN A SPACE TO BE SELECTED BY OWNER. WRAP ITEMS FOR STORAGE IN A PROTECTIVE COVERING CLEARLY MARKING THE CONTENTS. COORDINATE WITH OWNER'S REPRESENTATIVE.
- PROVIDE THE OWNER WITH A MAINTENANCE MANUAL OF MANUFACTURER'S RECOMMENDED ROUTINE AND SPECIAL MAINTENANCE INSTRUCTIONS FOR EACH ITEM.
- ALL FINISH MATERIALS ARE TO BE SUPPLIED FROM (1) DYE LOT OR COLOR BATCH PER ITEM, INCLUDING BUT NOT LIMITED TO CARPET, TILE, PAINT AND WALL COVERING.
- INSTALL ALL MANUFACTURED ITEMS, FINISH MATERIALS AND EQUIPMENT IN STRICT ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDED INSTRUCTIONS.
- THE MINIMUM FLAME SPREAD CLASSIFICATION OF ALL INTERIOR FINISHES SHALL BE CLASS C INTERIOR FINISH (FLAME SPREAD 75-200, SMOKE DEVELOPED 250, 200, 200, 200, 200).
- PAIN ALL HOLLOW METAL DOORS, DOOR FRAMES AND WINDOW FRAMES WITH SEMI-GLOSS FINISH, U.N.O.
- FLOORING TRANSITIONS TO OCCUR AT THE CENTERLINE OF THE FLOOR, U.N.O.
- PROVIDE ALUMINUM SCOTCHER STRIPS AT ALL HARD SURFACE FLOORING TRANSITIONS.
- SEE REFLECTED CEILING PLAN FOR MATERIAL LOCATIONS AND HEIGHTS.
- WOOD DOORS TO BE A HIGH-GRADE RFT-CUT BRCH.
- PROVIDE A FINISH SCHEDULE TO ARCHITECT FOR ALL FLOORING MATERIALS.
- PAINT CEILINGS & SOFFITS PT-1, U.N.O. WHERE REVEAL OCCURS & PT-1 IS ABOVE, PAINT THE REVEAL PT-1.
- COORDINATE SURFACE OF WALLS TO RECEIVE DARK PAINT TO BE FINISHED TO A HIGH STANDARD SO AS NOT TO REFLECT IMPERFECTIONS IN WALL CONSTRUCTION OR FINISHING.
- PROVIDE 2" FAUX WOOD BLINDS ON ALL WINDOWS. SHADES TO BE SELECTED BY ARCHITECT AND SUBMITTED TO OWNER AND CONTRACTOR FOR APPROVAL.
- COORDINATE LEAD TIMES FOR ALL REQUIRED LAMINATE FINISHES WITH TOILET PARTITIONS AND MILLWORK INSTALLATIONS.
- ALL MATERIAL TO BE INSTALLED IN ACCORDANCE WITH MANUFACTURER'S WRITTEN INSTRUCTIONS.
- PAIN ALL EXPOSED COLUMNS ACCORDING TO ROOM DESIGNATED COLOR, U.N.O.
- STAINLESS STEEL CORNER GUARDS TO BE PROVIDED AT ALL CORRIDOR CORNERS. CONTRACTOR TO CONFIRM COUNT AND LOCATIONS WITH INTERIOR DESIGNER.

1925 Prospect Ave.  
Orlando, FL 32814  
P (407) 661-9100  
F (407) 661-9101  
www.r-p.com



**IDENTIFY**  
HUTTON DEVELOPMENT

**PROJECT NAME**  
ROCKLEDGE FLATS - BUILDING B  
220 Baron Boulevard  
Rockledge, FL 32955

**SHEET TITLE**  
FLOORS 2-4 FINISH PLAN

NOV 02, 2019

Revision Schedule	
No.	Description

PROJECT NO. 21002	DATE 20/11/19	DRAWN [Signature]	CHECKED [Signature]
----------------------	------------------	----------------------	------------------------

1 FLOOR 2 - FLOOR 4 FINISH PLAN  
3/02' x 11/0'

GMP PRICING SET 15 NOVEMBER 2019