

ALL TREES WITHIN PAVED AREAS TO BE PLANTED IN STRUCTURAL SOIL A MINIMUM OF 8' RADIUS FROM TRUNK OF TREE.

**FDOT GENERAL NOTES**

- "Governing Standards and Specifications: 2017 Florida Department of Transportation, Design Standards, and 2017 Standard Specifications for Road and Bridge Construction."
- Contractor shall repair any and all damage done to FDOT property during demolition, relocation &/or installation activities at his sole expense.
- Ownership of all suitable excavated materials, as determined by the Department, shall remain in the Department until a final acceptance of the permitted project is fulfilled. Excavated materials shall be hauled by the Permittee, at their cost & expense from the site to the Broward Operations Center or stockpiled in those areas as directed by the Department, including asphalt millings.

PLEASE REFER TO SHEET CF08.3 FOR PLANTING DETAILS AND GENERAL LANDSCAPE NOTES AND; TO SHEET CF08.1 FOR EXISTING TREE DISPOSITION PLAN.

ALL ACCESSORY STRUCTURES SUCH AS BUT NOT LIMITED TO IRRIGATION PUMPS, DUMPSTER ENCLOSURES, AND UTILITY BOXES SHALL BE SCREENED WITH SHRUBS ON ALL APPLICABLE SIDES. SHRUBS PLANTED FOR THIS PURPOSE SHALL BE IN ADDITION TO REGULAR CODE REQUIREMENTS

LANDSCAPING SHALL BE WATERED VIA UNDERGROUND IRRIGATION SYSTEM FROM FROM A PERMANENT WATER SOURCE. IRRIGATION SHALL PROVIDE 100% COVERAGE AND 50% OVERLAP.

**LANDSCAPE NOTES:**

- Contractor responsible for locating and protecting all underground utilities prior to digging.
- Contractor responsible for protecting existing trees from damage during construction as shown on plans.
- General Contractor to install 6" minimum depth of clean, stable topsoil at all planting beds and lawn areas prior to fine grading. See Topsoil specification Sheet CF08.4.
- All shrub beds (existing and new) to be mulched with a 4-inch minimum layer of hardwood mulch (brown) as defined in the landscape specifications on Sheet CF08.4.
- Existing grass in proposed planting areas to be killed and removed and area to be hand raked to remove all rocks and debris larger than 1 inch in diameter prior to planting shrubs or laying sod. Landscape contractor to provide fine grading. See grading specification Sheet CF08.4.
- Any existing grass disturbed during construction to be fully removed, re-graded and replaced. All tree marks and indications to be repaired. No exceptions.
- Soil to be tested to determine fertilizer and lime requirements and distributed prior to laying sod as directed by L.A. Provide results to L.A. and Cumberland Farms Project Manager.
- Sod to be delivered fresh (Cut less than 24 hours prior to arriving on site), laid immediately, rolled, and watered thoroughly immediately after planting. Edge of sod adjacent to mulch beds to be shovelled out. All sod to be delivered in largest rolls available. There shall be no gaps between sod joints.
- All changes to design or plant substitutions are to be authorized in writing by the Landscape Architect, City of Ft. Lauderdale Landscape Architect, and Cumberland Farms Construction Project Manager.
- Planting Mix to be provided as specified in the landscape specifications Sheet CF08.4.
- All landscaping shall be installed in conformance with ANSI Z60.1 the "American Standard for Nursery Stock" and the accepted standards of the American Association of Nurserymen.
- The Landscape Contractor shall guarantee all plants installed for one full year from date of acceptance. All plants shall be alive and at a vigorous rate of growth at the end of the guarantee period. The Landscape Contractor shall not be responsible for acts of God or vandalism.
- Any plant that is determined dead, in an unhealthy or unsightly condition, lost its shape due to dead branches or other symptoms of poor, non-vigorous growth, as determined by the Landscape Architect, shall be replaced by the Landscape Contractor at no cost to Cumberland Farms.
- General Contractor to mound all parking islands 6" - 10" with clean-screened topsoil.
- Prior to installation, the Landscape Contractor shall inspect the subgrade, general site conditions, verify elevations, utility locations, irrigation, approve topsoil provided by General Contractor and observe the site conditions under which the work is to be done. Notify General Contractor of any unsatisfactory conditions, and work shall not proceed until such conditions have been corrected and are acceptable to the Landscape Architect, Landscape Contractor and Cumberland Farms Construction Manager.
- Stake all evergreen and deciduous trees.
- Remove all stakes and guying from all trees after one year from planting.
- Water all plant material that is newly planted thoroughly twice in first 24 hours and apply mulch immediately.
- Site to be 100% irrigated in all planting beds and grass area by an automatic underground irrigation system. See Irrigation Plan Sheets CF08.5 thru CF08.8.
- All tree protection devices to be installed by General Contractor prior to the start of land disturbance, and maintained until final landscaping.
- All tree protection areas to be protected from sedimentation.
- All tree protection fencing to be inspected daily, and repaired or replaced as needed or as instructed by L.A.
- Landscape Contractor shall provide a 1 year maintenance period under separate contract following acceptance by the Landscape Architect and Cumberland Farms Construction Manager. Maintenance contract to be assigned through Cumberland Farms maintenance Department.

UNLESS OTHERWISE SPECIFICALLY NOTED ON THIS PLAN, ALL LANDSCAPE AREAS (EXCLUDING SOD AREAS) TO RECEIVE 2" THICK LAYER OF CRIMSON LAVA ROCK, 1" - 2.5" IN SIZE WITH DeWITT PRO-5 WEED PREVENTION BARRIER UNDERNEATH, LAID IN SINGLE LAYER - CUT TO FIT BED SHAPE AND CUT TO ALLOW PLANTINGS..

**THOMAS**  
ENGINEERS - PROJECT MANAGERS - LAND PLANNING - LANDSCAPE ARCHITECTS

1000 CORPORATE DR. SUITE 200 FORT LAUDERDALE, FL 33334  
PH: (954) 202-7000  
P: 854-202-7070  
F: 954-202-7070

REV.	DATE	COMMENT	BY
1	03/07/18	ISSUED 75% RESUBMITTAL	MDG
2	09/25/18	ISSUED 75% RESUBMITTAL	MDG
3	11/06/18	RESPONSE TO 75% COMMENTS	MAT
4	01/04/19	ADDRESS TRAFFIC ENG. CONDITIONS	MAT
6	10/09/19	REVISED SIGNS	MDG

**811** KNOW WHAT'S BELOW ALWAYS CALL 811 BEFORE YOU DIG  
www.callsunshine.com

100% PLANS SUBMITTAL

PROJECT No.: F150057  
DRAWN BY: JVF  
CHECKED BY: MAT  
DATE: 09/11/2019  
CAD I.D.: F150057-LANDSCAPE PLAN

**CUMBERLAND FARMS**  
SUNRISE BLVD. & NE 4TH AVENUE


FOR  
**CUMBERLAND FARMS**

**THOMAS**  
ENGINEERS GROUP

RADICE III  
1000 CORPORATE DRIVE, SUITE 250  
FORT LAUDERDALE, FL 33334  
PH: (954) 202-7000  
FX: (954) 202-7070  
www.ThomasEngineeringGroup.com

**MICHAEL D. GROSSWIRTH**  
REGISTERED LANDSCAPE ARCHITECT  
October 10, 2019  
FLORIDA LICENSE NO. 11871  
FLORIDA BUSINESS REGISTRATION NO. 27528

SHEET TITLE:  
**LANDSCAPE PLAN**  
SHEET NUMBER:  
**CFG08.0**



Printed on Thursday, October 10, 2019, 10:51 AM by Max Kozlov