



KEYED NOTES - P300

- ① 3" COLD WATER FROM B.B.W.
- ② WATER SERVICE ENTRANCE. SEE DETAIL 1/1000.
- ③ EXISTING WATER HEATERS TO REMAIN. SEE DETAIL 2/1000.
- ④ THERMOSTATIC MIXING VALVE IN LOCKER ROOM MOUNTED STEADILY 60" AFF.
- ⑤ 2-1/2" CW & 1/2" HW DOWN INTO PLUMBING CHASE AND TO JANITOR'S SINK. SEE DETAIL 3/1000.
- ⑥ 1/2" HW DOWN TO SINK.
- ⑦ 1-1/4" CW DOWN TO FIXTURE SEE DETAIL.
- ⑧ 1/2" WATER HAMMER ARRESTOR WITH W-1.
- ⑨ 1-1/4" CW DOWN TO FIXTURE.
- ⑩ EXISTING PUMP FOR WATER HEATING SYSTEM. MINIMUM ACCEPTANCE VOLUME SHALL BE 20 GALLONS.
- ⑪ 1-1/2" CW & 1/2" HW DOWN INTO PLUMBING CHASE. SEE DETAIL 3/1000.
- ⑫ WATER HAMMER ARRESTOR, W-1-S.
- ⑬ 3/4" CW DOWN TO WALL HYDRANT.
- ⑭ DROP PIPING DOWN TO JUST ABOVE THE LAY-IN CEILING. COORDINATE WITH MECHANICAL AND ELECTRICAL EQUIPMENT.
- ⑮ 1/2" CW DOWN TO FIXTURE.
- ⑯ 2-1/2" CW & 1/2" HW DOWN INTO PLUMBING CHASE. SEE DETAIL 3/1000.
- ⑰ 1/2" HW DOWN IN WALL TO SUPPLY WASHER BOX, F-12.
- ⑱ 3/4" CW DOWN TO HOSE BIBS 18" ABOVE FINISHED FLOOR.
- ⑲ 1/2" CW DOWN IN WALL TO SUPPLY VALVE BOX F-13 FOR REFRIGERATOR ICE MAKER.
- ⑳ 1/2" CW DOWN IN WALL TO SUPPLY VALVE BOX F-14 FOR COFFEE MAKER.
- ㉑ DOMESTIC HOT WATER CIRCULATING PUMP, RCP-1.
- ㉒ 1-1/2" CW & 1/2" HW DOWN INTO PLUMBING CHASE AND FOR TESTING LAB SINK SUPPLY. SEE DETAIL 3/1000.
- ㉓ 3/4" CIRCUIT SOLVER ASSEMBLY (CSAS) WITH STRAINER, CHECK VALVE AND BALL VALVES.

1 PLUMBING FLOOR PLAN - DOMESTIC WATER
 1/8" = 1'-0"

WWW.LDILINE.COM

Order Plans @

DATE	DESCRIPTION

CITY OF MONROE
 PUBLIC SAFETY & MUNICIPAL
 COURT COMPLEX RENOVATION
 140 BLAINE ST., MONROE, GA 30655



THIS DRAWING IS AN INSTRUMENT OF SERVICE AND SHALL REMAIN THE PROPERTY OF THE ARCHITECT. NO PART OF THIS DOCUMENT SHALL BE REPRODUCED OR TRANSMITTED IN ANY FORM, ELECTRONICALLY OR MECHANICALLY, FOR ANY PURPOSE, WITHOUT THE EXPRESS WRITTEN PERMISSION OF THE ARCHITECT.

**PLUMBING
 DOMESTIC
 WATER PIPING
 PLAN**

PROJECT # 19160MONRpo
 DATE: Issue Date
 DRAWN BY: JAA
 CHECKED BY: DC

P300

SCALE 1/8" = 1'-0"

PERMIT SET