

16010 - GENERAL PROVISIONS
A. WORK CONSISTS OF FURNISHING LABOR, MATERIALS, EQUIPMENT AND SERVICES REQUIRED FOR THE COMPLETE INSTALLATION OF ELECTRICAL WORK SHOWN IN THE CONTRACT DOCUMENTS AND SPECIFIED IN DIVISION 16.

OO. REFINISH ALL ELECTRICAL EQUIPMENT DAMAGED DURING SHIPPING AND/OR INSTALLATION TO ITS ORIGINAL CONDITION. REMOVE ALL RUST, PRIME, AND PAINT PER MANUFACTURER'S RECOMMENDATIONS FOR FINISH EQUAL TO ORIGINAL.

L. MOUNT OUTLETS BOXES IN EXPOSED MASONRY WALLS WITH THE BOTTOM OF THE BOX ON THE TOP OF THE MORTAR JOINT AND THE VERTICAL LINE OF THE BOX EITHER ON THE MORTAR JOINT OR ON THE CENTER LINE OF THE MASONRY UNIT. PLUMB AND ACCURATELY ALIGN ALL WALL OUTLETS IN ROWS, MOUNT CEILING BOXES SYMMETRICAL WITH WALLS, BEAMS AND/OR TILES.

4. GENERAL ELECTRIC AO SERIES
3. PRE-APPROVED EQUAL
A. 480 VOLT
1. SQUARED D TYPE NF
2. SIEMENS TYPE S2 SERIES

1. PROVIDE F032, F025 AND F017 TB LAMPS FOR ALL 4', 3' AND 2' FIXTURES RESPECTIVELY, UNLESS NOTED OTHERWISE.
2. APPROVED MANUFACTURERS: GE STARCOAT SPX, PHILIPS TL80, OSRAM SYLVANIA OCTRON 800XP

16025 - DEMOLITION
A. EXAMINE THE BUILDING TO DETERMINE ACTUAL CONDITIONS AND EXTENT OF WORK PRIOR TO BEGINNING THE PROJECT. REFER ANY UNCLEAR DETAILS OR CONFLICTS TO THE ARCHITECT/ENGINEER FOR CLARIFICATION PRIOR TO BIDDING THE DRAWINGS.

16400 - POWER DISTRIBUTION
A. RETAIL METERING CENTER
1. PROVIDE METER SECTIONS CONFORMING TO METER QUANTITIES AS INDICATED ON THE DRAWINGS.

16450 - LIGHTING
A. COMPLY WITH NEC AS APPLICABLE TO THE INSTALLATION AND CONSTRUCTION OF LIGHT FIXTURES.
1. ALL WIRING AS APPLICABLE TO THE INSTALLATION AND CONSTRUCTION OF LIGHT FIXTURES.

16500 - EMERGENCY LIGHTING
A. PROVIDE AUTOMATIC BATTERY POWERED LIGHTING UNITS AS INDICATED ON THE DRAWINGS.
B. PROVIDE EMERGENCY LIGHTING AS SHOWN ON THE PLANS TO ILLUMINATE THE EGRESS CORRIDORS AND OTHER REQUIRED AREAS.

NO DATE DESCRIPTION
DATE: 12-20-2019
DRAWN BY: DJJ
CHECKED BY: PJF
PROJECT NO: R19-3725-000