

ITEM	QUANTITY	MODEL NUMBER	EQUIPMENT RESOURCE	REMARKS
BACKED BENCH (SURFACE MOUNT)	15	PWRB3/G-6PC34 (CEDAR COLOR)	PILOT ROCK - OR EQUIVALENT P.O. BOX 946 CHEROKEE, IA PH: 800.782.5002	CONTRACTOR SHALL MARK LOCATIONS PRIOR TO INSTALLATION AND SHALL BE APPROVED BY OWNER'S REPRESENTATIVE
RECYCLED PLASTIC CEDAR BACKLESS BENCH (SEE STRUCTURAL)	4	PWB/G-6PW (CEDAR COLOR)	PILOT ROCK - OR EQUIVALENT P.O. BOX 946 CHEROKEE, IA PH: 800.782.5002	CONTRACTOR SHALL MARK LOCATIONS PRIOR TO INSTALLATION AND SHALL BE APPROVED BY OWNER'S REPRESENTATIVE. SEE STRUCTURAL DRAWINGS FOR ATTACHMENT.
RECYCLED PLASTIC CEDAR ADULT BENCH SWING & SQUARE POST PACKAGE	4	ADULT SWING RIBBED BENCH (SP320) - GREEN 6 FOOT SQUARE POST (SP305R) - GREEN	WABASH VALLEY MFG., INC. OR EQUIVALENT P.O. BOX 5 - 505 EAST MAIN STREET SILVER LAKE, INDIANA 46982 CONTACT: ALLISON HASLEY OFFICE PH: 770.966.4042 CELL PHONE: 706.338.6004	CONTRACTOR SHALL MARK LOCATIONS PRIOR TO INSTALLATION AND SHALL BE APPROVED BY OWNER'S REPRESENTATIVE.
TRASH RECEPTACLES (32 GALLON) POWDER COATED GREEN W/ 10" SPRING LOADED HATCH TRASH RECEPTACLE LIDS POWDER COATED GREEN	3 3	CN/R/RN-32 (GREEN) T/CN-24 (GREEN)	PILOT ROCK - OR EQUIVALENT P.O. BOX 946 CHEROKEE, IA PH: 800.782.5002	PROVIDE 1 BAG OF CONCRETE PLACED IN THE BOTTOM OF EACH RECEPTACLE CONTRACTOR SHALL MARK LOCATIONS PRIOR TO INSTALLATION AND SHALL BE APPROVED BY OWNER'S REPRESENTATIVE
BOLLARD (TRAFFIC BARRIER - COLLAPSIBLE)	3	TB/C-1 (YELLOW POWDER COATED) SURFACE MOUNT	PILOT ROCK - OR EQUIVALENT 5705 COMMANDER DR. ARLINGTON TN PH: 800.552.8331	SURFACE MOUNT W/ MFG. PROVIDED ANCHORS PER MFG. RECOMMENDATION

1


SITE FURNISHING SCHEDULE

SCALE: N.T.S.

Order Plans @ www.LDIDesign.com

GENERAL SITE FURNISHINGS NOTES:

- THE CONTRACTOR IS TO PROVIDE THE FOLLOWING SUBMITTALS:
 - ALL MANUFACTURER'S DATA INCLUDING DIRECTIONS OR RECOMMENDATIONS FOR INSTALLATION, METHODS, PROCEDURES AND MAINTENANCE.
 - COMPLETE SHOP DRAWINGS FOR ALL SITE FURNISHINGS INDICATING ALL DETAILS OF FABRICATION AND INSTALLATION INCLUDING SIZES, SHAPES, FINISHES, COLORS, THICKNESS, MATERIAL QUALITY AND ALL OTHER RELATED WORK APPLICABLE TO THE SITE FURNISHINGS.
 - SUBMIT COLOR SAMPLES FOR APPROVAL.
- ALL SPECIFIED PRODUCTS ARE TO BE PROVIDED AS SPECIFIED OR "APPROVED EQUIVALENT".**
 - ALL REFERENCES TO VENDORS AND "APPROVED MANUFACTURERS" ARE EXCLUDED FOR DESCRIPTION OF QUALITY AND CONTENT OF THE DESIGNATED EQUIPMENT MATERIALS AS BASIS OF DESIGN. EQUIVALENT ITEMS MAY BE ACCEPTED IF THEY MEET ALL STANDARDS OF QUALITY AND PURPOSE FOR THE INTENDED USE, AS DETERMINED BY THE COUNTY.
 - PROPOSED SUBSTITUTIONS OF PRODUCTS SHALL BE EVALUATED BASED ON PRODUCT CONSTRUCTION, APPEARANCE AND PERFORMANCE. THE CONTRACTOR WILL BE RESPONSIBLE FOR SUBMITTING ALL DOCUMENTATION SUPPORTING PROPOSED PRODUCTS NOT LESS THAN 30 DAYS AFTER NOTICE TO PROCEED OF PROJECT. THE ACCEPTANCE OR REJECTION OF PRODUCTS OFFERED AS EQUAL OR SUBSTITUTION SHALL BE AT THE SOLE DISCRETION OF THE OWNER'S REPRESENTATIVE. THE COUNTY DETERMINES THAT THE EQUIVALENT SUBMITTED IS NOT AN EQUAL BY THE COUNTY QUALITY WARRANTY OR ETC.; THE CONTRACTOR SHALL PROVIDE SPECIFIED FURNISHINGS LISTED WITHIN THE CONTRACT DOCUMENTS. NO SECOND SUBMITTAL OF PROPOSED EQUIVALENT WILL BE REVIEWED OR ACCEPTED.
- DELIVER ALL MATERIALS WITH MANUFACTURER'S TAGS AND LABELS INTACT IN CLEAN, DRY AND PROTECTED LOCATIONS.
 - STORE AND HANDLE ALL SITE FURNISHINGS SO AS TO AVOID DAMAGE.
- ALL SITE FURNISHINGS SHALL BE PROVIDED BY THE CONTRACTOR INCLUDING ORDERING, SHIPPING, DELIVERY, UNPACKING, AND INSTALLING ACCORDING TO MANUFACTURER'S SPECIFICATIONS AND AS DETAILED ON THE DRAWINGS. THE CONTRACTOR SHALL VERIFY INSTALLATION PROCEDURE WITH THE OWNER'S REPRESENTATIVE PRIOR TO INSTALLING.
- THE CONTRACTOR SHALL COORDINATE WITH THE OWNER'S REPRESENTATIVE THE DELIVERY OF ALL SITE FURNISHINGS AND SHALL BE COMPLETELY RESPONSIBLE FOR SHIPPING, UNPACKING, REMOVING PACKAGING, DISCARDING PALLET AND PACKAGING MATERIALS, AND ALL HANDLING AFTER DELIVERY TO PLACE SITE FURNISHINGS IN LOCATIONS DESIGNATED ON THE PLANS.
- ALL SITE FURNISHINGS LOCATIONS ARE TO BE APPROVED BY OWNER'S REPRESENTATIVE PRIOR TO BEING PLACED ON SITE.
- ALL SITE FURNISHINGS SHALL BE GUARANTEED BY THE CONTRACTOR FREE OF DEFECTS, CRACKS, CHIPS, STAINS AND SHALL BE COMPLETELY CLEAN AND FREE OF DAMAGES UPON FINAL PLACEMENT AND APPROVAL.
- THE GENERAL CONTRACTOR SHALL SUPPLY A LIST OF SITE FURNISHING WITH QUANTITIES TO THE OWNER'S REPRESENTATIVE PRIOR TO ORDERING. QUANTITIES ON THE PLAN SHALL OVERRULE ANY LISTS (IF APPLICABLE) STATED ON THIS SHEET.



Project Title
 LLOYD N. HARRIS TRAIL @ HARBINS PARK
 2995 LUKE EDWARDS ROAD
 BY: GWINNETT COUNTY DEPT. OF COMMUNITY SERVICES
 LAWRENCEVILLE, GEORGIA
 5TH DISTRICT, LAND LOT 251, PARCEL ID# R5282.003

REVISIONS	BY

FOR PERMIT ONLY

DRAWN BY: CE
 CHECKED BY: SP
 DATE: 08 / 09 / 2019
 SCALE: N.T.S.
 JOB No: 18-LD-068
 SHEET NUMBER: L2.0

GWINNETT COUNTY
 Department of Planning and Development
 These project documents have been reviewed by applicable County Departments and have been found to be in substantial compliance with the applicable codes and regulations.
 Oct 08, 2019
 AUTHORIZED

MATERIAL DETAILS
 SCALE: N.T.S.

GWINNETT COUNTY CASE # CDP2018-00236