


LIGHT FIXTURE SCHEDULE										
TYPE	DESCRIPTION	LAMP	# OF LAMPS	TOTAL FIXTURE WATTAGE	BALLAST/DRIVER	VOLTAGE	MANUFACTURER	MODEL	REMARKS	EXAMPLE
CF1	CEILING PANEL LIGHT (INDOORS)	N/A	N/A	52W	N/A	120V	MIRKA-ALRE KICHER EMERSON	F126-480 BRUSHED ALUM 52 527025H 073085	AS LISTED FOR INTERIOR LOCATIONS BRUSHED ALUMINUM INDOOR USE 3" DEEP MAX UP TO 87" BLADE SPAN	
DL1	6" RECESSED LED DOWNLIGHT	LED 4000K 1000 LUMENS	LED	12W	INTEGRAL 0-10V DIMMING DRIVER	UNIV	GEORAM PATHWAY JUNO COOPER SPECTRUM	EVO-40129 6AR MD LS 5WVOLT 0210 APPROVED EQUAL APPROVED EQUAL APPROVED EQUAL APPROVED EQUAL	0" AFFAIRTURE MINIMUM 50% DIMMING CLEAR SPECULAR VERIFY FINISH WITH ARCHITECT PROVIDE EMERGENCY BATTERY PACK WHERE SHOWN ON PLANS	
DL2	6" RECESSED LED DOWNLIGHT	LED 4000K 2000 LUMENS	LED	24W	INTEGRAL 0-10V DIMMING DRIVER	UNIV	GEORAM PATHWAY JUNO COOPER SPECTRUM	EVO-40120 6AN MD LS 5WVOLT 0210 APPROVED EQUAL APPROVED EQUAL APPROVED EQUAL APPROVED EQUAL	0" AFFAIRTURE MINIMUM 50% DIMMING CLEAR SPECULAR VERIFY FINISH WITH ARCHITECT PROVIDE EMERGENCY BATTERY PACK WHERE SHOWN ON PLANS	
DL3	6" RECESSED LED DOWNLIGHT (SLOPED CEILING)	LED 4000K 9000 LUMENS	LED	36W	INTEGRAL 0-10V DIMMING DRIVER	UNIV	GEORAM PATHWAY JUNO COOPER SPECTRUM	EVO-40120 6AN MD LS 5WVOLT 0210 SCAB APPROVED EQUAL APPROVED EQUAL APPROVED EQUAL APPROVED EQUAL	0" AFFAIRTURE MINIMUM 50% DIMMING CLEAR SPECULAR VERIFY FINISH WITH ARCHITECT PROVIDE EMERGENCY BATTERY PACK WHERE SHOWN ON PLANS VERIFY SLOPED CEILING ADAPTER VERIFY MOUNTING WITH ARCHITECT VERIFY LOCATION LISTED	
EX1B	BATTERY THERMOPLASTIC EXIT SIGN	LED	LED	1W	INTEGRAL LED DRIVER	UNIV	LITHONIA HUBBELL JUNO COOPER PHILLIPS	EQMS W 8 120V277 EL N 5D APPROVED EQUAL APPROVED EQUAL APPROVED EQUAL APPROVED EQUAL	VERIFY FINISH WITH ARCHITECT IS JOT EMERGENCY COMPLIANT PROVIDE EMERGENCY BATTERY PACK AS SHOWN ON PLANS	
GF1	GROUND MOUNTED LED FLOODLIGHT (FLAGPOLE)	LED 4000K 1700 LUMENS	LED	59W	INTEGRAL LED DRIVER	UNIV	MICHAEL FC ERCO	4845 18LED WHITE 50VOLT NIP 611 P55A 02 APPROVED EQUAL APPROVED EQUAL APPROVED EQUAL	AS LISTED WITH LOCATIONS PROVIDE ARMING HOOD & HANDLE MOUNTED PROVIDE POLYURETHANE CONCRETE BASE (6" MIN) SPACE PER MANUFACTURER RECOMMENDATION. VERIFY MOUNTING AND FINISH WITH ARCHITECT	
PL1	DECORATIVE PENDANT (1088)	LED 4000K 3400 LUMENS	LED	85W	INTEGRAL LED DRIVER	UNIV	LUMINUS	SCY VR24-48 41K HO F	VERIFY FINISH LENGTH AND MOUNTING STEM WITH ARCHITECT PRIOR TO ORDERING	
PL2	DECORATIVE PENDANT (1088)	LED 4000K 3500 LUMENS	LED	77W	INTEGRAL LED DRIVER	UNIV	LUMINUS	SCY VR24 72 41K HO F	VERIFY FINISH LENGTH AND MOUNTING STEM WITH ARCHITECT PRIOR TO ORDERING	
PL3	DECORATIVE PENDANT (1088)	LED 4000K 4800 LUMENS	LED	37W	INTEGRAL LED DRIVER	UNIV	LUMINUS	SCY VR24 56 41K HO F	VERIFY FINISH LENGTH AND MOUNTING STEM WITH ARCHITECT PRIOR TO ORDERING	
RTL	2'X4' UNISED VANDAL RESISTANT LED TROFFER	LED 4000K 5000 LUMENS	LED	30W	INTEGRAL 0-10V DIMMING DRIVER	UNIV	LITHONIA COLUMBIA BATON	2VH18 L 48 5200LM AP 2500K 5WVOLT 041 40K APPROVED EQUAL APPROVED EQUAL	0-10V DIMMING CLEAR SPECULAR AND MOUNTING ARCHITECT PROVIDE EMERGENCY BATTERY PACK WHERE SHOWN ON PLANS	
ST1	4 FT. LED STRIP	LED 4000K 5000 LUMENS	LED	35W	INTEGRAL LED DRIVER (STANDARD 0-10V DIMMING)	UNIV	LITHONIA COLUMBIA ERCO COOPER DAY-BRITE	CLX LED LAB 5200LM SEP FOL 5WVOLT 0230 40K APPROVED EQUAL APPROVED EQUAL APPROVED EQUAL APPROVED EQUAL	0-10V DIMMING PROVIDE CHAIN FOR MOUNTING PROVIDE WIRE GUARD WHERE PROVIDE EMERGENCY BATTERY PACK WHERE SHOWN ON PLANS	
VL1	2'X2' VOLUMETRIC LED TROFFER	LED 4000K 3200 LUMENS	LED	30W	INTEGRAL 0-10V DIMMING DRIVER	UNIV	LITHONIA DURAN WERY BATON	2VH12 30 40P 421 118RD APPROVED EQUAL APPROVED EQUAL	0-10V DIMMING VERIFY FINISH WITH ARCHITECT PROVIDE EMERGENCY BATTERY PACK WHERE SHOWN ON PLANS	
VL2	2'X4' VOLUMETRIC LED TROFFER	LED 4000K 4900 LUMENS	LED	31W	INTEGRAL 0-10V DIMMING DRIVER	UNIV	LITHONIA COLUMBIA BATON	2VH12 30 40P 421 118RD APPROVED EQUAL APPROVED EQUAL	0-10V DIMMING VERIFY FINISH WITH ARCHITECT PROVIDE EMERGENCY BATTERY PACK WHERE SHOWN ON PLANS	
WL1	WALL PACK TRIANGLE LED	LED 4000K 3000 LUMENS	LED	25W	INTEGRAL LED DRIVERS (2)	UNIV	LITHONIA HUBBELL JUNO COOPER PHILLIPS	AS LISTED BY MANUFACTURER APPROVED EQUAL APPROVED EQUAL APPROVED EQUAL APPROVED EQUAL	VERIFY FINISH WITH ARCHITECT IS JOT EMERGENCY COMPLIANT PROVIDE EMERGENCY BATTERY PACK AS SHOWN ON PLANS	
WL2	EXTERIOR UP/DOWN LED	LED 4000K	LED	30W	INTEGRAL LED DRIVER	UNIV	PATHWAY APPROVED EQUAL	APPROVED EQUAL	COLOR CHOSEN BY ARCHITECT VERIFY LOCATION LISTED	
WL3	EXTERIOR WALL WASH (BUILDING SIGN)	LED 4000K	LED	W/ APPROXIMATE 120W PER FOOT	INTEGRAL LED DRIVER	UNIV	SPL LIGHTING APPROVED EQUAL	SEW12146 56 FT-L 40W 120V277V 4000K 51A APPROVED EQUAL	COLOR CHOSEN BY ARCHITECT VERIFY LOCATION LISTED VERIFY MOUNTING AND LENGTHS WITH ARCHITECT	

**LIGHTING FIXTURE NOTES**

1. ALL FIXTURES SHALL BE 4000K AS SPECIFIED. ALL DRIVERS SHALL BE ELECTRONIC AS SPECIFIED. SUBMITTAL SHEETS SHALL BE SUBMITTED WITH FIXTURE SUBMITTALS. DRIVERS AND BOARD WARRANTY SHALL BE COMPLETED BY CONTRACTOR AND TURNED OVER TO OWNER AT END OF PROJECT.
2. SUBSTITUTIONS APPROVED BY THE ENGINEER PREVIOUS TO BID ARE ACCEPTABLE AS LONG AS THEY ARE EQUAL TO THE FIXTURE SPECIFIED, UNLESS OTHERWISE NOTED. THIS INCLUDES LENS, COLORS, REFLECTORS, PHOTOMETRICS, HOUSING MATERIALS, FINISHES, ETC. ALL SUBSTITUTIONS SHALL BE SUBMITTED TO THE ENGINEER WITH CUT SHEETS FOR APPROVAL. SUBSTITUTE FIXTURES SHALL BE PRICED WITH THE SPECIFIED FIXTURE AND LISTED SEPARATELY SO THE ENGINEER AND OWNER CAN MAKE AN INFORMED DECISION.
3. SEE ARCHITECTURAL REFLECTED CEILING PLAN FOR EXACT FIXTURE LOCATIONS.
4. FIXTURES SHALL BE FIRE RATED. SEE PLANS FOR MORE INFORMATION/LOCATIONS.
5. PROVIDE LOW-TEMP (00F MINIMUM) DRIVERS FOR ALL FIXTURES INSTALLED IN EXTERIOR LOCATIONS OR OTHER AREAS SUBJECT TO COLD WEATHER.
6. SUSPEND ALL FOUR CORNERS WITH WIRE TO STRUCTURE. DO NOT ALLOW GRID ALONE TO SUPPORT FIXTURE.
7. MODULAR WRING ("RELOC") SYSTEMS ARE AN ACCEPTABLE WRING METHOD FOR LIGHTING CIRCUITS.
8. THE CONTRACTOR SHALL VERIFY THE LEAD TIME OF ALL PRODUCTS SPECIFIED IN THIS SCHEDULE AT THE TIME OF PACKAGE QUOTE.
9. DURING THE BID PROCESS, THE CONTRACTOR SHALL NOTIFY THE ARCHITECT/ENGINEER OF ANY DELIVERY SCHEDULING ISSUES.
10. NO SUBSTITUTIONS WILL BE ALLOWED DUE TO LACK OF COORDINATION OF DELIVERY DATES AND CONSTRUCTION SCHEDULE AFTER BID.
11. ALL EXPEDITED EXPENSES SHALL BE THE RESPONSIBILITY OF THE CONTRACTOR.
12. FIXTURES TO BE INSTALLED IN CEILINGS, INDICATED ON ARCHITECTURAL PLANS AS HAVING INSULATION IN CONTACT WITH CEILING SURFACE, SHALL BE IC RATED BY MANUFACTURER.
13. PROVIDE 90 MINUTE EMERGENCY BATTERY BACK UP. SEE PLANS FOR LOCATIONS. EMERGENCY BACK UP SHALL BE BASED ON TYPE OF FIXTURE, LED DRIVER, BALLAST, ETC. EMERGENCY BACKUP SHALL BE DUAL INPUT FOR BOTH SWITCHING AND CHARGING. PROVIDE UNBATTERYED "HOT" FROM LOCAL CIRCUIT UNLESS OTHERWISE INDICATED ON PLANS. PROVIDE WITH INDICATOR LIGHT. INSTALL LED INDICATOR ON LIGHT FIXTURE UNLESS DECORATIVE. DECORATIVE FIXTURES SHALL HAVE INDICATOR PLACED AT LOCAL CEILING. BODINE, PHILLIPS, POWER SENTRY OR EQUAL.
14. VERIFY ALL FIXTURE FINISHES, TRIM, AND COLOR OPTIONS WITH ARCHITECT PRIOR TO ORDERING.



RENOVATION AND  
ADDITION FOR  
**ABERDEEN  
POLICE  
DEPARTMENT**



10/25/2019

LIGHTING  
FIXTURE  
SCHEDULE

DATE: 10/25/2019  
PROJECT NO: 18062

REVISIONS  
NO. DATE DESCRIPTION

THIS DRAWING IS THE PROPERTY OF ADW ARCHITECTS, P.A. AND SHALL NOT BE REPRODUCED OR COPIED IN WHOLE OR PART. IT SHALL NOT BE USED ON ANY OTHER PROJECT OR GIVEN TO ANY OTHER COMPANY OR AGENCY WITHOUT THE CONSENT OF ADW ARCHITECTS, P.A.

Order Plans @ WWW.LDILine.com