SECTION 16A GENERAL ELECTRICAL REQUIREMENTS:

16A GENERAL INSTRUCTIONS

16A GENERAL REQUIREMENTS

ALL REQUIREMENTS UNDER DIVISION 1 AND THE GENERAL AND SUPPLEMENTARY CONDITIONS OF THESE SPECIFICATIONS APPLY TO THIS SECTION AND DIVISION. WHERE THE REQUIREMENTS OF THIS SECTION AND DIVISION EXCEED THOSE OF DIVISION 1, THIS SECTION AND DIVISION TAKE PRECEDENCE. BECOME THOROUGHLY FAMILIAR WITH ALL THEIR CONTENTS AS TO REQUIREMENTS THAT AFFECT THIS DIVISION, SECTION OR BOTH. WORK REQUIRED UNDER THIS DIVISION INCLUDES ALL MATERIAL, EQUIPMENT, APPLIANCES, AND LABOR REQUIRED TO COMPLETE THE ENTIRE ELECTRICAL SYSTEM AS REQUIRED BY THE DRAWINGS AND SPECIFICATIONS, OR REASONABLY INFERRED TO BE NECESSARY TO FACILITATE EACH SYSTEM'S FUNCTIONING AS IMPLIED BY THE DESIGN AND THE EQUIPMENT SPECIFIED.

THE SPECIFICATIONS AND DRAWINGS FOR THE PROJECT ARE COMPLEMENTARY, AND PORTIONS OF THE WORK DESCRIBED IN ONE, SHALL BE PROVIDED AS IF DESCRIBED IN BOTH. IN THE EVENT OF DISCREPANCIES, NOTIFY THE ENGINEER AND REQUEST CLARIFICATION PRIOR TO PROCEEDING WITH THE WORK INVOLVED.

DRAWINGS ARE GRAPHIC REPRESENTATIONS OF THE WORK UPON WHICH THE CONTRACT IS BASED. THEY SHOW THE MATERIALS AND THEIR RELATIONSHIP TO ONE ANOTHER, INCLUDING SIZES, SHAPES, LOCATIONS, AND CONNECTIONS. THEY ALSO CONVEY THE SCOPE OF WORK, INDICATING THE INTENDED GENERAL ARRANGEMENT OF THE EQUIPMENT, FIXTURES, OUTLETS AND CIRCUITS WITHOUT SHOWING ALL OF THE EXACT DETAILS AS TO ELEVATIONS, OFFSETS, CONTROL LINES, AND OTHER INSTALLATION REQUIREMENTS. USE THE DRAWINGS AS A GUIDE WHEN LAYING OUT THE WORK AND TO VERIFY THAT MATERIALS AND EQUIPMENT WILL FIT INTO THE DESIGNATED SPACES, AND WHICH, WHEN INSTALLED PER MANUFACTURERS' REQUIREMENTS, WILL ENSURE A COMPLETE, COORDINATED, SATISFACTORY AND PROPERLY OPERATING SYSTEM.

DRAWINGS ARE SCHEMATIC IN NATURE, SHOW THE VARIOUS COMPONENTS OF THE SYSTEMS APPROXIMATELY TO SCALE AND ATTEMPT TO INDICATE HOW THEY SHALL BE INTEGRATED WITH OTHER PARTS OF THE WORK. FIGURED DIMENSIONS TAKE PRECEDENCE TO SCALED DIMENSIONS. DETERMINE EXACT LOCATIONS BY JOB MEASUREMENTS, BY CHECKING THE REQUIREMENTS OF OTHER TRADES, AND BY REVIEWING ALL CONTRACT DOCUMENTS. CORRECT ERRORS THAT COULD HAVE BEEN AVOIDED BY PROPER CHECKING AND INSPECTION, AT NO ADDITIONAL COST TO THE OWNER.

SPECIFICATIONS DEFINE THE QUALITATIVE REQUIREMENTS FOR PRODUCTS, MATERIALS, AND WORKMANSHIP UPON WHICH THE CONTRACT IS BASED.

16A DEFINITIONS

WHENEVER USED IN THESE SPECIFICATIONS OR DRAWINGS, THE FOLLOWING TERMS SHALL HAVE THE INDICATED MEANINGS:

FURNISH: "TO SUPPLY AND DELIVER TO THE PROJECT SITE, READY FOR UNLOADING, UNPACKING, ASSEMBLING, INSTALLING, AND SIMILAR OPERATIONS."

INSTALL: "TO PERFORM ALL OPERATIONS AT THE PROJECT SITE, INCLUDING, BUT NOT LIMITED TO, AND AS REQUIRED: UNLOADING, UNPACKING, ASSEMBLING, ERECTING, PLACING, ANCHORING, APPLYING, WORKING TO DIMENSION, FINISHING, CURING, PROTECTING, CLEANING, TESTING, COMMISSIONING, STARTING UP AND SIMILAR OPERATIONS, COMPLETE, AND READY FOR THE INTENDED USE."

PROVIDE: "TO FURNISH AND INSTALL COMPLETE, AND READY FOR THE INTENDED USE." FURNISHED BY OWNER (OR OWNER-FURNISHED) OR FURNISHED BY OTHERS: "AN ITEM FURNISHED BY THE OWNER OR UNDER OTHER DIVISIONS OR CONTRACTS, AND INSTALLED UNDER THE REQUIREMENTS OF THIS DIVISION, COMPLETE, AND READY FOR THE INTENDED USE, INCLUDING ALL ITEMS AND SERVICES INCIDENTAL TO THE WORK NECESSARY FOR PROPER INSTALLATION AND OPERATION. INCLUDE THE INSTALLATION UNDER THE WARRANTY REQUIRED BY THIS DIVISION."

ENGINEER: WHERE REFERENCED IN THIS DIVISION, "ENGINEER" IS THE ENGINEER OF RECORD AND THE DESIGN PROFESSIONAL FOR THE WORK UNDER THIS DIVISION, AND IS A CONSULTANT TO, AND AN AUTHORIZED REPRESENTATIVE OF, THE ARCHITECT, AS DEFINED IN THE GENERAL AND/OR SUPPLEMENTARY CONDITIONS. WHEN USED IN THIS DIVISION, IT MEANS INCREASED INVOLVEMENT BY, AND OBLIGATIONS TO, THE ENGINEER, IN ADDITION TO INVOLVEMENT BY, AND OBLIGATIONS TO, THE "ARCHITECT".

AHJ: THE LOCAL CODE AND/OR INSPECTION AGENCY (AUTHORITY) HAVING JURISDICTION OVER THE WORK.

NRTL: NATIONALLY RECOGNIZED TESTING LABORATORY, AS DEFINED AND LISTED BY OSHA IN 29 CFR 1910.7 (E.G., UL, ETL, CSA), AND ACCEPTABLE TO THE AHJ OVER THIS PROJECT.

HOMERUN: THAT PORTION OF AN ELECTRICAL CIRCUIT ORIGINATING AT A JUNCTION BOX, TERMINATION BOX, RECEPTACLE OR SWITCH WITH TERMINATION AT AN ELECTRICAL PANELBOARD. NOTE: WHERE MC CABLE IS UTILIZED FOR RECEPTACLE AND/OR LIGHTING BRANCH CIRCUITING LOADS, THE ORIGINATING POINT OF THE HOMERUN SHALL BE AT THE FIRST LOAD IN THE CIRCUIT OR AT A JUNCTION BOX IN AN ACCESSIBLE CEILING SPACE IMMEDIATELY ABOVE THE FIRST LOAD.

THE TERMS "APPROVED EQUAL", "EQUIVALENT", OR "EQUAL" ARE USED SYNONYMOUSLY AND SHALL MEAN "ACCEPTED BY OR ACCEPTABLE TO THE ENGINEER AS EQUIVALENT TO THE ITEM OR MANUFACTURER SPECIFIED". THE TERM "APPROVED" SHALL MEAN LABELED, LISTED, CERTIFIED, OR ALL THREE, BY AN NRTL, AND ACCEPTABLE TO THE AHJ OVER THIS PROJECT.

16A PRE-BID SITE VISIT

PERSONALLY INSPECT THE SITE OF THE PROPOSED WORK AND BECOME FULLY INFORMED OF CONDITIONS UNDER WHICH THE WORK IS TO BE DONE. FAILURE TO DO SO WILL NOT BE CONSIDERED SUFFICIENT JUSTIFICATION TO REQUEST OR OBTAIN EXTRA COMPENSATION OVER AND ABOVE THE CONTRACT PRICE. COORDINATE SITE VISIT WITH ARCHITECT & BUILDING OWNER.

16A MATERIAL AND WORKMANSHIP

PROVIDE ALL MATERIAL AND EQUIPMENT NEW AND IN FIRST CLASS CONDITION. PROVIDE MARKINGS OR A NAMEPLATE FOR ALL MATERIAL AND EQUIPMENT IDENTIFYING THE MANUFACTURER AND PROVIDING SUFFICIENT REFERENCE TO ESTABLISH QUALITY, SIZE AND CAPACITY. ALL WORKMANSHIP SHALL BE OF THE FINEST POSSIBLE BY EXPERIENCED MECHANICS OF THE PROPER TRADE. IN GENERAL, PROVIDE THE FOLLOWING QUALITY GRADE(S) FOR ALL MATERIALS AND EQUIPMENT

COMMERCIAL SPECIFICATION GRADE

PROVIDE ALL HOISTS, SCAFFOLDS, STAGING, RUNWAYS, TOOLS, MACHINERY AND EQUIPMENT REQUIRED FOR THE PERFORMANCE OF THE ELECTRICAL WORK. STORE AND MAINTAIN MATERIAL AND EQUIPMENT IN CLEAN CONDITION, AND PROTECTED FROM WEATHER, MOISTURE, AND PHYSICAL DAMAGE.

FURNISH ONLY MATERIAL AND EQUIPMENT THAT ARE LISTED, LABELED, CERTIFIED, OR ALL THREE, BY A NATIONALLY RECOGNIZED TESTING LABORATORY (NRTL), WHENEVER ANY LISTING OR LABELING EXISTS FOR THE TYPES OF MATERIAL AND EQUIPMENT SPECIFIED.

AT A MINIMUM, GENERAL WORK PRACTICES FOR ELECTRICAL CONSTRUCTION SHALL BE IN ACCORDANCE WITH:
NECA 1 (LATEST EDITION), "STANDARD PRACTICES FOR GOOD WORKMANSHIP IN ELECTRICAL CONSTRUCTION".

16A MANUFACTURERS

IN OTHER ARTICLES WHERE LISTS OF MANUFACTURERS ARE INTRODUCED, SUBJECT TO COMPLIANCE WITH REQUIREMENTS, PROVIDE PRODUCTS BY ONE OF THE MANUFACTURERS SPECIFIED.

WHERE A LIST IS PROVIDED, MANUFACTURERS ARE LISTED ALPHABETICALLY AND NOT IN ACCORDANCE WITH ANY RANKING OR PREFERENCE.

WHERE MANUFACTURERS ARE NOT LISTED, PROVIDE PRODUCTS SUBJECT TO COMPLIANCE WITH REQUIREMENTS FROM MANUFACTURERS THAT HAVE BEEN ACTIVELY INVOLVED IN MANUFACTURING THE SPECIFIED PRODUCT FOR NO LESS THAN 5 YEARS.

16A COORDINATION

COORDINATE ALL WORK WITH OTHER DIVISIONS AND TRADES SO THAT VARIOUS COMPONENTS OF THE ELECTRICAL SYSTEMS ARE INSTALLED AT THE PROPER TIME, FIT THE AVAILABLE SPACE, AND ALLOW PROPER SERVICE ACCESS TO ALL EQUIPMENT. REFER TO ALL DRAWINGS, INCLUDING, BUT NOT LIMITED TO, CIVIL, ARCHITECTURAL, STRUCTURAL, MECHANICAL, AND PLUMBING, AND TO RELEVANT EQUIPMENT SUBMITTALS AND SHOP DRAWINGS TO DETERMINE THE EXTENT OF CLEAR SPACES. MAKE ALL OFFSETS REQUIRED TO CLEAR EQUIPMENT, BEAMS AND OTHER STRUCTURAL MEMBERS, AND TO FACILITATE CONCEALING RACEWAYS IN THE MANNER ANTICIPATED IN THE DESIGN. PROVIDE MATERIALS WITH TRIM THAT WILL FIT PROPERLY THE TYPES OF CEILING, WALL, OR FLOOR FINISHES ACTUALLY INSTALLED.

16A ORDINANCES, CODES, AND STANDARDS

COMPLY, AT A MINIMUM, WITH NATIONAL FIRE PROTECTION ASSOCIATION (NFPA) STANDARDS, STATE AND LOCAL BUILDING CODES, AND ALL OTHER APPLICABLE CODES AND ORDINANCES FOR PERFORMANCE, WORKMANSHIP, EQUIPMENT, AND MATERIALS. ADDITIONALLY, COMPLY WITH RULES AND REGULATIONS OF PUBLIC UTILITIES AND MUNICIPAL DEPARTMENTS AFFECTED BY CONNECTION OF SERVICES.

WHERE CONFLICTS BETWEEN VARIOUS CODES, ORDINANCES, RULES, AND REGULATIONS EXIST, COMPLY WITH THE MOST STRINGENT. WHEREVER REQUIREMENTS OF THESE SPECIFICATIONS, DRAWINGS, OR BOTH, EXCEED THOSE OF THE ABOVE ITEMS, THE REQUIREMENTS OF THESE SPECIFICATIONS, DRAWINGS, OR BOTH, SHALL GOVERN. CODE COMPLIANCE, AT A MINIMUM, IS MANDATORY. CONSTRUE NOTHING IN THESE CONSTRUCTION DOCUMENTS AS PERMITTING WORK NOT IN COMPLIANCE, AT A MINIMUM, WITH THESE CODES.

PROMPTLY BRING ALL CONFLICTS OBSERVED BETWEEN CODES, ORDINANCES, RULES, REGULATIONS, REFERENCED STANDARDS, AND THESE DOCUMENTS TO THE ENGINEER'S ATTENTION FOR FINAL RESOLUTION. CONTRACTOR WILL BE HELD RESPONSIBLE FOR ANY VIOLATION OF THE LAW.

PROVIDE AND MAINTAIN ALL NECESSARY SIGNAL LIGHTS AND GUARDS FOR THE SAFETY OF THE PUBLIC. OBTAIN AND PAY FOR ALL PERMITS FOR WORK IN THIS DIVISION.

16A PROTECTION OF EQUIPMENT AND MATERIALS

STORE AND PROTECT FROM DAMAGE EQUIPMENT AND MATERIALS DELIVERED TO JOB SITE, IN ACCORDANCE WITH MANUFACTURERS' RECOMMENDATIONS. FOR MATERIALS AND EQUIPMENT SUSCEPTIBLE TO CHANGING WEATHER CONDITIONS, DAMPNESS, OR TEMPERATURE VARIATIONS, STORE INSIDE IN CONDITIONED SPACES. FOR MATERIALS AND EQUIPMENT NOT SUSCEPTIBLE TO THESE CONDITIONS, COVER WITH WATERPROOF, TEAR-RESISTANT, HEAVY TARP OR POLYETHYLENE PLASTIC AS REQUIRED TO PROTECT FROM PLASTER, DIRT, PAINT, WATER, OR PHYSICAL DAMAGE. EQUIPMENT AND MATERIAL THAT HAS BEEN DAMAGED BY CONSTRUCTION ACTIVITIES WILL BE REJECTED, AND CONTRACTOR SHALL FURNISH NEW EQUIPMENT AND MATERIAL OF A LIKE KIND.

PLUG OR CAP OPEN ENDS OF CONDUITS WHILE STORED AND INSTALLED DURING CONSTRUCTION WHEN NOT IN USE TO PREVENT THE ENTRANCE OF DEBRIS INTO THE SYSTEMS.

16A SUBSTITUTIONS

INCLUDE IN THE BASE BID THE PRODUCTS SPECIFICALLY NAMED IN THESE SPECIFICATIONS OR ON THE DRAWINGS. SUBMIT, IN THE FORM OF ALTERNATES, WITH BID, PRODUCTS OF ANY OTHER MANUFACTURERS FOR SIMILAR USE, PROVIDED THE DIFFERENCES IN COST, IF ANY, ARE INCLUDED FOR EACH PROPOSED ALTERNATE.

PRIOR TO THE BID DATE, SUBSTITUTIONS WILL NOT BE CONSIDERED UNLESS SUBMITTED FOR ENGINEER'S REVIEW, AT LEAST TEN CALENDAR DAYS PRIOR TO THE DATE FOR RECEIPT OF BIDS. INCLUDE THE NAME OF THE MATERIAL OR EQUIPMENT FOR WHICH IT IS TO BE SUBSTITUTED AND A COMPLETE DESCRIPTION OF THE PROPOSED SUBSTITUTE INCLUDING CUTSHEETS, PHOTOMETRIC DATA, AND ALL OTHER INFORMATION NECESSARY FOR AN EVALUATION FOR EACH SUCH REQUEST. PROVIDE FACTORY GENERATED POINT-BY-POINT CALCULATIONS FOR ALL EXTERIOR LIGHT FIXTURES (PHOTOMETRIC FILES SUPPLIED SO THE ENGINEER CAN GENERATE A POINT-BY-POINT DO NOT SUFFICE FOR THE POINT-BY-POINT CALCULATIONS). PROVIDE INTERIOR POINT-BY-POINT CALCULATIONS AT THE DISCRETION OF THE ENGINEER. SUBMIT A $100.00 REVIEW FEE TO THE ENGINEER WITH EACH SUCH POINT-BY-POINT CALCULATION FOR USE OF ELECTRONIC BASE FILES.

AFTER THE BID DATE, PROPOSALS TO SUBSTITUTE LIGHT FIXTURES FOR THOSE SHOWN ON THE DRAWINGS OR SPECIFIED HEREIN, WILL ONLY BE CONSIDERED AS A DEDUCT. SUBMIT PROPOSED SUBSTITUTIONS SEPARATELY, IN SUBMITTAL FORM, WITH A LIST OF PROPOSED SUBSTITUTIONS TOGETHER WITH A DEDUCT PRICE FOR EACH SUBSTITUTION. THE ENGINEER WILL THEN REVIEW THE PROPOSED SUBSTITUTIONS.

THE ENGINEER WILL HAVE THE FINAL AUTHORITY AS TO WHETHER THE LIGHT FIXTURE IS AN ACCEPTABLE REPLACEMENT TO THE SPECIFIED ITEM. THE PROPOSED SUBSTITUTION MAY ALSO BE REJECTED BY THE ARCHITECT, THE ENGINEER OR THE OWNER FOR AESTHETIC REASONS IF FELT NECESSARY OR DESIRABLE. IN THE EVENT THE PROPOSED SUBSTITUTIONS HEREIN DESCRIBED ARE REJECTED, FURNISH THE SPECIFIED ITEM.

16A SUBMITTALS

ASSEMBLE AND SUBMIT FOR ENGINEER'S REVIEW, MANUFACTURERS' PRODUCT LITERATURE FOR MATERIAL AND EQUIPMENT TO BE FURNISHED, INSTALLED, OR BOTH, UNDER THIS DIVISION, INCLUDING SHOP DRAWINGS, MANUFACTURERS' PRODUCT DATA AND PERFORMANCE SHEETS, SAMPLES, AND OTHER SUBMITTALS REQUIRED BY THIS DIVISION. HIGHLIGHT, MARK, LIST OR INDICATE THE MATERIALS, PERFORMANCE CRITERIA AND ACCESSORIES THAT ARE BEING PROPOSED. PROVIDE THE NUMBER OF SUBMITTALS REQUIRED BY DIVISION 1. BEFORE SUBMITTING, VERIFY THAT ALL MATERIALS AND EQUIPMENT SUBMITTED ARE MUTUALLY COMPATIBLE AND SUITABLE FOR THE INTENDED USE, FIT THE AVAILABLE SPACES, AND ALLOW AMPLE AND CODE-REQUIRED ROOM FOR ACCESS AND MAINTENANCE. SUBMITTALS SHALL CONTAIN THE FOLLOWING INFORMATION. SUBMITTALS NOT SO IDENTIFIED WILL BE RETURNED TO THE CONTRACTOR WITHOUT ACTION:

THE PROJECT NAME.

THE APPLICABLE SPECIFICATION SECTION AND PARAGRAPH.

THE SUBMITTAL DATE.

THE CONTRACTOR'S STAMP, WHICH SHALL CERTIFY THAT THE STAMPED DRAWINGS HAVE BEEN CHECKED BY THE CONTRACTOR, COMPLY WITH THE DRAWINGS AND SPECIFICATIONS, AND HAVE BEEN COORDINATED WITH OTHER TRADES.

SUBMITTALS AND SHOP DRAWINGS SHALL NOT CONTAIN RTM'S FIRM NAME OR LOGO, NOR SHALL IT CONTAIN THE RTM'S ENGINEERS' SEAL AND SIGNATURE. THEY SHALL NOT BE COPIES OF RTM'S WORK PRODUCT.

TRANSMIT SUBMITTALS AS EARLY AS REQUIRED TO SUPPORT THE PROJECT SCHEDULE. ALLOW FOR TWO WEEKS ENGINEER REVIEW TIME, PLUS MAILING TIME, PLUS A DUPLICATION OF THIS TIME FOR RESUBMITTALS, IF REQUIRED. TRANSMIT SUBMITTALS AS SOON AS POSSIBLE AFTER NOTICE TO PROCEED AND BEFORE CONSTRUCTION STARTS. THE ENGINEER'S SUBMITTAL REVIEWS WILL NOT RELIEVE THE CONTRACTOR FROM RESPONSIBILITY FOR ERRORS IN DIMENSIONS, DETAILS, SIZE OF MEMBERS, OR QUANTITIES; OR FOR OMITTING COMPONENTS OR FITTINGS; OR FOR NOT COORDINATING ITEMS WITH ACTUAL BUILDING CONDITIONS.

REFER TO DIVISION 1 FOR ACCEPTANCE OF ELECTRONIC SUBMITTALS FOR THIS PROJECT. FOR ELECTRONIC SUBMITTALS, CONTRACTOR SHALL SUBMIT THE DOCUMENTS IN ACCORDANCE WITH THE PROCEDURES SPECIFIED IN DIVISION 1. CONTRACTOR SHALL NOTIFY THE ARCHITECT AND ENGINEER THAT THE SHOP DRAWINGS HAVE BEEN POSTED. IF ELECTRONIC SUBMITTAL PROCEDURES ARE NOT DEFINED IN DIVISION 1, CONTRACTOR SHALL INCLUDE THE WEBSITE, USER NAME AND PASSWORD INFORMATION NEEDED TO ACCESS THE SUBMITTALS. FOR SUBMITTALS SENT BY E-MAIL, CONTRACTOR SHALL COPY THE ARCHITECT AND ENGINEER'S DESIGNATED REPRESENTATIVES. CONTRACTOR SHALL ALLOW THE ENGINEER REVIEW TIME AS SPECIFIED ABOVE IN THE CONSTRUCTION SCHEDULE. CONTRACTOR SHALL SUBMIT ONLY THE DOCUMENTS REQUIRED TO PURCHASE THE MATERIALS AND/OR EQUIPMENT IN THE ELECTRONIC SUBMITTAL AND SHALL CLEARLY INDICATE THE MATERIALS, PERFORMANCE CRITERIA AND ACCESSORIES BEING PROPOSED. GENERAL PRODUCT CATALOG DATA NOT SPECIFICALLY NOTED TO BE PART OF THE SPECIFIED PRODUCT WILL BE REJECTED AND RETURNED WITHOUT REVIEW.

16A ELECTRONIC DRAWING FILES

IN PREPARATION OF SHOP DRAWINGS OR RECORD DRAWINGS, CONTRACTOR MAY, AS AN OPTION, OBTAIN ELECTRONIC DRAWING FILES IN AUTOCAD OR DXF FORMAT FROM THE ENGINEER FOR A SHIPPING AND HANDLING FEE OF $200 FOR A DRAWING SET UP TO 12 SHEETS AND $15 PER SHEET FOR EACH ADDITIONAL SHEET. CONTACT THE ARCHITECT FOR WRITTEN AUTHORIZATION; AND, CONTACT THE ENGINEER TO OBTAIN THE NECESSARY RELEASE AGREEMENT FORM AND TO INDICATE THE DESIRED SHIPPING METHOD AND DRAWING FORMAT. IN ADDITION TO PAYMENT, ARCHITECT'S WRITTEN AUTHORIZATION AND ENGINEER'S RELEASE AGREEMENT FORM MUST BE RECEIVED BEFORE ELECTRONIC DRAWING FILES WILL BE SENT.

16A OPERATION AND MAINTENANCE INSTRUCTIONS

SUBMIT FOR ENGINEER'S REVIEW, COPIES EACH OF OPERATIONS AND MAINTENANCE INSTRUCTION MANUALS, APPROPRIATELY BOUND INTO MANUAL FORM INCLUDING APPROVED COPIES OF THE FOLLOWING, REVISED IF NECESSARY TO SHOW SYSTEM AND EQUIPMENT AS ACTUALLY INSTALLED. PROVIDE THE NUMBER OF SUBMITTALS REQUIRED BY DIVISION 1; HOWEVER, AT A MINIMUM, SUBMIT THREE (3) SETS, AND INCLUDE, AT A MINIMUM, THE FOLLOWING INFORMATION:

MANUFACTURERS' CATALOGS AND PRODUCT DATA SHEETS

WIRING DIAGRAMS

MAINTENANCE INSTRUCTIONS

OPERATING INSTRUCTIONS

PARTS LISTS

TEST REPORTS AS DEFINED IN NETA ATS FOR THE SYSTEMS AND EQUIPMENT PROVIDED OR FURNISHED OR INSTALLED UNDER THIS CONTRACT.

NAMES, ADDRESSES, TELEPHONE NUMBERS, AND E-MAIL ADDRESSES OF LOCAL CONTACTS FOR WARRANTY SERVICES AND SPARE PARTS.

SUBMIT MANUALS PRIOR TO REQUESTING THE FINAL PUNCH LIST AND BEFORE ANY REQUESTS FOR SUBSTANTIAL COMPLETION. ALSO PROVIDE ADEQUATE VERBAL INSTRUCTIONS OF SYSTEM OPERATIONS TO OWNER'S REPRESENTATIVE AT THE COMPLETION OF, AND BEFORE FINAL ACCEPTANCE OF, THE WORK.

16A WARRANTIES

WARRANT EACH SYSTEM AND EACH ELEMENT THEREOF AGAINST ALL DEFECTS DUE TO FAULTY WORKMANSHIP, DESIGN OR MATERIAL FOR A PERIOD OF 12 MONTHS FROM DATE OF SUBSTANTIAL COMPLETION, UNLESS SPECIFIC ITEMS ARE NOTED TO CARRY A LONGER WARRANTY IN THE CONSTRUCTION DOCUMENTS OR MANUFACTURER'S STANDARD WARRANTY EXCEEDS 12 MONTHS. REMEDY ALL DEFECTS, OCCURRING WITHIN THE WARRANTY PERIOD(S), AS STATED IN THE GENERAL CONDITIONS AND DIVISION 1.

ALSO WARRANT THE FOLLOWING ADDITIONAL ITEMS:

ALL RACEWAYS ARE FREE FROM OBSTRUCTIONS, HOLES, CRUSHING, OR BREAKS OF ANY NATURE.

ALL RACEWAY SEALS ARE EFFECTIVE.

THE ENTIRE ELECTRICAL SYSTEM IS FREE FROM ALL SHORT CIRCUITS AND UNWANTED OPEN CIRCUITS AND GROUNDS.

THE ABOVE WARRANTIES SHALL INCLUDE LABOR AND MATERIAL. MAKE REPAIRS OR REPLACEMENTS WITHOUT ANY ADDITIONAL COSTS TO THE OWNER.

PERFORM THE REMEDIAL WORK PROMPTLY, UPON WRITTEN NOTICE FROM THE ENGINEER OR OWNER.

AT THE TIME OF SUBSTANTIAL COMPLETION, DELIVER TO THE OWNER ALL WARRANTIES, IN WRITING AND PROPERLY EXECUTED, INCLUDING TERM LIMITS FOR WARRANTIES EXTENDING BEYOND THE ONE YEAR PERIOD, EACH WARRANTY INSTRUMENT BEING ADDRESSED TO THE OWNER AND STATING THE COMMENCEMENT DATE AND TERM.

16A MISCELLANEOUS REMODELING WORK

PROVIDE ALL DEMOLITION OF EXISTING ELECTRICAL SYSTEMS AND NEW ELECTRICAL SYSTEM MODIFICATIONS REQUIRED BECAUSE OF BUILDING REMODELING, AS NOTED ON THE DRAWINGS, OR NECESSARY FOR PROPER OPERATION AND NEW CONSTRUCTION. REMOVE ALL ABANDONED CABLES AND WIRING ABOVE ACCESSIBLE CEILINGS AND VENTILATION SHAFTS.

16A ELECTRICAL WORK

16A BUILDING OPERATION

COMPLY WITH THE SCHEDULE OF OPERATIONS AS OUTLINED IN THE ARCHITECTURAL PORTIONS OF THIS SPECIFICATION. BUILDING SHALL BE IN CONTINUOUS OPERATION. ACCOMPLISH WORK THAT REQUIRES INTERRUPTION OF BUILDING OPERATION AT A TIME WHEN THE BUILDING IS NOT IN OPERATION, AND ONLY WITH WRITTEN APPROVAL OF BUILDING OWNER AND/OR TENANT. COORDINATE INTERRUPTION OF BUILDING OPERATION WITH THE OWNER AND/OR TENANT A MINIMUM OF 7 DAYS IN ADVANCE OF WORK.

16A COINCIDENTAL DAMAGE

REPAIR ALL STREETS, SIDEWALKS, DRIVES, PAVING, WALLS, FINISHES, AND OTHER FACILITIES DAMAGED IN THE COURSE OF THIS WORK. REPAIR MATERIALS SHALL MATCH EXISTING CONSTRUCTION. ALL BACKFILLING AND REPAIRING SHALL MEET ALL REQUIREMENTS OF THE OWNER, CITY AND OTHERS HAVING JURISDICTION. REPAIR WORK SHALL BE THOROUGHLY FIRST CLASS. CONFORM TO ALL REQUIREMENTS OF DIVISION 2 OF THESE SPECIFICATIONS.

16A CUTTING AND PATCHING

FOLLOWING THE REQUIREMENTS IN DIVISION 1, CUT WALLS, FLOORS, CEILINGS, AND OTHER PORTIONS OF THE FACILITY AS REQUIRED TO PERFORM WORK UNDER THIS DIVISION. OBTAIN PERMISSION OF THE ENGINEER, OWNER, OR BOTH, BEFORE DOING ANY CUTTING. CUT ALL HOLES AS SMALL AS POSSIBLE. PATCH WALLS, FLOORS, AND OTHER PORTIONS OF THE FACILITY AS REQUIRED BY WORK UNDER THIS DIVISION. ALL PATCHING SHALL BE THOROUGHLY FIRST CLASS AND SHALL MATCH THE ORIGINAL MATERIAL AND CONSTRUCTION, INCLUDING FIRE RATINGS IF APPLICABLE.

16A ROUGH-IN

COORDINATE WITHOUT DELAY ALL ROUGHING-IN WITH OTHER DIVISIONS. CONCEAL ALL RACEWAYS EXCEPT IN UNFINISHED AREAS AND WHERE OTHERWISE INDICATED ON THE DRAWINGS.

16A SUPPORT SYSTEMS

1. STEEL SLOTTED SUPPORT SYSTEMS (SLOTTED CHANNEL): COMPLY WITH MFMA-3, FACTORY-FABRICATED COMPONENTS FOR FIELD ASSEMBLY; 12-GAUGE, 1-5/8-INCH BY 1-5/8-INCH; COOPER B-LINE, ERICO INTERNATIONAL CORPORATION, HILTI, INC., POWER-STRUT, THOMAS & BETTS CORPORATION, UNISTRUT.

FINISHES:

1. METALLIC COATINGS: HOT-DIP GALVANIZED AFTER FABRICATION AND APPLIED ACCORDING TO MFMA-3.

FIELD FABRICATION:

WHERE FIELD CUTTING OF STANDARD LENGTHS OF CHANNEL ARE REQUIRED, MAKE CUTS STRAIGHT AND PERPENDICULAR TO MANUFACTURED SURFACES.

FOR FIELD-CUT OR DAMAGED SURFACES OF COATED CHANNELS, DRESS CUT ENDS, DAMAGED SURFACES, OR BOTH, WITH AN ABRASIVE MATERIAL (E.G., FILE, GRINDING STONE, OR SIMILAR) AND CLEANSER TO REMOVE OIL, RUST, SHARP EDGES AND SHARDS.

FOR CHANNEL WITH A FACTORY-APPLIED COATING, RE-FINISH CUT EDGES WITH A COATING COMPATIBLE WITH THE FACTORY FINISH AND AS RECOMMENDED BY THE MANUFACTURER (E.G., MANUFACTURER'S TOUCH-UP PAINT OR ZINC-RICH COLD-GALVANIZING COMPOUND, AS APPLICABLE).

16A PENETRATIONS

COORDINATE SLEEVE SELECTION AND APPLICATION WITH SELECTION AND APPLICATION OF FIRESTOPPING SPECIFIED IN DIVISION 7 SECTION "THROUGH-PENETRATION FIRESTOP SYSTEMS."

ROOFS:

COORDINATE ALL ROOF PENETRATIONS WITH ENGINEER, OWNER, AND AS APPLICABLE, THE ROOFING CONTRACTOR PROVIDING A ROOF WARRANTY.

KEEP ALL RACEWAY PENETRATIONS WITHIN MECHANICAL EQUIPMENT CURBS WHEREVER POSSIBLE. COORDINATE WITH THE MECHANICAL CONTRACTOR.

FLASH AND COUNTERFLASH ALL OPENINGS THROUGH ROOF, AND/OR PROVIDE PRE-FABRICATED MOLDED SEALS COMPATIBLE WITH THE ROOF CONSTRUCTION INSTALLED, OR AS REQUIRED BY THE ENGINEER, OWNER, OR ROOFING CONTRACTOR. ALL ROOF PENETRATIONS SHALL BE LEAKTIGHT AT THE TERMINATION OF THE WORK AND SHALL NOT VOID ANY NEW OR EXISTING ROOF WARRANTIES.

WALLS AND FLOORS:

SLEEVES FOR RACEWAYS AND CABLES

1. STEEL PIPE SLEEVES: ASTM A 53/A 53M, TYPE E, GRADE B, SCHEDULE 40, GALVANIZED STEEL, PLAIN ENDS AND DRIP RINGS.

2. CAST-IRON PIPE SLEEVES: CAST OR FABRICATED "WALL PIPE," EQUIVALENT TO DUCTILE-IRON PRESSURE PIPE, WITH PLAIN ENDS AND INTEGRAL WATERSTOP, UNLESS OTHERWISE INDICATED.

SLEEVES FOR RECTANGULAR OPENINGS: GALVANIZED SHEET STEEL WITH MINIMUM 0.138 INCH THICKNESS AND OF WIDTH AND LENGTH TO SUIT APPLICATION.

16A FIRE-STOPPING THROUGH PENETRATIONS

FIRE-RESISTANT THROUGH PENETRATION SEALANTS: TWO-PART, FOAMED-IN-PLACE, SILICONE SEALANT FORMULATED FOR USE IN THROUGH-PENETRATION FIRE-STOPPING AROUND CABLES, RACEWAYS, AND CABLE TRAY PENETRATIONS THROUGH FIRE-RATED WALLS AND FLOORS. SEALANTS AND ACCESSORIES SHALL HAVE FIRE-RESISTANCE RATINGS INDICATED, AS ESTABLISHED BY TESTING IDENTICAL ASSEMBLIES IN ACCORDANCE WITH ASTM E 814, BY UNDERWRITERS' LABORATORIES, INC., OR OTHER NRTL ACCEPTABLE TO AHJ.

ACCEPTABLE MANUFACTURERS:

HILTI, INC.
3M CORP.
RECTORSEAL.
SPECIFY TECHNOLOGY INC.
UNITED STATES GYPSUM COMPANY.

SUBMITTALS

SUBMIT PRODUCT DATA, MANUFACTURER'S SPECIFICATIONS AND TECHNICAL DATA FOR EACH MATERIAL INCLUDING THE COMPOSITION AND LIMITATIONS, DOCUMENTATION OF UL FIRESTOP SYSTEMS TO BE USED AND MANUFACTURER'S INSTALLATION INSTRUCTIONS TO COMPLY WITH DIVISION 1.

MANUFACTURER'S ENGINEERING JUDGMENT IDENTIFICATION NUMBER AND DRAWING DETAILS WHEN NO UL SYSTEM IS AVAILABLE FOR AN APPLICATION. ENGINEERING JUDGMENT SHALL INCLUDE BOTH PROJECT NAME AND CONTRACTOR'S NAME WHO WILL INSTALL FIRESTOP SYSTEM AS DESCRIBED IN DRAWINGS.

SUBMIT MATERIAL SAFETY DATA SHEETS PROVIDED WITH PRODUCT DELIVERED TO JOB-SITE.

16A EQUIPMENT FURNISHED BY OTHERS

PROVIDE NECESSARY EQUIPMENT AND ACCESSORIES THAT ARE NOT PROVIDED BY THE EQUIPMENT SUPPLIER OR OWNER TO COMPLETE INSTALLATION OF EQUIPMENT FURNISHED BY OTHERS, IN LOCATIONS AS INDICATED ON THE DRAWINGS, SPECIFIED HEREIN, OR BOTH. EQUIPMENT AND ACCESSORIES NOT PROVIDED BY THE EQUIPMENT SUPPLIER MAY INCLUDE SUCH ITEMS AS FLEXIBLE CORDS AND PLUGS, AS REQUIRED FOR PROPER OPERATION OF THE COMPLETE SYSTEM, IN ACCORDANCE WITH THE MANUFACTURERS' INSTRUCTIONS.

BE RESPONSIBLE FOR CORRECT ROUGH-IN DIMENSIONS, AND VERIFY THEM WITH ENGINEER, OWNER'S REPRESENTATIVE, EQUIPMENT SUPPLIER, OR ALL THREE, PRIOR TO ROUGH-IN AND SERVICE INSTALLATIONS.

16A CLEANING

IN ADDITION TO THE REQUIREMENTS OF DIVISION 1, REMOVE FROM THE PREMISES DIRT AND REFUSE RESULTING FROM THE PERFORMANCE OF THE ELECTRICAL WORK, AS REQUIRED, TO PREVENT ACCUMULATION. COOPERATE IN MAINTAINING REASONABLY CLEAN PREMISES AT ALL TIMES. IMMEDIATELY PRIOR TO FINAL INSPECTION, MAKE A FINAL CLEANUP OF DIRT AND REFUSE RESULTING FROM THE WORK. CLEAN ALL MATERIAL AND EQUIPMENT INSTALLED UNDER THIS DIVISION. REMOVE DIRT, DUST, PLASTER, STAINS AND FOREIGN MATTER FROM ALL SURFACES. TOUCH UP AND RESTORE ALL DAMAGED FINISHES TO THEIR ORIGINAL CONDITION.

16A ADJUSTING, ALIGNING AND TESTING

ADJUST, ALIGN, AND TEST ALL ELECTRICAL EQUIPMENT ON THIS PROJECT PROVIDED UNDER THIS DIVISION AND ALL ELECTRICAL EQUIPMENT FURNISHED BY OTHERS FOR INSTALLATION OR WIRING UNDER THIS DIVISION, FOR PROPER OPERATION.

TEST ALL SYSTEMS AND EQUIPMENT ACCORDING TO THE REQUIREMENTS IN NETA ATS (LATEST EDITION) AND ALL ADDITIONAL REQUIREMENTS SPECIFIED IN FOLLOWING SECTIONS.

MAINTAIN THE FOLLOWING ON THE PROJECT PREMISES AT ALL TIMES: A TRUE RMS READING VOLTMETER, A TRUE RMS READING AMMETER, AND A MEGOHMMETER INSULATION RESISTANCE TESTER. PROVIDE TEST DATA READINGS AS REQUESTED OR AS REQUIRED BY THE ENGINEER.

16A EQUIPMENT IDENTIFICATION

PROVIDE EQUIPMENT IDENTIFICATION NAMEPLATES:

ON ALL PANELBOARDS, SWITCHES, STARTERS, DIMMERS, SWITCHES IN DISTRIBUTION PANELBOARDS AND SWITCHBOARDS.

NAMEPLATES:

ENGRAVED, CONTRASTING COLOR, THREE-LAYER, LAMINATED PLASTIC INDICATING THE NAME OF THE EQUIPMENT, LOAD, OR CIRCUIT AS DESIGNATED ON THE DRAWINGS AND IN THE SPECIFICATIONS:

FIELD-APPLIED PERMANENT EPOXY ADHESIVE, COMPATIBLE WITH THE EQUIPMENT FINISH.

ATTACHMENT METHOD SHALL BE ACCEPTABLE TO THE MANUFACTURERS OF THE EQUIPMENT TO WHICH THE NAMEPLATES ARE BEING APPLIED.

COLOR: BLACK BACKGROUND WITH WHITE LETTERS FOR NORMAL POWER

LETTER HEIGHT: 1/2-INCH MINIMUM.

16A SYSTEM START UP

PRIOR TO STARTING UP THE ELECTRICAL SYSTEMS:

1. CHECK ALL COMPONENTS AND DEVICES.

2. LUBRICATE ITEMS ACCORDINGLY.

3. TIGHTEN SCREWS AND BOLTS FOR CONNECTORS AND TERMINALS ACCORDING TO MANUFACTURER'S PUBLISHED TORQUE-TIGHTENING VALUES. IF MANUFACTURER'S TORQUE VALUES ARE NOT INDICATED, USE THOSE SPECIFIED IN UL 486A AND UL 486B.

4. ADJUST TAPS ON EACH TRANSFORMER FOR RATED SECONDARY VOLTAGE WHEN THE TRANSFORMER IS AT MINIMUM LOAD.

5. CHECK AND RECORD BUILDING'S SERVICE ENTRANCE VOLTAGE, GROUNDING CONDITIONS, GROUNDING RESISTANCE, AND PROPER PHASING.

6. REPLACE ALL BURNED-OUT LAMPS AND LAMPS USED FOR TEMPORARY CONSTRUCTION LIGHTING IN PERMANENT LIGHT FIXTURES.

7. BALANCE ALL SINGLE-PHASE LOADS AT EACH PANELBOARD, REDISTRIBUTING BRANCH CIRCUIT CONNECTIONS UNTIL BALANCE IS ACHIEVED. DO NOT TYPE UP FINAL PANELBOARD DIRECTORIES UNTIL ALL RE-BALANCING AND REDISTRIBUTION OF CIRCUITS ARE COMPLETE. TURN ON ALL LOADS IN AN ATTEMPT TO MAXIMIZE THE LOAD ON THE PANEL AND TAKE AMPERE READINGS ON EACH OF THE PHASES BEFORE REDISTRUBITNG CIRCUITS AND BALANCING THE PANEL.

8. AFTER ALL SYSTEMS HAVE BEEN INSPECTED AND ADJUSTED, CONFIRM ALL OPERATING FEATURES REQUIRED BY THE DRAWINGS AND SPECIFICATIONS AND MAKE FINAL ADJUSTMENTS AS NECESSARY.

16A EXISTING EQUIPMENT REUSE AND REMOVAL

REMOVE ALL EXISTING WIRING, LIGHT FIXTURES, EXPOSED CONDUITS AND OTHER ELECTRICAL INSTALLATIONS NOT REUSED PRIOR TO SUBSTANTIAL COMPLETION OF THE WORK.

EXISTING RACEWAYS MAY BE REUSED IF THEIR POINTS OF TERMINATIONS ARE SUITABLE; IF THEY ARE CLEAN INSIDE WITH NO EVIDENCE OF RUST OR BURRS; IF FREE FROM CRACKS, FLATTENED SECTIONS OR SHARP BENDS; AND, IF SUITABLY LOCATED TO AVOID CONFLICTS WITH OTHER TRADES OR INSTALLATIONS. CAREFULLY "FISH" ALL EXISTING CONDUITS REUSED UNDER THIS CONTRACT TO REMOVE ALL DEBRIS AND OBSTRUCTIONS, AND SWAB UNTIL ALL MOISTURE IS REMOVED.

CUT, PATCH, AND REPAIR WHERE REQUIRED FOR NEW ELECTRICAL INSTALLATIONS, AND PATCH AND REPAIR ALL SURFACE DAMAGE RESULTING FROM THIS WORK. CUT FLUSH WITH THE FLOOR AND PLUG AT BOTH ENDS, RACEWAYS STUBBED ABOVE THE FLOOR AND NOT USED AT SUBSTANTIAL COMPLETION OF THE WORK.

RELOCATE ALL EXISTING ELECTRICAL SYSTEMS REQUIRED TO BE IN OPERATION AT SUBSTANTIAL COMPLETION OF THE CONTRACT, IF REQUIRED, AS A RESULT OF WORK INCLUDED UNDER THIS CONTRACT, EVEN IF NOT SPECIFICALLY INDICATED IN THE DRAWINGS OR SPECIFICATIONS.

EXISTING SERVICE ENTRANCE CONDUCTORS AND FEEDER CONDUCTORS MAY BE REUSED IF ALL OF THE FOLLOWING CONDITIONS ARE MET:

1. CONDUCTOR SIZES MEET OR EXCEED THE SIZES SPECIFIED ON THE DRAWINGS.

2. CONDUCTOR INSULATION IS IN GOOD OR BETTER CONDITION.

3. CONDUCTOR INSULATION IS THE CORRECT TYPE FOR THE CONDITIONS.

16A ALTERNATES

INCLUDE ALL LABOR, MATERIALS, EQUIPMENT AND SERVICES NECESSARY FOR AND INCIDENTAL TO THE COMPLETION OF ALL WORK UNDER EACH PARTICULAR ALTERNATE. FURNISH SEPARATE BIDS FOR EACH APPLICABLE ALTERNATE, STATING THE AMOUNT TO BE ADDED TO OR DEDUCTED FROM THE BASE BID FOR EACH ALTERNATE ACCEPTED. APPLICABLE SECTIONS OF THE BASE SPECIFICATIONS APPLY TO ALL WORK REQUIRED BY THE ALTERNATES UNLESS OTHERWISE SPECIFIED. REFER TO THE ARCHITECTURAL PORTION OF THE SPECIFICATIONS FOR THE LIST OF ALTERNATES.

SECTION 16B BASIC ELECTRICAL MATERIALS AND METHODS:

16B METHODS

16B1-1 RACEWAYS

METALLIC CONDUIT AND TUBING:

ELECTRICAL METALLIC TUBING, COUPLINGS AND FITTINGS (EMT): ANSI C80.3, UL 797. ONLY STEEL PRODUCTS ALLOWED. REDUCED WALL EMT IS NOT ALLOWED

FLEXIBLE METAL CONDUIT (FMC): ZINC-COATED STEEL OR ALUMINUM, UL 1. REDUCED-WALL FMC IS NOT ALLOWED

INTERMEDIATE METAL CONDUIT (IMC): HOT-DIP GALVANIZED RIGID STEEL CONDUIT: ANSI C80.6, UL 1242.

LIQUIDTIGHT FLEXIBLE METAL CONDUIT (LFMC): FLEXIBLE STEEL CONDUIT WITH PVC JACKET: UL 360

RIGID METAL CONDUIT (RMC): HOT-DIP GALVANIZED RIGID STEEL CONDUIT (GRS): ANSI C80.1, UL 6.

PLASTIC-COATED IMC, RMC, AND FITTINGS: NEMA RN 1, UL LISTED.

IMC AND RMC FITTINGS: NEMA FB 1; COMPATIBLE WITH CONDUIT TYPE AND MATERIAL, UL LISTED

NON-METALLIC CONDUIT AND TUBING:

RIGID NONMETALLIC CONDUIT (RNC): SCHEDULE 40 PVC, 90 DEG C RATED, NEMA TC- 2, UL 651; FITTINGS: NEMA TC 3, TC 6; UL 514, COMPATIBLE WITH CONDUIT/TUBING TYPE AND MATERIAL, UL LISTED. NON-METALLIC CONDUIT/TUBING IS ALLOWED BELOW SLAB ON GRADE ONLY.

16B1-2 RACEWAY INSTALLATION

ABOVE GROUND USE

INSTALL ALL CIRCULAR RACEWAYS CONCEALED ABOVE SUSPENDED CEILINGS OR CONCEALED IN WALLS OR FLOORS WHEREVER POSSIBLE EXCEPT WHERE OTHERWISE INDICATED.

PROVIDE GRS FOR ALL CONDUITS RUN EXPOSED TO WEATHER, OR EXPOSED TO OTHER HAZARDOUS CONDITIONS.

ALL OTHER RACEWAY MAY BE EMT WHERE APPROVED BY LOCAL CODE. USE COMPRESSION TYPE FITTINGS FOR EMT, WITH ALL FITTINGS UL LISTED FOR THE ENVIRONMENT IN WHICH THEY ARE USED.

EQUIPMENT CONNECTIONS

USE FMC FOR FINAL CONNECTION TO EACH MOTOR AND TRANSFORMER, AND TO ANY DEVICE THAT WOULD OTHERWISE TRANSMIT MOTION, VIBRATION, OR NOISE. USE LFMC WHERE EXPOSED TO LIQUIDS, VAPORS OR SUNLIGHT, AND TO CONNECT TO KITCHEN AND FOOD SERVICE EQUIPMENT. PROVIDE ALL FMC AND LFMC WITH AN INSULATED BONDING CONDUCTOR.

USE ONLY METAL RACEWAYS FOR ALL POWER WIRING FROM THE OUTPUT OF VARIABLE FREQUENCY DRIVES TO THEIR RESPECTIVE MOTORS.

GENERAL RACEWAY INSTALLATION REQUIREMENTS

INSTALL RACEWAYS PARALLEL AND PERPENDICULAR TO BUILDING LINES. INSTALL RACEWAYS TO REQUIREMENTS OF STRUCTURE AND TO REQUIREMENTS OF ALL OTHER WORK ON THE PROJECT; TO CLEAR ALL OPENINGS, DEPRESSIONS, PIPES, DUCTS, REINFORCING STEEL, AND OTHER IMMOVABLE OBSTACLES.

INSTALL RACEWAYS SET IN FORMS FOR CONCRETE STRUCTURE IN SUCH A MANNER THAT INSTALLATION WILL NOT AFFECT THE STRENGTH OF THE STRUCTURE.

EXCEPT WHERE APPROVED IN WRITING BY THE ENGINEER, INSTALL NO RACEWAY IN A SLAB-ON-GRADE. LOCATE RACEWAY BELOW GRANULAR FILL BELOW SLABS-ON-GRADE.

Order Plans @ www.LDILine.com

engineering consultants
9225 Indian Creek Pkwy., Suite 1075 | Overland Park, KS 66210
T: 913.322.1400 : www.rtmassociates.com
GEORGIA COA #: PEF006838

hckloverarchitect
8813 PENROSE LANE, SUITE 400 • LENEXA, KS 66219
ph: 913.649.8181 • fx: 913.649.1275 • www.klover.net

THIS DRAWING has been prepared by the Architect, or prepared under his direct supervision as an instrument of service and is intended for use only on this project. All Drawings, Specifications, ideas and designs, including the overall layout, form, arrangement, and composition of spaces and elements portrayed, constitute the original, unpublished Work of the Architect. Any reproduction, use, or disclosure of the information contained herein without the written consent of the Architect is strictly prohibited

© 2019 H.C. KLOVER ARCHITECT

THE ARCHITECT DISCLAIMS responsibility for the existing building structure, site conditions, existing construction elements, or any documents, drawings or other instruments used for any part of this Project which do not bear the Architect's seal. The Architect's services are undertaken only in the interest of the Project Owner. No obligation is assumed by the Architect for the benefit of any other entity.

RELATED DOCUMENTS: This Drawing is a single component of an integrated set of Construction Documents. General and Supplementary Conditions of the Contract, General Requirements, Specifications and other Drawings may affect the Work described. Failure to review and integrate the design intent of the whole of the Construction Documents does not relieve the Contractor from providing a complete Project.

COMPLY WITH all laws, codes, ordinances and regulations with authorities having jurisdiction and with requirements of the landlord, if applicable. Do not start Work until all permits and required approvals are obtained.

VERIFY ACTUAL CONDITIONS and dimensions prior to construction. Commencement of work constitutes verification and acceptance of all existing conditions. Application of a material or equipment item to Work installed by others constitutes acceptance of that Work, and assumption of responsibility for satisfactory installation.

DIMENSIONS SHOWN are to finish face of a material unless otherwise indicated.

CONTRACTOR'S NOTES: Written dimensions hold preference over scaled dimensions. Do not scale the drawings. The contractors must visit job site to verify all existing conditions and dimensions before submitting bids. Report any discrepancies of any conditions which may interfere with the proper execution of the contract to the tenant's representative. Report discrepancies during bidding process and before start of construction. Change orders will not be approved for issues arising from the field conditions or conflicts between the plans and the existing conditions.

project title

HELZBERG DIAMONDS
STORE 211, NG-M
MALL OF GEORGIA
3333 BUFORD DR, 2070C
BUFORD, GEORGIA 30519

project number
19007.019

drawing issuance
OWNER/PERMIT/BID 1.7.20

drawing revisions

△	Date:	Description:

professional seal

GEORGIA REGISTERED No. PE 037207 PROFESSIONAL ENGINEER JENNIFER LUCE
1-9-2020
Exp 12/31/2020

drawing title
ELECTRICAL SPECIFICATIONS

drawing number
E500

1/9/2020 11:51:52 AM
C:\Revit\Revit 2019 Projects\HBBG_2019_paul.hough.rvt