



**FLOOR FRAMING NOTES:**


- INDICATES 16" DEEP OPEN WEB TRUSSES SPACED 24" o.c. MAXIMUM IN UNITS UNLESS NOTED OTHERWISE. TRUSS LAYOUT IS FOR SCHEMATIC PURPOSES ONLY, AND TRUSS SHOP DRAWINGS SHOULD REFERENCED FOR LOCATION OF TRUSSES. TRUSSES TO ALIGN AT ALL FLOORS. TRUSS DESIGNER SHALL COORDINATE TRUSS SPACING WITH FIXTURE LOCATIONS PER PLUMBING DRAWING AND MECHANICAL CLOSETS PER MECHANICAL DRAWINGS. TOPPING TO BE 1" MAXIMUM GYPCRETE.
- PROVIDE A MINIMUM OF (2) STUDS (MATCH TYPICAL WALL STUD SPECIES AND GRADE) AT EACH END OF BEAMS UNLESS NOTED OTHERWISE. LJK MINIMUM EACH END OF HEADERS, UNLESS NOTED OTHERWISE.
- REFER TO ARCHITECTURAL AND MECHANICAL PLANS FOR FLOOR PENINS.
- REFER TO S1.0.0 FOR ADDITIONAL STRUCTURAL NOTES.
- INDICATES LOAD BEARING STUD WALL. WALLS NOT SHOWN SOLID ARE NOT TO BE USED FOR BEARING. REFER TO WALL SCHEDULES FOR STUD GRADE AND BEARING.
- INDICATES 2x8 PRESSURE TREATED JOISTS SPACED 16" o.c. MAXIMUM AT UNIT BALCONIES, UNLESS NOTED OTHERWISE IN PLANS. BALCONIES TO HAVE SLOPED (2" MAXIMUM) CONCRETE TOPPING.
- INDICATES 14" OPEN WEB TRUSSES @ 24" o.c. MAXIMUM AT BREEZEWAYS UNLESS NOTED OTHERWISE. BREEZEWAY STUDS TO BEAR DIRECTLY ON UNIT WALLS. TOPPING TO BE 1" MAXIMUM GYPCRETE.
- FLOOR FRAMING PER NOTE 9 OF HORIZONTAL AND UPLIFT LOAD SYSTEM NOTES' ON SHEET S1.0.2.
- REFER TO SHEARWALL PLANS FOR SHEARWALL LOCATIONS, AND SHEARWALL SCHEDULE FOR REQUIREMENTS.
- REFER TO ARCHITECTURAL DRAWINGS TO CONFIRM LOCATION OF ACCESSIBLE UNITS.
- STEEL STAIRS AND LANDINGS BY STEEL SUPPLIER, PER NOTES ON SHEET S1.0.0.
- DRAWING DESIGNATION BELOW UNIT TYPE INDICATES UNIT FLOOR FRAMING PLAN. UNITS SHOWN ON STRUCTURAL PLANS OCCUR BELOW FLOOR INDICATED IN SHEET TITLE.

**WOOD BEAM/HEADER SCHEDULE \*\***

MARK	MEMBER***	MARK	MEMBER***	MARK	MEMBER***
2-6	(2) 2x6*	2-7L	(2) 1 3/4"x1 1/4" LVL	35-8P	3 1/2"x4 1/4" PSL
2-8	(2) 2x8*	2-7R	(2) 1 3/4"x1 1/4" LVL	35-11P	3 1/2"x11 1/4" PSL
2-10	(2) 2x10*	2-11L	(2) 1 3/4"x1 1/4" LVL	35-12P	3 1/2"x11 7/8" PSL
2-12	(2) 2x12*	2-12L	(2) 1 3/4"x1 7/8" LVL	35-14P	3 1/2"x14" PSL
		2-14L	(2) 1 3/4"x1 1/4" LVL	35-16P	3 1/2"x16" PSL
3-6	(3) 2x6*	2-16L	(2) 1 3/4"x16" LVL	35-18P	3 1/2"x18" PSL
3-8	(3) 2x8*	2-18L	(2) 1 3/4"x18" LVL		
3-10	(3) 2x10*			5-9P	5 1/4"x4 1/4" PSL
3-12	(3) 2x12*			5-11P	5 1/4"x11 1/4" PSL
		3-7L	(3) 1 3/4"x1 1/4" LVL	5-12P	5 1/4"x11 7/8" PSL
		3-7R	(3) 1 3/4"x1 1/4" LVL	5-14P	5 1/4"x14" PSL
4-6	(4) 2x6*	3-12L	(3) 1 3/4"x1 7/8" LVL	5-16P	5 1/4"x16" PSL
4-8	(4) 2x8*	3-14L	(3) 1 3/4"x1 1/4" LVL	5-18P	5 1/4"x18" PSL
4-10	(4) 2x10*	3-16L	(3) 1 3/4"x16" LVL		
4-12	(4) 2x12*	3-18L	(3) 1 3/4"x18" LVL		
				7-4P	7"x4 1/4" PSL
		(2) SF - INDICATES (2) 1/2" STEEL FLITCH PLATES WITH 1/2" THROUGH-BOLTS @ 12" o.c. STAGGERED REFER TO 9.51.2.4 FOR FLITCH PLATE DETAIL.		7-11P	7"x11 1/4" PSL
				7-12P	7"x11 7/8" PSL
				7-14P	7"x14" PSL
				7-16P	7"x16" PSL
				7-18P	7"x18" PSL

\* PROVIDE 1/2" PLYWOOD BETWEEN FLIES AT INTERIOR CONDITIONS  
 \*\* REFER TO NOTE 9 OF 'WOOD FRAMING NOTES' ON SHEET S1.0.0 FOR HANGERS TO BE USED IF NOT SPECIFIED ON FRAMING PLANS OR IN FRAMING NOTES. (PLEASE NOTE THAT SOME BEAM TYPES MAY NOT BE SPECIFIED IN THIS PROJECT.)  
 \*\*\* MEMBERS SHOWN DASHED ON FRAMING PLANS TO BE DROPPED BELOW FLOOR CAVITY. MEMBERS SHOWN SOLID ON FRAMING PLANS TO BE WITHIN FLOOR CAVITY UNLESS NOTED OTHERWISE.

**PARTIAL FLOOR FRAMING PLAN - BUILDING #3 - 347.13'**  
 SCALE: 1/8" = 1'-0"



**CRABTREE NORTH APTS.**  
 2251 Charles Drive  
 Raleigh, North Carolina  
 EYC COMPANIES

**03FEB20 PRICING SET**

PROJECT 1015  
 DATE 06NOV19  
 DRAWN BY SCG  
 CHECKED BY F80

PARTIAL FLOOR FRAMING PLAN - BUILDING #3 - 347.13'

**S3.5.3**