


PLANT LIST						
TREE	SYM	BOTANICAL NAME	COMMON NAME	SIZE (min)***	ROOT**	REMARKS
SHRUBS, SMALL TREES AND GRASSES:						
1	SM	<i>Abies balsamea</i> (Mill.) B.S.P.	Little Richard Spruce	22'-ft.	3 GAL	
2	CS	<i>Camellia sasanqua</i>	Camellia	30'-ft.	5 GAL	
3	IC	<i>Ilex cornuta</i> (L.) Dur.	Evergreen Holly	18'-ft.	3 GAL	
4	RS	<i>Rosa glauca</i>	Wild Rose	18'-ft.	3 GAL	
5	IV	<i>Ilex vomitoria</i> (L.) Mill.	Wintergreen Holly	18'-ft.	3 GAL	
6	LC	<i>Lonicera chrysantha</i> Pursh	Chrysantha Honeysuckle	18'-ft.	3 GAL	
7	PA	<i>Panicum capillare</i> (L.) Vahl	Common Panicum	18'-ft.	3 GAL	
8	GM	<i>Spirea japonica</i> (L.) Thunb.	Japanese Spirea	18'-ft.	3 GAL	
TREE						
9	SM	<i>Thuja occidentalis</i> (L.) Mill.	Eastern White Pine	SOD		

- LANDSCAPE NOTES:**
- ALL TECHNICAL SPECIFICATIONS AND GENERAL CONDITIONS APPLY. ALL GENERAL NOTES AND GENERAL CONSTRUCTION NOTES APPLY.
 - THE CONTRACTOR IS RESPONSIBLE FOR ALL QUANTITY TAKE-OFFS AND VERIFICATION OF MATERIALS AS SHOWN ON THESE PLANS AND IN WRITTEN SPECIFICATIONS. THE CONTRACTOR SHALL NOTIFY THE LANDSCAPE ARCHITECT OF ANY DISCREPANCIES PRIOR TO FINAL BIDDING OR INSTALLATION.
 - THE CONTRACTOR SHALL VERIFY LOCATIONS OF EXISTING AND PROPOSED UNDERGROUND UTILITIES PRIOR TO THE INSTALLATION OF ANY PLANT MATERIAL.
 - ALL LANDSCAPE MATERIALS SHALL CONFORM TO THE ACCEPTED STANDARDS ESTABLISHED BY THE AMERICAN ASSOCIATION OF NURSERYMEN.
 - PRIOR TO THE END OF EACH WORKING DAY, THE CONTRACTOR SHALL PROPERLY BACKFILL ALL PLANT MATERIAL THAT HAS BEEN PLACED IN PREPARED HOLES, AND PROPERLY WATER AND MULCH ALL PREPARED GROUNDCOVER, PERENNIAL AND ANNUAL BEDS.
 - ALL TREES AND SHRUBS SHALL BE SOAKED WITH WATER AND MULCHED IMMEDIATELY FOLLOWING INSTALLATION.
 - LANDSCAPE ARCHITECT OR OWNER SHALL APPROVE ANY ON-SITE PLANT STORAGE AREA.
 - ALL ROOT BALLS REMOVED FROM CONTAINERS SHALL BE SCARIFIED BY HAND PRIOR TO PLACEMENT AND BACK FILLING WITH PREPARED SOILS. HAND TOOLS ARE NOT TO BE USED TO SCARIFY ROOT BALLS.
 - ALL ROPE AND WRAPPING TWINE SHALL BE CUT AND REMOVED FROM AROUND THE UPPER PARTS OF THE ROOT BALL. METAL BASKET WIRES AND BURLAP SHALL BE PULLED BACK AND TUCKED UNDER THE EDGES OF THE SAUCER RINGS ON ALL TREES AND LARGE SHRUBS. ALL SYNTHETIC BURLAP SHALL BE REMOVED FROM PLANT BALLS PRIOR TO BACKFILLING.
 - ALL PLANTING AREAS SHALL BE EDGED WITH SMOOTH, CONTINUOUS CURVES.
 - ALL PLANT MATERIAL SHALL BE PLANTED AT HEIGHTS AS SPECIFIED IN THE PLANTING DETAILS & PLANT LIST. CONTAINER SIZES PROVIDED FOR REFERENCE ONLY.
 - TREE STAKING AND GUYING, IF NECESSARY, SHALL BE PERFORMED WITHIN A WEEK OF PLANTING. THE LANDSCAPE CONTRACTOR SHALL BE RESPONSIBLE FOR REMOVING ALL TREE STAKING MATERIAL AFTER THE FIRST FULL GROWING SEASON OR ONE YEAR, WHICHEVER COMES FIRST.
 - B & B AS LISTED UNDER "ROOT" IN THE PLANT LIST INDICATES BALLED AND BURLAPPED.
 - ALL PLANT BEDS AND RAISED SAUCER RINGS SHALL BE GRADED TO PROVIDE ADEQUATE DRAINAGE AND SHALL BE MULCHED AS SPECIFIED.
 - ALL MATERIALS, PLANTING AND LANDSCAPE WORK SHALL CONFORM TO THE LOCAL OR COUNTY JURISDICTIONAL AUTHORITY'S STANDARD SPECIFICATIONS AND DETAILS.

Order Plans @



NO.	REVISIONS	DATE	PER CITY COMMENTS
1		01/17/2020	

PROJECT: STATE EMPLOYEES' CREDIT UNION - CHARLOTTE ALBEMARLE RD REMOTE ATM ADDITIONS
SHEET TITLE: LANDSCAPE PLAN
PROJECT MANAGER: MTA
CHECKED BY: DM
DRAWN BY: AN
FIELD SURVEY DATE: -
DRAWING DATE: 11/26/2019
JOB #: SE19.070
SHEET: L-10